



This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:


- + *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.
- + *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.
- + *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.
- + *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at <http://books.google.com/>

Shelf

HARVARD UNIVERSITY



LIBRARY

OF THE

MUSEUM OF AMERICAN
ETHNOLOGY AND ETHNOLOGY


GIFT OF


HENRY W. HAYNES

(Class of 1851)

OF BOSTON

June 5, 1912.





MANUAL
OF
ORIENTAL ANTIQUITIES



MANUAL
OF
ORIENTAL ANTIQUITIES

INCLUDING THE

Architecture, Sculpture, and Industrial Arts

OF

*CHALDÆA, ASSYRIA, PERSIA, SYRIA, JUDÆA,
PHŒNICIA, AND CARTHAGE.*

BY

ERNEST BABELON,

*Librarian of the Department of Medals and Antiques in the
Bibliothèque Nationale, Paris.*

NEW EDITION,

WITH A CHAPTER ON THE RECENT DISCOVERIES AT SUSÁ.

With Two Hundred and Fifty-five Illustrations.

LONDON :

H. GREVEL AND CO.,

33, KING STREET, COVENT GARDEN, W.C.

1906.

H.D. AS. B 11 m E

Gift of
Henry W. Haynes
Rec. June 5, 1912.

PREFACE.

THE domain which we are about to traverse in this little work embraces all the civilisations of the ancient East except that of Egypt. It includes the Chaldæans, the Assyrians, the Persians before Alexander, the Hittites of Syria, Cappadocia, and Asia Minor, the Jews, the Phœnicians, and even Cyprus, ending with the Carthaginians and their colonies. So vast a field, which, in the monumental work of MM. G. Perrot and C. Chipiez, occupies four volumes, can only be explored here in a summary manner, and the author claims no more than to have written a modest abridgment. It must not be supposed, however, in spite of the diversity and remoteness from one another of the peoples that we have just enumerated, that the subject lacks cohesion and unity. If the reader will have the goodness to follow us to the conclusion, he will be, on the con-

trary, struck by the perfect homogeneity of the book and the connection of all its parts. The picture, so to speak, contains many figures, but all concur in a common action, and the spectator grasps, at the first glance, the harmony of the composition.

For, in these old Eastern civilisations which held sway over the world before Greece and Rome, only two streams of artistic influence are really to be traced—that which rises in Egypt and that which issues from Assyria. Often they took a parallel course, side by side, sharing like brothers the empire of the arts; sometimes they opposed or obstinately excluded one another; or else they joined forces, mingled closely with one another, and united their original capacities in a common fund. But if these varying conditions produced in certain countries a local and indigenous art which is neither purely Egyptian nor purely Assyrian, we can always decompose its elements and make a chemical analysis of it, so to speak; and, when we have restored to Egypt that which properly belongs to her, and to Assyria all that has been borrowed from her, we perceive that nothing remains at the bottom

of the crucible. Thus it may be said that, properly speaking, there is no Persian art, or Hittite art, or Jewish art, or Phœnician or Carthaginian art; everywhere we find the forms of Egypt or those of Assyria grouped, mixed, perhaps altered, in proportions which vary according to time, environment, and political conditions.

Leaving Egypt on one side, it is the Asiatic, or, more strictly, the Chaldæo-Assyrian stream that we have undertaken to study exclusively. We see it at its source, almost on the site of that Garden of Eden where Genesis and the Chaldæan legends place the ancestors of mankind; we follow it into Assyria, and observe its progress and transformations. Before long it overflows and passes on all sides beyond the limits of the basin of the Tigris and Euphrates; on one side, in Persia, it invades the palaces of Susa and Persepolis; on the other side, among the Hittites, the Aramæan populations of Syria, and the Jews, it spreads and divides into many rivulets, until it arrives at the frontier of Egypt and the heart of Asia Minor. Far from losing itself in the waves of the Mediterranean, it reaches all the shores of that great lake, Cyprus,

Sicily, Africa, Spain ; even passing beyond the Pillars of Hercules.

It seemed to us, then, that it would be a work of interest to draw a picture of Chaldæo-Assyrian art not only in its native country where it develops at its ease, but in its many ramifications among the neighbouring nations where it comes into collision with its rival and is interpreted by foreigners, until the day when Greece snatches the torch of the arts from the failing hand of the East. This Asiatic art, as we shall see, has no cause to be ashamed by the side of the Egyptian art. Chaldæa possesses a genius as spontaneous as that of Egypt, and the valley of the Euphrates is not less fertile than that of the Nile. The ambitions of her architects and sculptors were as high and noble as those of the artists who flourished at the court of the Pharaohs, and the staged towers were the equals of the Pyramids. Both nations pursued an ideal which contains a part of the truth, for in making a building colossal and imposing by its size, they thought that they attained to supreme greatness and perfection. The Greeks, through their greater refinement, did not fall into these

excesses. But who will ever be able to say how much the powerful originality of the Hellenic genius borrowed from the imperfect models furnished by Egypt and Assyria? Who will ever be able to define with clearness and precision the kind of influence which Chaldæo-Assyrian art, in particular, imported by the ships of Phœnicia into all maritime countries, had on the origin of art in that younger civilisation of which Athens was the centre?

The ancient peoples of Asia, which form a compact group from the point of view of the history and development of the arts, are also akin in the complete destruction which has overtaken their architectural monuments. As if by a providential chastisement, from the table-land of Iran to the Pillars of Hercules, at Susa, at Babylon, at Nineveh, as at Jerusalem, Tyre, Carthage, and Gades, nothing is left of those temples, palaces, and towers which threw a challenge in the face of Heaven, and which wore out so many generations of slaves in the building of them. While the Pyramids still rise opposite to the Parthenon, and our astonishment is still excited by the imposing ruins

of Egypt, Greece and Rome, nothing remains of the grand monuments which were the pride of the capitals of Asia. Everywhere we have to dig into the bowels of the earth and uncover the base of crumbled walls. Everything is reduced to dust like the image with the feet of clay, and a shroud of ashes covers that world the material culture of which is to be brought to life again, as far as possible, in the following pages.

In the first English edition, M. Babelon's work was somewhat enlarged, and occasionally revised by the translator—Mr. B. T. A. Evetts, then of the Department of Egyptian and Assyrian Antiquities, British Museum. In the present edition will be found a new chapter by the author on the recent finds at Susa.

A. S. G.

TABLE OF CONTENTS.

CHAPTER I.

CHALDÆAN ART.

	PAGE
§ 1. ARCHITECTURE	3
§ 2. STATUES AND BAS-RELIEFS	22
§ 3. MINOR SCULPTURE AND THE INDUSTRIAL ARTS	35
§ 4. ENGRAVED SEALS	44

CHAPTER II.

ASSYRIAN ARCHITECTURE.

§ 1. THE PRINCIPLES OF BUILDING	52
§ 2. PALACES	66
§ 3. TEMPLES AND STAGED TOWERS	72
§ 4. TOWNS AND THEIR FORTIFICATIONS	79

CHAPTER III.

ASSYRIAN SCULPTURE AND PAINTING.

§ 1. STATUES, STELE, OBELISES	85
§ 2. BAS-RELIEFS	91
§ 3. PAINTING AND ENAMELLING	114

CHAPTER IV.

THE INDUSTRIAL ARTS IN ASSYRIA.

§ 1. CERAMICS	121
§ 2. METALS	125
§ 3. WOOD AND IVORY	134
§ 4. LEATHER AND TEXTILES	138
§ 5. ORNAMENTS AND SEALS	142

CHAPTER V.

PERSIAN ART.

	PAGE
§ 1. CIVIL ARCHITECTURE	147
§ 2. SCULPTURE	159
§ 3. PAINTING AND ENAMELLING	167
§ 4. RELIGIOUS AND SEPULCHRAL MONUMENTS	172
§ 5. ENGRAVED STONES AND ORNAMENTS	180

CHAPTER VI.

THE HITTITES.

§ 1. HITTITE MONUMENTS IN SYRIA	186
§ 2. HITTITE MONUMENTS IN CAPPADOCIA	191
§ 3. HITTITE MONUMENTS IN ASIA MINOR	199

CHAPTER VII.

JEWISH ART.

§ 1. THE TEMPLE OF JERUSALEM	205
§ 2. THE DECORATION AND FURNITURE OF THE TEMPLE	223
§ 3. CIVIL ARCHITECTURE	230
§ 4. TOMBS	233

CHAPTER VIII.

THE ART OF PHŒNICIA AND CYPRUS.

§ 1. TEMPLES	239
§ 2. CIVIL ARCHITECTURE	246
§ 3. TOMBS	253
§ 4. PHŒNICIAN SCULPTURE	262
§ 5. CYPRIOTE SCULPTURE	269
§ 6. PHŒNICIAN AND CYPRIOTE POTTERY	277
§ 7. PHŒNICIAN GLASS	283
§ 8. BRONZES AND ORNAMENTS	288
§ 9. ENGRAVED STONES	294

CHAPTER IX.

ARCHÆOLOGICAL DISCOVERIES AT SUSIA.

§ 1. M. DE MORGAN'S MISSION IN SUSIANA	299
§ 2. CHRONOLOGY OF THE RUINS ACCORDING TO RECENT DISCOVERIES	303
§ 3. THE PRINCIPLES OF BUILDING	313
§ 4. STONE SCULPTURE	316
§ 5. BRONZE METAL-WORK	326
§ 6. JEWELLERY AND THE INDUSTRIAL ARTS	331

LIST OF ILLUSTRATIONS.

FIGURE	PAGE
1. Brick from Tello	5
2. Plan of the palace at Tello	9
3. Section of pillar	10
4. Corbelled vaulting at Mugheir	14
5. Socket for pivot of door from Tello	18
6. Terra-cotta cone from Tello	18
7. Drainage pipe at Mugheir	20
8. Foundation cylinder from Khorsabad	22
9. Bas-relief from Tello	23
10. Bas-relief from Tello	24
11. The Vulture Stela	25
12. The Vulture Stela	25
13. The Vulture Stela	26
14. Chaldæan head	27
15. Chaldæan head	27
16. Chaldæan statue	28
17. Chaldæan statue	29
18. Foot of Chaldæan vase	31
19. Bas-relief from Tello	32
20. Bas-relief from Tello	32
21. The "Caillou Michaux"	34
22. Stela of Marduk-nadin-akhi	34
23. Chaldæan statuette in bronze	35
24. Chaldæan statuette	36
25. Canephoros of Kudurmapuk	37
26. Chaldæan statuette in bronze	38
27. Chaldæan statuette in terra-cotta	40
28. Chaldæan statuette in alabaster	42
29. Bas-relief on the tablet of the god Samas	42

FIGURE	PAGE
30. Chaldæan head in steatite	43
31. Chaldæan cylinder	45
32. Chaldæan cylinder	46
33. Chaldæan cylinder	46
34. Cylinder of Sargani	47
35. Chaldæan cylinder	48
36. Tomb at Warka	51
37. Masonry at Khorsabad	53
38. Section of wall at Khorsabad.	53
39. Vaulted and domed houses	56
40. Vaulted drain	57
41. Vaulted drain at Khorsabad	58
42. Vaulted drain at Khorsabad. Slope of the bricks	59
43. Façade with pilasters	62
44. Base of column	62
45. Assyrian capital	63
46. Capital of Sassanian period from Warka	63
47. Shrine with columns	64
48. Base of small column	65
49. Plan of Dur-Sarrukin	67
50. Plan of the palace of Sargon	68
51. South-eastern façade of the palace of Sargon	69
52. Birds'-eye view of the palace of Sargon	71
53. The staged tower of Khorsabad	75
54. Temple of the god Haldia	77
55. Walls of Babylon	80
56. Chaldæan plan of a fortress	81
57. Assyrian plan of a fortress	82
58. Siege of a fortress	83
59. Plan of a gate at Khorsabad	84
60. Gate of Khorsabad	84
61. Statue of Assur-nasir-pal	86
62. Statue in the hareem at Khorsabad	87
63. Stela of Samsi-Rammanu	88
64. Stela of Assurbanipal	89
65. Obelisk of Shalmaneser	89
66. Assur-nasir-pal sacrificing a bull	91
67. Genius with the beak of an eagle	92
68. Two-winged genius	92
69. Four-winged genius, Khorsabad	93
70. Winged and human-headed lion	94

FIGURE	PAGE
71. Front face of a winged bull	95
72. Battle scene	96
73. The Assyrian army in a mountainous country	97
74. Siege of a fortress	98
75. Navigation scene	99
76. Eunuchs	101
77. Assurbanipal and his queen	102
78. Jewish type from a bas-relief from the palace of Sennacherib	103
79. Assurbanipal in his chariot	104
80. Sargon	105
81. Wounded lioness	107
82. Slaves carrying a lion and birds. Bas-relief	108
83. Envoy bringing apes as tribute	109
84. Fragment of threshold, Kouyunjik	111
85. Slaves dragging a winged bull	112
86. Deer-hunt. Bas-relief	113
87. Painting on plaster, Nimroud	115
88. Portion of an enamelled archivolt at Khorsabad	116
89. Enamelled brick, Nimroud	117
90. Izdubar. Terra-cotta	122
91. Head of a monster. Terra-cotta	122
92. Tablet with figure of boar in relief	123
93. The Divine Mother. Terra-cotta	124
94. Istar. Terra-cotta	124
95. Gates of Balawat	126
96. Fragment of metal band of Balawat gates	127
97. Bronze dish, Nimroud	128
98. Assyrian archers	128
99. Various forms of the Assyrian helmet	128
100. Bronze lion	129
101. Bronze siren	129
102. Bronze siren	130
103. The demon of the south-west wind	130
104. Bronze plaque	131
105. Bronze plaque	132
106. Standard in a bas-relief from Khorsabad	133
107. Foot of a piece of furniture	133
108. Tent serving as the royal stable	136
109. Sennacherib's throne. Bas-relief	136
110. Assyrian chariot	137
111. Ivory plaque	137

FIGURE	PAGE
112. Assur-nasir-pal offering a libation	139
113. Richly caparisoned horse and rider	140
114. Assyrian deities carried in procession	142
115. Archaic Assyrian cylinder	144
116. Assyrian cylinder	145
117. Assyrian cylinder	145
118. Assyrian cylinder	145
119. Median cylinder	146
120. Platform of the palace of Cyrus	149
121. Basement at Persepolis	150
122. Gate and windows of the palace of Darius	151
123. Persepolitan capital	153
124. Plan of the Apadana of Artaxerxes	154
125. Susian capital restored	155
126. Base of a column	156
127. Façade of the Apadana of Artaxerxes	157
128. Cyrus. Bas-relief	160
129. Bas-relief at Persepolis	161
130. Bas-relief at Persepolis	162
131. Bas-relief from Persepolis	163
132. Bas-relief at Persepolis	164
133. Bas-relief at Persepolis	165
134. Portico at Persepolis	166
135. The lion frieze	168
136. Susian archer	169
137. Polychrome decoration of the palace of Artaxerxes	171
138. The tower of Jur. Restoration	173
139. The Gabr-i-Madar-i-Soleiman	176
140. Tomb of Cambyses I.	177
141. Façade of tomb at Nakhsh-i-Rustam	178
142. Cylinder of Darius	181
143. Persian cylinder	182
144. Persian seal	182
145. Seal of Artaxerxes	182
146. Persian seal. Conical	182
147. Persian seal	183
148. De Luynes' bas-relief	184
149. The lion of Marash	186
150. Stela from Birejik	187
151. Fragments of sculpture from Carchemish	188
152. Bas-relief at Rum-Qalah	189

FIGURE	PAGE
153. Stela at Marash	189
154. The sphinx of Euyuk	192
155. Rock sculptures at Iasili-Kafa	193
156. Rock sculptures at Iasili-Kafa	194
157. Rock sculptures at Iasili-Kafa	194
158. Rock sculpture at Iasili-Kafa	195
159. Rock sculpture of Iasili-Kafa	195
160. Rock sculpture of Iasili-Kafa	196
161. Tomb of Gherdek-Kafasi	196
162. Sculpture at Iasili-Kafa	198
163. Rock sculptures at Ghiaur Kalesi	199
164. Rock sculpture at Ibriz	200
165. Rock sculpture at Nymphio	201
166. Boss of Tarkudimme	203
167. Hittite cylinder	203
168. Site of the Temple on Mount Moriah	206
169. Plan of Herod's restoration	211
170. The Jews' Wailing-place	213
171. The western door. Present state	215
172. Interior view of the Double Gate	216
173. Plan of Herod's Temple	218
174. Bird's-eye view of Herod's Temple	219
175. The Altar of Burnt-offerings	221
176. Egyptian naos and cherubim	225
177. Egyptian ark and naos	225
178. Egyptian table of offerings	226
179. Seven-branched candlestick	226
180. Capital of the bronze columns	227
181. The brazen sea	228
182. Movable basin	229
183. The tomb of Abraham at Hebron	233
184. Absalom's tomb	234
185. Sepulchral chamber at Medaïn Salih	235
186. The monolith of Siloam	236
187. Tomb in the valley of Hinnom	237
188. Shrine at Ain el-Hayât	240
189. Coin of Paphos	241
190. Plan of the Giganteja	244
191. Roman wall at Byrsa	245
192. Terra-cotta house	248
193. Plan of the harbours at Carthage	250

FIGURE	PAGE
194. Jetty of Thapsus	252
195. Tomb at Amrith. Plan	253
196. Tomb at Amrith. Section	253
197. Sepulchral chamber at Amrith	254
198. Mighzal at Amrith	254
199. The Burj el-Bezzak	255
200. Chamber of the Burj el-Bezzak	255
201. The Burj el-Bezzak. Restoration	255
202. Section of a tomb at Saïda	256
203. Entrance of a tomb at Gebal	256
204. The sarcophagus of Eshmunazar	257
205. Sarcophagus in human form	258
206. Tomb at Amathus	260
207. Sepulchral chamber at Amathus	260
208. Plan of a tomb at Carthage	261
209. Phœnician slab at Amrith	263
210. Cypriote statue	265
211. Votive stela from Carthage	266
212. Stela from Lilybæum	267
213. Stela of Hadrumetum	268
214. Colossal head from Athieno	270
215. The colossus of Amathus	272
216. The priest with the dove	273
217. Bas-relief of Heracles and Eurytion	274
218. Sarcophagus from Amathus	275
219. Phœnician chariot in terra-cotta	277
220. Pygmy in terra-cotta	278
221. Pygmy in terra-cotta	278
222. Terra-cotta head from sarcophagus	279
223. Astarte. Phœnician terra-cotta	279
224. Terra-cotta from Cyprus	280
225. Cypriote terra-cotta	280
226. Cypriote terra-cotta	281
227. Cypriote terra-cotta	281
228. Mask from Carthage	282
229. Terra-cotta mask from Carthage	282
230. Transparent glass vase bearing name of Sargon	285
231. Phœnician glass	285
232. Glass vase from Jerusalem	285
233. Patera from Paestrina	285
234. Dish from Dali	285

LIST OF ILLUSTRATIONS.

xix

FIGURE	PAGE
235. Handle of a bronze crater	291
236. Phœnician gold ornament	292
237. Phœnician earrings	293
238. Cylinder in the De Clercq collection	294
239. Cylinder in the British Museum	295
240. Scarabœoid seal	297
241. Scarabœoid seal	297
242. Bone cylinder, showing the earliest stage of cuneiform writing	305
243. Fragment of an Elamite tablet inscribed with arithmetical calculations	306
244. Cylinder showing giants, lions, and bulls, glazed pottery	307
245. Brick Column. Susa	315
246. Triumphal stela of Naram-Sin	318
247. Fragment of bas-relief representing figure of Negrito type .	323
248. Stela of Hammurabi, on which his code of laws is engraved	324
249. Kudurru (unfinished), Kassite period	325
250. Bronze bas-relief fragment	328
251. Bronze statuette. Temple of Shushinak	331
252. Gold and silver statuettes	332
253. Silver mask. Elamite period	333
254. Headdress. Elamite period	334
255. Figure of a woman, ivory	335

ORIENTAL ANTIQUITIES.

CHAPTER I.

CHALDÆAN ART.

THE extensive region of Western Asia to which the Greeks gave the name of Mesopotamia was already, at the period which lies farthest back among the memories of mankind, the centre of a mighty civilisation rivalling that of Egypt, and disputing with the latter the glory of having formed the cradle of the arts in the ancient East. Babylon and Nineveh were by turns, according to the course of political events, the intellectual hearth at which the bold and original genius was kindled, which marks the artistic productions of Chaldæa and Assyria, and the reflection of which is shown in the monuments of Persia, Judæa, Phœnicia, and Carthage, the island of Cyprus, and the Hittite races. Yet it is neither in the capital of Chaldæa nor in that of Assyria that the oldest traces have hitherto been found of this great civilisation, extinct now for twenty-four centuries; it is not among the ruins of these famous cities that we can hear, as it were, an echo of the first wailings of the genius of plastic art, observe its groping efforts, touch with our finger its rudest attempts. In the country, formerly so fertile, called Lower Chaldæa, where, according to

the popular tradition preserved by Berosus, the fish-god Oannes taught men in the beginning "all that serves to soften life," the traveller comes, almost at every step, upon artificial mounds known as *tells*, concealing under a veil of dust the remains of cities which yield in point of antiquity neither to Babylon nor Nineveh; and it is there that modern archæologists have had the good fortune to disinter ruins far more ancient than those of the palaces of Sargon, Assurbânipal, or Nebuchadnezzar. Though a number of tumuli remain unexplored, and, as we may conjecture, future excavations will afford much new matter for science, nevertheless a brilliant light has already been thrown by numerous and important discoveries on the oriental origin of art and on the degree of material culture reached by the nation which founded Babel and the other Chaldæan towns of Genesis. The ruins of Abu Habbah, identified with the two Sipparas (Sepharvaim, that of the god Samas and that of the goddess Anunit), have yielded to our curiosity several monuments of the highest interest; those of Abu Shahrein (Eridu), Senkereh (Larsa), Mugheir (Ur, the native city of Abraham), the great necropolis of Warka (Uruk, the Erech of the Bible), are sites which have all furnished already an important harvest of remains belonging to the most distant ages, incomplete as their exploration has been. But the extensive and methodical excavations undertaken from 1877 to 1881 by M. E. de Sarzec at Tello (Tell Loh) have enriched the Louvre with a collection of monuments unique in the museums of Europe, and enable us to give, at the present time, an exact and precise account of the

character of Chaldæan architecture and sculpture long before Nineveh and Babylon had succeeded in imposing their supremacy upon these regions. Tello, fifteen hours north of Mugheir, twelve hours east of Warka, seems to represent the ancient Sirpurla.* Its ruins, which cover a space of four miles and a quarter, consist of a series of mounds at a short distance from the course of an ancient canal dug by the hand of man, the Shatt el Hai, which starts from the Euphrates and flows into the Tigris twelve hours below Bagdad. The principal tell contained the substructures of a palace which was, two or three thousand years before our era, the dwelling of a prince named, according to Assyriologists, Gudea. Hither we must especially transport ourselves, as well as to the mounds of Mugheir, Warka, and Abu Shahrein, where the English explorers Loftus and Taylor made some excavations with good results. The narrative of these excavations and the monuments which they have yielded to our museums, will help us to determine the peculiar features of an essentially self-made art, born spontaneously on the soil where it flourished, and apparently in no degree borrowed from its neighbours.

I. ARCHITECTURE.

One of the fundamental characters of Chaldæo-Assyrian architecture is the exclusive use of bricks as the constructive material. This is required by the very nature of the soil of Mesopotamia, in which

* The authority of a syllabary and a bilingual text enables us to correct the pronunciation of this name to Lagas. See Pinches in *Babylonian and Oriental Record*, vol. iii., p. 24. [Translator's note.]

building-stone and wood suitable for carpenters' work are entirely wanting, while the clay is thick, adhesive, and peculiarly adapted for fashioning in the mould and baking in the kiln. Accordingly, while the modern inhabitants of the country continue to make bricks, their manufacture is already recorded in the biblical reminiscences of the Tower of Babel: "Go to," say the men who would build a tower that should reach to Heaven, "let us make brick and burn them throughly: and they had brick for stone and slime had they for mortar."* The prophet Nahum informs us of the method of brick-making: "Draw thee waters," he says, ". . . go into clay, and tread the mortar, make strong the brick-kiln."† There were two kinds of bricks. The unbaked brick is a square of whitish clay, mixed with fine straw and simply dried in the sun when it comes out of the mould; it was generally from 8 in. to 1 ft. square by 4 in. thick. The month in which the heat of summer first becomes intolerable in these regions, namely the month of Sivan (May-June) was called "the brick month," or that in which the clay cakes were submitted to the action of the sun. To judge by what is done in Egypt at the present day, one workman could by himself make from one thousand to fifteen hundred bricks a day. The baked brick was subjected to the action of fire in proper kilns, like those of our modern brickyards; it acquired, through the baking, a reddish colour, and was less sensible than the crude brick to the decomposing action of damp; it was also more limited in its dimensions, in order that the heat might penetrate the internal substance of the mass,

* Genesis xi. 3.

† Nahum iii. 14.

without danger of calcination on the surface. On one side of every brick, baked or unbaked, the name and official titles of the reigning prince were stamped by means of a matrix or a die used as a seal; thus, at Tello most of the bricks were marked with the name of Gudea, and at Babylon bricks of Nebuchadnezzar are found by hundreds of thousands.

While describing the construction of the fortifications at Babylon, Herodotus shows the process followed by the Chaldæans in building a wall: "As they dug the moat, they made bricks of the earth taken out of the trench, and when they had made a certain number of bricks they baked them in kilns. Then, using boiling bitumen as mortar, and inserting mats of woven reeds at every thirtieth course of bricks, they built first the borders of the moat, and next the wall itself in the same way."* Mesopotamia possesses abundant wells of bitumen, notably at Hit and at Kalah Shergat; as for the tall reeds which still grow in abundance in the marshes of Lower Chaldæa, their employment in building had the effect of giving more solidity and cohesion to the courses of bricks. For walls less




Fig. 1.—Brick from Tello (Louvre).

* Herodotus i. 179.

carefully constructed, or for partition-walls in the interior of the houses, a simple mortar of clay was used instead of bitumen. In great structures, such as Birs Nimroud at Babylon, the bricks are bound together by mortar made of lime, solid enough to stand all tests. The ruins of Mugheir have revealed the use of a mixture of ashes and lime, which is still employed by the natives, and called by them *sharûr*.

The necessarily limited size of bricks baked in kilns or dried in the sun must have helped to bring about a speedier disintegration of the structures, and have been a serious obstacle to the erection of walls of a height to be compared, for instance, with that of the Egyptian temples. At certain seasons of the year in Mesopotamia the rain falls in torrents, and, filtering through walls in bad repair, would soon open cracks and bring about the ruin of the structure. In these lowlands furrowed with watercourses, the crude brick of the foundations often on this account ran the risk of returning to its condition of clayey mud without consistency. Greek tradition relates that the Medes and Chaldæans saw a part of the walls of Nineveh fall of themselves, when they prolonged a blockade which forced the besieged to admit the waters of the Tigris during many weeks into the moats beneath the ramparts. The cuneiform inscriptions themselves, while the empire founded by Nebuchadnezzar was flourishing, often point out temples and palaces falling to ruin, which the kings strive without ceasing to repair or rebuild.

The old sanctuaries of primitive Chaldæa, E-saggil, E-zida, the Temple of the Great Light, E-parra, E-anna,

E-ulbar, and others consecrated to Sin, to Samas, to Nana, to Bel Marduk, to Nebo, are restored at great expense by Nabonidus, the last King of Babylon, who sets himself the task of recalling in his inscriptions the material difficulties of this work worthy of a pious antiquarian. Let no one be surprised after this at the striking contrast between the ruins of Mesopotamia, and those of Egypt as we now see them. In the valley of the Nile building-stone abounds, and the architect has only to make his choice among the various qualities of material. Accordingly he hews out gigantic monoliths, erects imposingly majestic pylons, rears to an aerial height forests of pillars which seem to uphold the sky, plants in the middle of the desert those massive Pyramids which will defy to the end of time even the most determined of Vandals. On the banks of the Tigris and Euphrates, on the contrary, there is now nothing but the uniform plain of the desert, broken here and there by mounds of *débris* covered with sand; here it may be said with truth that the very ruins have perished. Only in thought can the archæologist reconstruct vast buildings in accordance with the vast material buried in disorder in the mud. The use of bricks in building has been, to a greater extent than political events, the auxiliary of Jehovah's wrath against Nineveh and Babylon.

If the nature of the soil forced the Mesopotamian architect to build with bricks, the neighbourhood of rivers and canals for irrigation and the want of outlet for the water obliged him at the same time to have recourse to an expedient peculiar to Chaldæo-Assyrian architecture. He had to raise the actual dwelling on

an artificial terrace removed from the level of a soil impregnated with unwholesome damp. This platform or basement of unbaked brick on which the building was placed is met with everywhere, not only at Nineveh and Babylon, but from the beginning in the substructures of Mugheir, Tello, Warka, and Abu Shahrein. In the palace of the *patesi* Gudea, the mass forms a sort of immense pedestal 39 ft. high, and nearly 655 ft. at the base; at the present day the sides form in relation to the plain a slope of 164 ft. Formerly the platform was mounted by a gentle slope intended for horses and chariots, and by one or more flights of steps which broke the outline of the terrace. The stone staircases by which the terrace of the palaces of Persepolis is ascended, are still in place; in Chaldæa and Assyria, where they were built of brick, they have almost everywhere disappeared. However, Taylor discovered two on the side of the platform of the palace of Abu Shahrein; one has only twelve steps 2 ft. broad; but the other was a monumental staircase of stone, 16 ft. broad, with a slope of more than 65 ft.

The edifice which surmounts the platform at Tello is of bricks cemented together with bitumen; its exterior walls are 5 ft. 10 in. thick, and form a parallelogram 173 ft. long and 101 ft. broad. Like the palaces of Warka and Mugheir, its orientation is according to the Assyrian custom—that is to say, the angles are turned towards the cardinal points, not the sides as in the Egyptian monuments. The two longer sides bulge slightly towards the middle, thus describing two opposite elliptical curves—a peculiarity which gives to the plan of the edifice something of the appearance of

a barrel, or of two trapeziums joined at the base. The outer surface of the walls is not everywhere uniform and flat ; the adjacent sides of the northern angle are ornamented by projections alternately curved and rectilinear—a system of decoration which has also been observed at Warka, among the ruins of the temple called Wuswas, and is found later in the Assyrian monuments. The great north-eastern façade exhibits




Fig. 2.—Plan of the palace at Tello (after Heuzey).

in the middle, besides the outward swell of which we have spoken, a projection 3 ft. 3 in. thick and 18 ft. long. The wings of this projection are formed of square pilasters and half-columns 1 ft. 7 in. in diameter, which recall the clustered pillars of our cathedrals, and form one of the most interesting peculiarities of the primitive architecture of Chaldæa. Taylor* and

* *Journal of the Royal Asiatic Society*, vol. xv., p. 406.

Loftus * had already remarked, at Abu Shahrein and Warka respectively, pillars and half-columns of brickwork; M. de Sarzec has found the same architectural features in one of the secondary mounds of Tello, which he calls the *tell of pillars*,† and which seems to represent the ruins of the temple of the god Nin Girsu. Two of these pillars, which measured 6 ft. in thickness, and were separated by a space of $6\frac{1}{2}$ ft., still consisted of twenty-four courses of bricks.




Fig. 3.—Section of pillar (after Heuzey).

pillar," says M. de Sarzec, "is formed of a cluster of four round columns close together, and built entirely of brickwork. . . . If one of the four round columns is taken to pieces it is found that every alternate course is formed of a circular brick in the centre, round which radiate eight triangular bricks grooved at their interior angle, and rounded on the outer surface, so that they describe by their union a complete circle. In the next course the circle is composed, on the contrary, of eight triangular bricks ending in a point, which are united at the centre of the column, and of six other curved bricks which enclose the first eight. The space between the four circles thus formed is

* *Travels and Researches in Chaldæa and Susiana*, p. 175.

† *Decouvertes en Chaldée*, p. 62.

filled up with two large bricks hollowed out in the form of an arc of a circle, which fit exactly into it. These curious pillars, thus ingeniously constructed, recall the Egyptian order, modelled upon vegetable forms, which imitates four lotus-stalks in a bouquet; they show how skilfully the Chaldæans could dispense with the stone column. The base consisted of a square mass of bricks forming a pedestal projecting on all sides 2 ft. 11 in. beyond the shaft. The whole group was covered with a thick bed of plaster.*

Yet, whatever skill was displayed in the manufacture of these specially moulded bricks, round, triangular, or forming a section of a circle, pillars of this construction could not, like the Egyptian column, show sufficient solidity to support a heavy mass; they would soon have bent under the burden. Accordingly they could only be employed exceptionally and almost entirely for decoration, whether to support the roof of a grand staircase or to shelter the *cella* in which a deity delivered his oracles.

The defective side of Chaldæan architecture, therefore, consists in the lack of stone supports rising proudly into space like the Egyptian column, and upholding on their bold heads, quite as well as the thickest walls, the foot of the arch, the architraves, the roof, the upper terraces or the upper stories of the building. But the proof that the architects would have hewn columns of stone, if nature had furnished them with the necessary material, is just this ingenious artifice by which they succeeded in replacing them; and moreover they did not hesitate to employ small columns of wood or metal in the con-

* See Heuzey, *Un palais chaldéen*, pp. 37-58.

struction of small buildings, such as the shrines of their gods. A stela of King Nabu-ablu-iddin (about B.C. 900), found at Abu Habbah, represents the shrine of the god Samas, supported by small wooden pillars, covered with plates of bronze overlapping each other so as to resemble the trunk of a palm tree (see fig. 29). The base and the capital are alike; they are composed of a double volute shaped like a lotus-flower, approaching somewhat the Ionic capital; in short, the Chaldæans knew how to make use of the column in minor architecture.

One doorway at least was opened in each façade of the palace of Tello, but these openings were not on the axis of the structure, nor even symmetrical. The principal side (the north-east) had two entrances; the largest, nearly in the middle of the swell, had an opening 3 ft. 11 in. broad. It was constructed at a later period—that is to say, at the time near the Christian era when the Græco-Parthian kings of Characene conceived the idea of restoring Tello and installing themselves there. Like the Arab houses of our day, the outer walls of the palace of Gudea show no other openings; there are neither windows nor lights of any sort, admitting the air and the day, and looking out over the country or the town.

Let us now penetrate into the interior of the Chaldæan edifice, of which the blind and dumb walls leave in our imagination an impression of gloom and cold uniformity. The walls seem never to have exhibited the smallest architectural decoration; they are entirely bare, and only characterised from time to time by depressions and projections; no traces of mouldings, of

plinths, of cornices, and of those devices to which the architects of all countries have recourse in order to break the lines of the walls, and to call forth effects of light and shade. It must be supposed that the interior decoration of the palace consisted entirely of colouring and hanging draperies. The thickness of the wall varies from 8 ft. 6 in. to 2 ft. 7 in. All the partitions cut one another at right angles, forming thirty-six square or rectangular chambers; the largest measures 39 ft. 4 in. by 12 ft. 2 in., and the smallest 10 ft. 11 in. by 9 ft. 9 in. The disproportion which exists, especially in the state saloon, between the length and breadth, the extreme thickness of the walls, even of those which are the least important in the structure, form essential peculiarities to which we shall draw attention later in the Assyrian edifices. At Nineveh it has been proved that it is the thrust of the semicircular vaulting, which roofs the chambers, that has forced the architect to bring the parallel walls near to one another and to give them an enormous thickness. Are we, in the absence of palpable proof, to draw the same conclusion with regard to the palaces of old Chaldæa? Are we authorised to assert that the vault was known three thousand years before our era? In a word, how were the halls of Gudea's building covered? Was it everywhere by means of transverse rafters supporting a floor and a terrace? or was it oftener by a bricked vault? As far as we have read M. de Sarzec's narrative, or M. Heuzey's studies on the excavations of Tello, we have found no direct answer to this question. Perhaps the present state of the ruins or the successive alterations to which the primitive structure has been subjected do

not allow a categorical solution of the problem to be given. However, important indications authorise us to believe that the Chaldæans of the time of Gudea already understood the vault and used it for roofing their houses. In several parts even of the palace of Tello, M. de Sarzec found small vaulted passages, 3 ft. 3 in. high and 1 ft. 11 in.* thick, in a perfect state of preservation; in one of the secondary mounds he brought to light a small vaulted drain which carried the




Fig. 4.—Corbelled vaulting at Mugheir (after Taylor).

sewage of the town far away into the plain. Taylor found, in an underground chamber of the necropolis at Mugheir, the most primitive kind of vault that has ever been known—that called the corbelled vault. In this false vault the courses of bricks ascend in parallel rows on each side until they meet one another, every fresh course projecting perceptibly beyond that beneath it, until the opposite courses touch and form one.

It was, then, as it seems, the Chaldæans who invented the vault;† the want of timber compelled them in early times to contrive to defend themselves at once against the heavy rains and the ardour of a torrid sun; the creation of the vault was in their case instinctive and spontaneous. They raised, two or three thousand

* E. de Sarzec, *Découvertes en Chaldée*, pp. 34, 35.

† See, however, Garstang, *The Third Egyptian Dynasty*, Constable, 1904, pp. 28-29, plates, v., xiv.

years before our era, vaults and domes like those which are built to this day by the rudest masons at Mosoul or Bagdad. No doubt the present state of the Chaldæan ruins and the insufficient explorations which have been undertaken among them do not enable us to say whether these Proto-Chaldæans knew every kind of vault, as the Assyrians did in the age of the Sargonids, or the Babylonians at the epoch of Nebuchadnezzar; but the remarkable perfection observed in their monumental structures, and in the very manufacture of the bricks, are so many arguments in favour of the inference that the palaces and houses of the Chaldæans in the time of Gudea were surmounted, for the most part, by semi-circular vaults or by cupolas, as were later, according to Strabo,* the houses of the Babylonians. The vaults supported a terrace formed of clay; this layer of earth would be less thick over rooms roofed only with a ceiling of palm-beams and reed-matting. The ascent was by staircases, an example of which seems to have been found in the palace at Tello.†

While clearing away the material accumulated between the courts A and B, the workmen employed by the French explorer came into contact (at the point H) with a structure of baked brickwork, which proves that the Chaldæans at the remotest epoch had already invented one of the most interesting and characteristic elements of their architecture—the *sikkurat* or staged tower. The lower layers in the palace of Gudea alone exist, and are composed of two solid masses in stages one above the other. In its present condition the upper terrace is a mass 26 ft. square, 13 ft. less on all

* Strabo xvi. 1, 5.

† E. de Sarzec, *op. cit.*, p. 37.

sides than the lower stage ; perhaps there still exists a third and lower step, which has not been reached by the soundings, which are imperfect at this point. The *zikkurat* of Tello was not in any case so lofty or so important a structure as those of the Ninevite palaces or those represented by the ruins of Babil or Birs Nimroud at Babylon. It was even much less considerable than that which Taylor observed at Abu Shahrein, and which was equally old. These towers always had, from the first, seven stages, each painted of a different colour, and connected with the worship of the sun (Samas), the moon (Sin), and the five planets of the astronomical system of the Chaldæans.

The disposition of the royal apartments showed a striking analogy with that which we shall meet with again later in the palaces of Nineveh ; there were the convenience and comfort which we find in the palaces of modern oriental sovereigns. To the Chaldæans again we must give the credit of having invented that architectural arrangement which springs from the necessities of oriental life, and is so well fitted to its needs that for four thousand years it has never varied. There were in the palace of Gudea three interior courts (A, B, C, fig. 2), round each of which the rooms radiated, and from which they received air and light. Each of these three groups had its own entrance, and communicated with the next group only by a single passage easy to guard or to close. The group of chambers situated in the northern angle (C) was especially isolated and removed from the others ; it was the hareem or women's apartments. At the eastern angle (B) were the rooms composing the seraglio or *selamlık*—that is to

say, the part of the palace inhabited by the king and his officers; there was the saloon for official receptions, of which we have given the dimensions. This part of the royal dwelling communicated on one side with a state courtyard, measuring 55 ft. 8 in. by 68 ft. 9 in., and on the other with the outside by means of a smaller room serving as an antechamber; beside the door opening on the façade, boxes or recesses had been arranged in which the guards were posted. The third group of chambers, on the south-east (A), formed the *Khan*—that is to say, the dependencies of the palace, the kitchens, the slaves' lodgings, and the stables.

All the rooms were paved with bricks; they very rarely led into one another, and had an opening looking on to the court. The largest of the doorways, that which opened into the state saloon, was of the unusual breadth of 6 ft. 6 in.; it was probably a folding door. Under each of the principal doors there was a great threshold of marble or alabaster, sometimes covered with an inscription and placed on a bed of bitumen and crushed bricks; under this concrete, finally, cylinders of precious stone and talismanic amulets were generally found.

The leaves of the door turned on pivots, the point of which rested in a cavity hollowed out for this purpose in a great block of diorite. M. de Sarzec brought to the Louvre a large number of these natural blocks, which were found buried in the pavement so as only to rise an inch or two above the surface. On the smooth surface of each of them it is seen that the socket, hollowed out in the form of a conical cup, has

undergone an incessant friction; round the hole an inscription, sometimes circular, was engraved (fig. 5). To prevent the wooden pivot of the doors from wearing



Fig. 5.—Socket for pivot of door, from Tello (Louvre).

out too rapidly, it was enveloped in a metal sheath, which took the form of a funnel, and which was fixed to the wood by means of nails. One of these bronze cups has been found at Tello, still in place on the socket.*

The discoveries of Loftus and Taylor show us how the façades and the rooms of the Chaldæan palaces were decorated. The principal façade of the buildings at Abu Shahrein and Warka had a mural decoration of a kind as primitive as it was singular.† First it was plastered with a thick layer of clay stucco; then, before this plaster was completely dry, cones of baked clay were buried in it, like metal nails. Only the head of these cones is visible on the surface of the wall, while the stem is plunged into the thick clay and sticks there unseen. To the heads of these cones, disposed at regular distances, and acting perhaps also as talismans,



Fig. 6.—Terra-cotta cone from Tello (Louvre).

* F. de Sarzec, *op. cit.*, p. 59.

† Loftus, *Travels and Researches*, pp. 187-189.

various colours are applied ; they are black, red, white, or yellow. Moreover, each head is separated from its neighbours by coloured geometrical lines, so that it became to the eye the centre of a lozenge or a square.

If the interior of the rooms was lined in monochrome with white stucco, or with fresco painting, nothing of this decoration is left. But we have in sufficiently large quantities, although always much mutilated, the remains of another more original system of wall decoration, of which the Chaldæans are the inventors—that is to say, enamelled bricks. By applying a coloured paste, which the fire would vitrify, to one of the surfaces of the bricks before baking, a glaze or enamel was produced, closely united to the clay and immovably solid. It was again necessity and their ungrateful climate which induced the Chaldæans to have recourse to this ingenious method. They were in great need of a remedy for the want of stone and a means of preventing the heavy rains from spoiling the colours applied to the walls. They succeeded so perfectly in this that even at the present day the brilliancy of these glazed tiles is not affected. The colours with which they are painted are of the simplest, and vary little ; they are blue, white, black, yellow and red. Unfortunately, those fine fragments which have been brought to our museums are only so far interesting that they teach us the technical methods of a manufacture which involves that of opaque glass ; even those which are least mutilated contain at the most a few floral designs or portions of the figures of animals, and moreover these last are not older than the epoch of Nebuchadnezzar.

The trenches dug among the massive terraces of Chaldæa have revealed other curious details of construction. We know, for instance, what steps were taken to prevent the sewage of the houses or the rain-water which fell upon them from filtering through the platforms of crude brick on which the buildings stood; a rapid disintegration would have followed. They, therefore, planned a complete system of water-channels and drainage. In one of the mounds at Tello, M. de Sarzec found a series of cylindrical pipes or tubes of baked clay, fitted into one another, and forming together a conduit for the water.*




Fig. 7.—Drainage pipe at Mugheir (after Loftus).

But the place where this method has been carried out with peculiarly ingenious skill is the necropolis at Mugheir. The top of the platform, in the body of which the tombs are sunk, is covered with a brick pavement laid with special care, in which every chink is filled up with bitumen. Under this upper crust the coffins are ranged in order, one above the other, each one being placed separately in a small chamber. At intervals brick tubes are met with, fitted into one another and forming a sort of immense flue hidden in the structure. The lower extremity of the pipes opened into a drain; the upper end, on a level with the surface of the pavement of the terrace, was furnished with a cap pierced with an infinite number of small holes like a skimmer. Through these the rainwater was carried off, and this system of drainage was so

* E. de Sarzec, *op. cit.*, p. 60.

wonderfully well understood and carried out, that it has remained intact to our own day, and, according to Loftus, the tombs have been so well preserved that they are found perfectly dry, including the bodies and their furniture. We shall see the Assyrians take similar precautions to preserve the terraces of the Ninevite palaces from the percolation of water.

The construction of a temple or palace was the occasion of a religious ceremony analogous to that which we call the laying of the first stone. In a hollow formed in the foundation-wall a cylinder of baked clay was deposited (fig. 8), on which an inscription was written describing the erection of the building and setting forth the piety and great deeds of the prince; this cylinder was accompanied by various talismanic objects: cones and statuettes of bronze and baked clay, cylindrical seals, votive tablets, sometimes of silver or gold. Among the foundations of the palace of Gudea, M. de Sarzec found four of these cavities in the wall measuring 1 ft. 1 in. by 10 in. by 4 in.; they still contained the cylinders and amulets deposited there.

Hiding-places of the same kind have been observed at Senkereh, at Mugheir, and among the ruins of almost all the Chaldæan and Assyrian buildings. The Assyrians themselves, when they wished to restore an old ruined temple, took pains first to find out the hiding-place of the foundation-cylinder or *timmennu*.

The last king of Babylon, Nabonidus, relates in one of the official inscriptions of his reign how he happened to find the *timmennu* of the earliest builders of the temple of the Sun at Larsa. King Kurigalzu (about B.C. 1350), and later Esarhaddon (B.C. 680—667), and

Nebuchadnezzar himself, had repaired this venerated sanctuary, and sought vainly for the hiding-place of the talismans. "Then I, Nabonidus, inspired by my piety towards the goddess Istar of Agade, my sovereign, caused an excavation to be made. The gods Samas and Rammanu granted me their constant favour, and I found the foundation-cylinder of the temple of E-Ulbar." It bore the name of the king Sagasaltias (about B.C. 1500). After reading the inscription, Nabonidus restored it to its place and himself made another cylinder to record




Fig. 8.—Foundation-cylinder from Khorsabad (Louvre).

his researches and his own works; he deposited it in the foundation by the side of the ancient cylinder. Modern explorers, no doubt also favoured by Samas and Rammanu,

found in a sufficiently good state of preservation the mysterious hiding-places and the precious objects which had been piously placed there 550 years before our era.*

II. STATUES AND BAS-RELIEFS.

The discoveries of M. de Sarzec at Tello, and those of other explorers in Chaldæa, allow us to go back almost to the origin of sculpture in Western Asia. Our museums possess, in fact, bas-reliefs and statues belonging to a rudimentary stage of art, the remote age of which is still attested by the archaic inscriptions which accompany them, and these most ancient monu-

* M. Babelon's statement that the cylinder of Sagasaltias was found by modern explorers with that of Nabonidus is unfortunately inaccurate. Only the records of Nabonidus were discovered. See Taylor, *Journal of the Royal Asiatic Society*, vol. xv.

ments are followed, as in the case of Egypt and Greece, by other statues and bas-reliefs which, descending a chronological scale across the ages, represent the graduated phases of artistic progress in Chaldæa before the Ninevite supremacy was imposed upon this country. Among the fragments of sculpture at Tello, that which M. Heuzey considers most primitive, and which should be placed at the head of the productions of oriental sculpture, is a bas-relief of greyish limestone, 10 in. broad and 5 in. high. Four figures alone remain of the complicated scene which decorated this stone panel.

One of them is seated, with the profile turned to the left; it is a beardless man rather than a woman, and his face is half covered by an exaggerated eye seen from the front as in children's drawings. His hair consists of two long



Fig. 9.—Bas-relief from Tello
(Louvre).

tresses falling to his shoulders, and almost to be mistaken for the lappets of the high tiara with which he is crowned. This tiara seems to be adorned with two bulls' horns. The bust is draped with a large shawl which leaves the right shoulder bare. The hand, raised to a level with the face, looks like a simple fork; it holds a cup, as if the scene represented a libation, and in fact we still see a part of the deity to whom the offering is directed. On the right a bearded man with square shoulders, crowned with a low cap, dressed in a large robe without folds, holds in his right hand a sort of club, with which he seems to deliver a blow upon the

head of his companion, whom he seizes by the hand. It will be seen that the explanation of this picture is exceedingly doubtful; but looking from the point of view of the history of art, we must recognise in it without hesitation a fragment which comes down from remote antiquity. The relief is low, the outline of the figures is timid and uncertain, the details are disproportioned, as if the rude chisel which carved them had been held in the unskilful hands of a child; the design is full of elementary mistakes, though limestone is soft and easily worked.



Fig. 10.—Bas-relief from Tello (Louvre).

A more advanced art marks the fragment of a bas-relief which M. Heuzey called "the Eagle and Lion Tablet," and which is dated by an inscription mentioning the king Ur-Nina (B.C. 2500). An eagle is seen here with outspread wings standing upon a lion. The sculpture is equally flat and without modelling, but the graceful outline of the figures is clearly chiselled, and with a surer hand; the extremities of the wing feathers of the eagle are indented, the body of the lion is remarkably correct in outline, except the head, which still remains barbarous.

A third stage of Chaldæan sculpture may be represented by the "Vulture Stela," on which the names of two kings have been read, one of whom is the son of Ur-Nina. The three fragments of this limestone stela are carved on both sides. On one of them a flock of vultures carry away human remains in their flight—

heads, hands, and arms. The human heads denote an art which has left the gropings of childhood behind: they are entirely shaved, the nose is always aquiline, the eye of an exaggerated size and triangular. The vultures, more rudely drawn, are nevertheless well characterised by their long curved beak and their claws of exaggerated length; the markings



Fig. 11.—The Vulture Stela (Louvre).

of the feathers and wings are brought out. On another fragment of the same stela it seems that we witness the construction of a sepulchral tumulus.

Men dressed in a short tunic, fringed, and tightened at the waist, carry on their heads wicker baskets, probably containing earth to cover the pile of corpses heaped one upon the other in symmetrical and alternate rows. The third piece of the same monument seems to represent a scene of carnage. As for the back of the stela, it is less ornamented; however, on one of the fragments (fig. 13), a pole surmounted by an eagle with outspread wings is seen, and then a large human head, incomplete but highly interesting; it exhibits, from an anatomical point of view, the same



Fig. 12.—The Vulture Stela (Louvre).

character as the smaller heads which we have just considered; but its head-dress is a most curious feature,—a sort of tiara decorated with bulls' horns. "By an archaic conventionality," observes M. Heuzey, "these two horns are seen in profile, curved forwards and backwards; but in reality they were attached to the sides of the cap. . . . The cap is also surmounted by a crest of four large feathers, in the middle of which rises a cone decorated with a quaint head also crowned by a crescent; this little decorative head, drawn in full



Fig. 13.—The Vulture Stela (Louvre).

face, has an exceedingly long and broad nose without any sign of a mouth, so that it may be doubted whether it be the head of a man or of an animal."* The same tiara is found with unimportant modifications on Assyrian cylinders and

bas-reliefs, in which it forms the head-dress of deities or pontiffs. The artistic superiority of the bas-reliefs of the Vulture Stela over the monuments quoted previously is abundantly evident, and already allows us a foretaste of the sober and vigorous art revealed to us by the large statues found in the palace of Gudea.

It was in the most spacious court of the palace that M. de Sarzec found assembled nearly all the Chaldæan statues which he had transported to the museum of the Louvre. To the number of ten, they are of blackish diorite with a bluish tinge; all are headless and bear

* Heuzey, *Gazette Arch.*, 1884, p. 195.

inscriptions in the name of Gudea or of Ur-Bau. At the moment of discovery they were lying on the slabs of the court-yard,—on one side those which represent upright figures, on the other the seated statues. A separate head, appearing to belong to one of the statues, was also found in the same courtyard. The other heads were unearthed elsewhere, and it is impossible to say whether they had been removed from the headless statues that we know.

All these heads, though exhibiting common characteristics, are distinguished from one another by

peculiarities which disclose the surprising skill and the fecundity of the Chaldæan genius at this remote epoch.

The man's head (fig. 14) found in the great courtyard is of life-size, the hair and beard completely shaven, as in certain Egyptian statues. The eyebrows form an exaggerated projection above enormous eyes; the skull is remarkably elongated; the mutilated nose alone prevents us from having the complete type of the Chaldæan race, with its hard features and thick, sensual lips.



Fig. 14.—Chaldæan head (Louvre).



Fig. 15.—Chaldæan head (Louvre).

In a neighbouring tell M. de Sarzec found another head of the same size and of an equally interesting type. It is less severe in aspect than the preceding

one, but carved with equal skill. The face is round and almost smiling, the chin broad and powerful, the nose flat. The very original head-dress is composed of a woollen cap fitting closely to the head, and furnished with a thick border, which, turning up, forms a sort of crown; the meshes of the woollen tissue are conventionally marked by a number of symmetrical



Fig. 16.—Chaldæan statue (Louvre).

rolls. Even at the present day in Lower Chaldæa the Christian priests of the Chaldæan rite envelop their heads in a turban of black stuff, which allows of a similar arrangement.*

As for the headless statues, whether seated or standing, they have all the same characteristics, exhibit an identical type,

and are incontestably of the same school of sculpture. Here is a personage seated on a sort of stool not fully carved out; he recalls involuntarily the Greek statues of the sacred way of the Branchidæ at Miletus, and is in the same religious attitude. A cloak without sleeves is crossed over his breast and thrown back over his shoulder; a handsome fringe, delicately

* E. de Sarzec, *Découvertes*, p. 61.

carved, falls over the whole depth in front ; the hands are clasped on the breast in the oriental posture of meditation and devotion ; the bare feet are chiselled with an attention to detail never to be surpassed in later times, even by the Ninevite artists. On the knees of the personage lies a tablet intended to receive an inscription or a design. In fact, another statue like this, though of smaller proportions, holds on its knees a similar tablet, on which the plan of a fortress with its bastions and posterns is engraved in outline, just as an architect of the present day would draw it. A graduated rule, that is to say, one subdivided into fractions of unequal but proportional length, $10\frac{3}{4}$ in. long, is carved in relief beside the plan, for which it serves as a scale ; finally, at the side lies the style with which the architect engraved his design (see fig. 53). The



Fig. 17.—Chaldæan statue (Louvre).

standing statues answer almost to the same description ; they also are bare-footed, with the hands crossed upon the breast but the arrangement of the long shawl, which seems to form the only garment of all these personages, becomes more intelligible. The Arab still drapes himself in the same fashion in his burnoos,—that garment, at once so simple and so dignified, of the shepherd of the desert. It is a piece of woollen stuff, the borders of which are adorned with a fringe ; it is folded in two, and wrapped

round the body obliquely, so that it covers one arm and leaves the other bare; the upper corner, held fast by wrapping the garment once round, is enough to keep the whole in place. We shall find this large shawl again on the Ninevite bas-reliefs, just as we shall observe the persistence and exaggeration of this sober and nervous style, which, as early as the Proto-Chaldæan epoch, lays too much stress on the muscles, and lingers with an excessive fondness over anatomical details.

The Chaldæan statues were intended to be seen all round, and not laid flat against a wall; they are completely finished behind as well as in front. Compared with the statues found in the temples of Cyprus, for instance, they show us that the artist has sought to spare neither his time nor his trouble. Amid this sobriety of treatment and this uniformity of attitudes we feel that Chaldæan art is already far from the hesitation and incorrectness of the first age; the chisel attacks the hardest stone with vigour and success; the artist's hand is experienced and sure of itself. This archaic art is above all realistic, and aims at a precise and even affected following of nature. The bare shoulder is modelled and copied with surprising truth, the hands and feet are studied even to the knuckles, the nails, the wrinkles of the skin. At the same time the figures are thick-set and, it may be said, far too short—a fact which contributes to increase the impression of strength and muscular energy produced by an attentive observation of them.

The suppleness of the Chaldæan genius at the time of Gudea appears again in a singular monument of the

De Sarzec collection, which may be taken to be the foot of a vase rather than the base of a small column (fig. 18). Small figures in high relief, nude, and seated on the ground, lean against a cylindrical stem. The best preserved figure has an oval face of rare refinement, and of a type entirely foreign to that of the large statues; with his beard cut in a point, and his head covered with a woollen turban, he looks straight in front of him with a smiling aspect; in all Assyrian sculpture no countenance of such originality could perhaps be found. We do not know what is the meaning of these little figures crouched round this sort of basin. They seem to hold the place of the winged bulls and lions or other fantastic genii, whom Assyrian art will soon multiply everywhere in the capacity of architectural supports or ornaments.



Fig. 18.—Foot of Chaldean vase
(Louvre).

In front of the palace at Tello stood a large stone basin decorated with sculpture, some fragments of which have come down to us. This monolithic trough, 8 ft. 2 in. long by 1 ft. 7½ in. broad, served, perhaps, to water the camels and the flocks which halted at the gate of Gudea's dwelling; or rather, on account of its rich ornamentation, may we believe that it was a basin consecrated to the service of the temple, like the brazen sea in the Temple of Jerusalem, or the vase of Amathus? However it may be, there were,

on its two longer surfaces, in low relief, women with arms outstretched, holding magic vases, from which



Fig. 19.—Bas-relief from Tello (after Heuzey).

two jets of liquid gushed, on each side of an ear of corn, a graceful symbol of the proverbial fertility of Mesopotamia, enclosed by the sacred streams of

the Tigris and Euphrates, which were adored under the name of Naharaim, the two rivers *par excellence*.

The fragment reproduced here (fig. 19) shows us that the Proto-Chaldæans already gave to flowing water the conventional form of undulating lines (see also fig. 34); the woman is drawn with surprising truth.* The same technical skill is remarked in a bas-relief from Tello, which represents a bearded personage, in full face, with a costume in which M. Heuzey has recognised the fleecy stuff called *kaunakes* by the Greeks. Observe



Fig. 20.—Bas-relief from Tello (*Rev. arch.*, t. i., 1887, p. 265).

* L. Heuzey, *Un palais chaldéen*, pp. 59-117.

the delicacy with which the Chaldæan artists treated the costume and the beard. It may almost be said that Mesopotamian art has no further progress to make, and that it already shows its full proportions at the fabulously remote epoch represented by the antiquities of Tello.

There is less modelling in the figures which adorn the upper part of the *Caillou Michaux*; the relief upon it is dry and flat, and the drawing affects a hieratic stiffness which would suggest an epoch of decadence, or at least a time when Chaldæan art was arrested in its upward march. This monument, dated in the reign of Marduk-nadin-akhi, King of Babylon about B.C. 1120, was perhaps a stone rolled down by the waters of the river, which was made into a sacred object; the cuneiform inscription contains the donation of a landed estate, settled as a dowry.* The curious figures, under the protection of which this contract is placed, show us, as they do in many cylinders, that at this epoch Chaldæan mythology was turned to profit by the artists, who knew how to unite human to animal forms without falling into monstrosity or deformity, and to give symbolical figures to the stars and to the invisible genii conceived by their wild imagination. The drawing of these strange figures is not unskilful; they inspire terror without degenerating into the caricature and grotesque forms which mark the images of the gods among barbarous peoples. Chaldæan art is as learned as the secrets of its mythology are complicated. Examine, for instance, this winged goat

* See the translation which I have given of it in Lenormant and Babelon, *Histoire ancienne de l'Orient*, vol. v., p. 84.

lying before an altar ; the angular outlines of its horns



Fig. 21.—The *Caillou Michaux* (Cabinet des Médailles).

are rendered with truth, the muscles of its legs, perhaps badly placed anatomically, are analysed in their smallest details, and the movement of this animal, which is making an effort to rise, is very natural, though lacking in life and suppleness. We shall recognise the same characters of dryness and rudeness in the black basalt stela of the same king, Marduk-nadin-akhi. Here, as in the *Caillou Michaux*, the relief is flat, — nothing supple, graceful, or amiable ; the Chaldæan genius cannot smile. Of those ample garments of the Oriental, those draperies with which the Greek artist will be able to produce so powerful an effect, the Chaldæan artist is satisfied with scratching in outline, so to speak, the folds and fringes ; he makes heavy embroidered copes of them, like those of Catholic priests. But, in compensation, he looks at these embroideries through a magnifying glass, and excels in analysing

are rendered with truth, the muscles of its legs, perhaps badly placed anatomically, are analysed in their smallest details, and the movement of this animal, which is making an effort to rise, is very natural, though lacking in life and suppleness. We shall recognise the same characters of dryness and rudeness in the black basalt stela of the same king, Marduk-nadin-akhi.



Fig. 22.—Stela of Marduk-nadin-akhi (British Museum).

and reproducing the richness of the tissue, the innumerable and complicated forms of the design. We can henceforth foresee that the sculptor, losing sight of synthesis so as to place his ideal exclusively in the infinitely little, will never rid himself of the narrow formula in which he so early imprisoned his talent. All his figures in statuary or in the bas-reliefs, so highly finished in detail, show as a whole a hieratic and conventional stiffness, which will unhappily descend as a heritage to the Assyrian artist.

III. MINOR SCULPTURE AND THE INDUSTRIAL ARTS.

The Chaldæans could work in bronze as skilfully as in stone. M. de Sarzec has collected some bronze figures which, compared with other monuments already secured, allow us to fix some precise landmarks in the gradual development of the art of casting and chiselling metals in Chaldæa. A certain statuette of a man or woman (fig. 23) may be considered the most rudimentary attempt.* It has simply the shape of a cylindrical stem, the upper part of which is furnished with two arms and a human head like the *xoana* of the Greeks. This head, surmounted by small horns, is strangely barbarous; it recalls the art of the men of the bronze age and the most rustic of the Cypriote terra-cottas. Progress is manifest in other bronzes—



Fig. 23.—Chaldæan statuette in bronze (Louvre).

* Perrot and Chipiez, *op. cit.*, vol. ii., p. 192 f. [Eng. ed.]

separated, perhaps, from the former by several hundred years. These are statuettes which, instead of being fixed on a base, end in a reversed and much elongated cone, which must have served to plunge them into a soft matter such as mortar. One represents a recumbent bull, the other (fig. 24) a kneeling man holding in his hands the base of the cone; he is



Fig. 24.—Chaldean statuette (Louvre).

bearded and covered with the tiara with several pairs of horns, reserved for gods and genii. A third, lastly, is a woman carrying a basket on her head, whose body has remarkably the appearance of an elongated ingot. This canephoros, whose female form is only indicated by the breasts and the width of the hips, leads us naturally to speak of another canephoros (fig. 25), found at Afaj on the Euphrates, bearing the name of the king Kudurmapuk (B.C. 2000). It may be seen by this statuette that the art of working in bronze followed closely the progress of sculpture in stone. Though the head and arms are still the work of half-trained artists, the head is very remarkable; the arch of the eyebrows and the eyes are treated as in the large diorite statues; the hair is completely shaved. The same characters are observed in a remarkable figure of a bearded priest, wearing a tiara of moderate height, dressed in a long tunic with flounced fringes.* Here

* Perrot and Chipiez, *op. cit.*, vol. ii., p. 195, fig. 106.

is a mutilated statuette from Tello (fig. 26); it is a god standing on a crouching lion; the head of the roaring beast has a ferocious and natural expression, but the god's robe is cylindrical, without amplitude and without modelling, and the artist has tried in vain to conceal this stiffness, which betrays his impotence, by engraving the fringes and rosettes of the drapery. Remark that the long hairs of the lion are treated like the woollen shag of the priest's cap which we examined just now (fig. 15). The animal has very small wings; his forelegs are those of a bull, his hind-legs end in lion's claws; the study of nature here is perfect, but in those conventional lines which are meant to express the swell of the muscles, we feel the tendency to exaggeration and trivial rudeness which we remarked in the statues.

In one of the smaller mounds at Tello, M. de Sarzec discovered a fragment of a large bronze statue. "It was," he says, "a life-sized bull's horn, of bronze plating mounted on a wooden frame, but the wood was carbonised by the action of fire."* He had also found a sword, which was stolen and destroyed by an Arab. But we can cite another weapon of the same kind in the possession of Colonel Hanbury; the blade, curved



Fig. 25.—Canephoros of Kudurmapuk (Louvre).

* E. de Sarzec, *Découvertes*, p. 61.

† *Revue archéologique*, 1883 (3^e série, t. ii.) pl. xx.

like a scythe, and triangular, bears a votive inscription in the name of the Assyrian king Ramman-nirari, the son of Pudil (B.C. 1300). The curious peculiarity of this weapon is that on one of its surfaces a small recumbent deer is to be seen engraved, and this is the maker's mark : from this time onward the jealousy of craftsmen comes into play and declares itself by the same measures as in our day.



Fig. 26.—Chaldean statuette in bronze (Louvre).

Surprising as the phenomenon is at first sight, Chaldean pottery was far from following the progress of sculpture. The excavations of Tello have enriched the museum of the Louvre with five hundred terracotta cones, bearing the name of Gudea and Ur-Bau, but these are only industrial products, without artistic character, and belonging

to the brick manufacture. The necropoles of Warka and Mugheir, where we might have expected to meet with works of art, as in the tombs of Greece or Etruria, have only furnished coarse vases which bear witness to the complete inferiority of pottery among the Chaldæo-Assyrians. They are all singularly barbarous and rustic, whether they come from the archaic tombs of Warka and Mugheir, or issue from the ruins of the palaces where, nevertheless, the art of sculpture soars and displays itself in its perfect development. Assyrian pottery, even that of the

best epoch, resembles, sometimes so much as to be mistaken for it, the most archaic pottery of Greece proper and the Islands of the Ægean. But here it is only the beginning of art, the first effort of the potter who before long will fashion masterpieces; there, on the contrary, these vulgar kitchen receptacles form the whole art, and represent at once the start and the finish.

This neglect of ceramics by the Chaldæo-Assyrian artists results from geological and climatic causes analogous to those which, as we shall see, developed sculpture in bas-relief to the detriment of sculpture in the round. It is especially owing to the bad quality of the clay in Mesopotamia, which, though quite fit to be turned into square bricks, has not a fine enough grain for the purpose of fashioning from it the fragile frame of a broad crater, or of a slim amphora, and still less for the purpose of lending itself to all the details of face and drapery in graceful and slender figurines like those of Tanagra, Cyme, or Myrina.

The cohesion of the Mesopotamian clay is so imperfect that the Babylonian terra-cottas which have come down to us crumble almost at the first touch, in spite of the process of baking to which they have been subjected. It is observed that, to give some consistency to the body of the vases and to prevent cracks, the potter has been obliged to mix the clayey paste with chopped straw. It was impossible then to make the sides thin, or to fashion them with art; consequently it would not have been natural to decorate with rich and careful painting vases which could only be heavy and coarse. It was enough to trace out geometrical designs, bands

of colour, ovals, symmetrical festoons round the neck of the amphoræ; nothing in this sort of decoration has been borrowed from the animal or vegetable world or from history, of which the artist could, however, make so wonderful a use in the decoration of metal vases, or of knickknacks in ivory, wood, or stone.

The Chaldæan terra-cotta figurines, however coarse they may be, are not entirely divested of interest for the history of art and mythology, and M. Heuzey has been able to appreciate them with delicacy from this point of view.*



Fig. 27.—Chaldæan statuette in terra-cotta.

The statuettes collected in great quantities by Loftus, at Warka, are of solid clay, and were manufactured in a mould in one piece; the back is flat and modelled with the hand. The clay is of a greenish grey, or sometimes brown; it is well baked and very hard. The attitude of these grotesque little figures offers singularly striking analogies to the terra-cotta figurines of the first Egyptian dynasty; they are men in long robes, with their beards cut in the Assyrian fashion, women dressed in tight tunics and wearing falling head-dresses like the Egyptian figurines; their hands are clasped on their breast in the religious attitude which we know already from the Tello statues. It is, however, very difficult to give the precise date of these figurines, which, perhaps, for the most part, are not anterior to the time

* *Les figurines antiques du Musée du Louvre*, p. 1 ff.

of Nebuchadnezzar. Besides, we shall return to them later on. It is enough for the moment to observe how little varied and meagre was the theme worked out by the Chaldæan modellers in clay, at a time when sculpture and the other arts were nevertheless already most flourishing.

The monuments which we have just reviewed allow us to appreciate the degree of prosperity and perfection attained side by side with the higher branches of art by various industries in Chaldæa, such as tapestry, weaving, and the embroidery of stuffs. The stela of Marduk-nadin-akhi, for example (fig. 22), bears witness to the wonderful skill of the women of the royal hareem, or of the men employed in the workshop, whence issued that robe with golden fringe, covered with elegant designs and precious stones set in the web of the tissue, that tiara adorned with feathers and wide-open daisies, those sandals, the broad lozenge-shaped stitches of which can be counted.

M. Heuzey* has demonstrated that the stuff called *kaunakes* (καυνάκης) by the Greeks, who gave this name to a Babylonian garment, goes back at least as far as the epoch of Gudea. The representation of this woollen tissue shows several series of tufts arranged in rows one above the other; the principle of the manufacture of the *kaunakes* is the same as that of plush or velvet, only the woollen pile is longer and arranged less closely. This sort of material, invented by the Chaldæans, continued to be made by the Assyrians and Persians; in this way the Greeks came to know it, and Aristophanes speaks of it in his comedy of the *Wasps*.

* *Revue archéol.*, mai-juin, 1887.

Garments made of *kaunakes* are frequently met with on the Chaldæan monuments, especially on the cylinders, where they have been mistaken for robes of a gathered and gauffered material. They are worn both by women and by men, as is proved by the bearded personage whom we reproduced above (fig. 20), and a female statuette in alabaster which shows all the characteristics of Chaldæan art contemporary with the monuments of Tello (fig. 28).



Fig. 28.—Chaldæan statuette in alabaster.

The tablet of the god Samas (fig. 29), found at Abu-Habbah (Sepharvaim), and dated in the reign of the Babylonian king Nabu-




Fig. 29.—Bas-relief of the tablet of the god Samas (British Museum). pal-iddin (B.C. 850), shows together the two principal Chaldæan garments—that made of *kaunakes*, and that

of a plain material, open in front, which we shall often meet with again in Assyria. Moreover, this bas-relief, if it is closely studied, throws a remarkable light on the different industries in wood, iron, stone and wearing material. The tabernacle in which the god Samas is seated on his throne seems to be an iron niche, the upper part being curved to imitate a shallow vault; in the front of the shrine there are small pillars of wood or iron; the stem is covered with scales in imitation of the trunk of the palm-tree, and made, no doubt, of plates of metal laid over it; for base and capital there are volutes something like the Ionic capital. The solar disk, the symbol of the god, is supported by cords held in the hands of two genii, who seem to play a purely ornamental and decorative part. The throne of the god, and the table on which the radiated disk is placed, are elegantly sculptured pieces of furniture, and reveal a civilisation which strives after the highest refinement in its luxuries.



Fig. 30.—Chaldæan head in steatite (Louvre).

As for ornaments of precious metal, none have yet been found in Chaldæa, though we know that from the most distant ages gold and silver flowed into Babylon and the towns of Chaldæa as well as into Egypt. The goldsmith's art must have been on a par with that of the seal-engraver, the monuments of which are so numerous, as we shall now see. To these branches of art belongs a small head in steatite, carved in the round and forming the gem of the Tello collection; better than anything else, this head, treated in so

realistic and, at the same time, so highly finished a manner, brings us into contact, so to speak, with the brilliant superiority of the Chaldæan artist when he devotes himself to these secondary forms of art, which at the present day require the use of the magnifying-glass, and in which we are at a loss whether to admire most the patience of the artist, the steadiness of his hand, or the delicacy of his talent.

IV. CHALDÆAN SEAL-ENGRAVING.*

Though we do not yet possess more than a limited number of pieces of sculpture and statues, those imposing witnesses of Chaldæan art in the time of Gudea or Hammurabi, we can at least supply this want by the numerous and varied productions of the seal-engraver's art. The Chaldæans invented the carving of precious stones, and no people ever made a more constant use of those cylinders, cones and seals of every form, on which are seen, engraved in lines fine and deep, the same images which monumental sculpture drew upon the walls of temples and palaces. These stones carved in intaglio, whether hæmatite, porphyry, chalcedony, marbles or onyx of every variety, were worn round the neck, on the finger, on the wrist, or fastened to the garment; they were at the same time prophylactic amulets against sickness or witchcraft, and seals with which impressions were made at the end of public or private documents.

The most ancient of the Chaldæan cylinders reveals to our eyes the very origin of seal-engraving, the first

* See especially J. Menant, *La Glyptique orientale*, t. i., and L. de Clercq, *Catalogue de sa collection*, fasc. 1-3.

attempts to carve the round, ovoid, or cylindrical gems of the necklaces of the stone age. The burin and the puncheon, handled for the first time, do not yet trace out more than zigzags, lozenges, straight and semi-circular lines crossing one another. Soon attempts are made to trace buildings, figures of animals, antelopes feeding (fig. 31), or fish. The joints and swells of the quadrupeds' bodies are represented by round holes, the limbs by simple strokes.

Soon, with greater mastery over his instruments, the artist—for we may now give him this name—will seek to reproduce on the cylinders the human figure, and then that of the divine beings or the heroes begotten of popular fancy, whose image is to increase the talismanic virtue of the stone. There are monsters standing on their hind-legs, struggling with one another, and giants killing lions or human-faced quadrupeds. M. Menant has remarked that the figures of animals are always represented in profile, while the human figures, with long beards, are in full face even when the body is in profile. There are double-faced genii, quadrupeds with a single head and two bodies. One of the most remarkable cylinders of this primitive epoch is, without contradiction, that of the rich De Clercq collection, the design of which we give here (fig. 32). Men and various animals are here seen : a goat with wavy horns browsing on the leaf of a tree ; a rhinoceros, antelopes,



Fig 31.—Chaldæan cylinder (De Clercq collection).

There are monsters standing on their hind-legs, struggling with one another, and giants killing lions or human-faced quadrupeds. M. Menant has remarked that the figures of animals are always represented in profile, while the human figures, with long beards, are in full face even when the body is in profile. There are double-faced genii, quadrupeds with a single head and two bodies. One of the most remarkable cylinders of this primitive epoch is, without contradiction, that of the rich De Clercq collection, the design of which we give here (fig. 32). Men and various animals are here seen : a goat with wavy horns browsing on the leaf of a tree ; a rhinoceros, antelopes,

bulls, fish, an eagle, and some trees; two demons subduing fantastic animals, scorpions, and palm-trees. We think of the biblical scene of Adam and Eve in the earthly paradise surrounded by all the living beings in creation.



Fig. 32.—Chaldæan cylinder (De Clercq).

Fresh progress is marked by the appearance of inscriptions at the sides of the figured scenes. Every possessor of a cylinder makes a point of having his name or that of a favourite deity engraved upon it. Accordingly the names of several *patesis*, who governed Chaldæan towns three or four thousand years before our era, have been found upon cylinders. The cylinder on which M. Oppert read the name of Asrinilu, *patesi* of Umalnaru (fig. 33), represents an episode in the Chaldæan epic. The hero Izdubar, with curly beard and hair, seizes with each hand by a hind-leg two lions hanging head downwards. The scene is completed by trees, an antelope, a small human figure, a lion-headed scorpion, a human-headed bull. What is here especially striking is the archaism of the cuneiform signs, formed of strokes,



Fig. 33.—Chaldæan cylinder (De Clercq).

which cross one another, but have not yet the form of wedges, which they are to assume later, and also the modelling and suppleness of most of the figures; the instrument is no longer felt through the work.

Chaldæan seal-engraving reaches its apogee with another cylinder of the De Clercq collection, which has the advantage of being dated, at least relatively: it bears the name of Sargani or Sargon the First, king of Agade, about 3800 years before our era. M. Menant mentions it as marking an important stage in the history of art. The picture, which is very simple, is composed of two symmetrical scenes: Izdubar, with one knee on the ground, on the bank of a river, holds with both hands the sacred ampulla, from which a



Fig. 34.—Cylinder of Sargani (De Clercq).

double jet of water escapes, and at which a bull with long striated horns comes to drink.* Here the artist possesses all the secrets of his art: never, at any epoch, will he be able to reproduce with greater delicacy and truth the powerful muscles of the bull and the giant. And as it must certainly be admitted that monumental sculpture advances as rapidly as seal-engraving, I do not know which should astonish us most—the degree of perfection to which the Chaldæans had carried the plastic arts, or the prodigiously distant epoch to which such monuments transport us.

* Heuzey, *Un palais chaldéen*, p. 91.

A cylinder in the museum at New York (fig. 35), which from the characters of the writing seems almost contemporary with that of Sargon the First, is executed with a still greater perfection. The play and graceful suppleness of the muscles of the bull and the lion are rendered with the precision which the direct study of nature brings, and with the ease which betrays an artist who can overcome technical difficulties.

If all Chaldæan cylinders could be classed chronologically and by schools, epochs of perfection or of



Fig. 35.—Chaldæan cylinder (New York Museum, after Menant).

decadence would no doubt be observed, and also greater activity in some artistic centres than in others, the choice of subjects being modified from town to town and from age to

age. In the present state of our knowledge we can only hazard conjectures with regard to this. M. Menant looks upon the cylinders which represent the goddess Istar holding her child upon her knees and receiving the homage of the faithful, as issuing from the workshops of Uruk (Erech); it is the prototype of the divine mother whose worship is to spread even into Greece. At Ur cylinders of very different types, but of a dry execution, which is rather a mark of decadence than of archaism, were manufactured: there are scenes of worship or initiation into mysteries, and sacrifices, among which that of the kid

is the most frequent. On certain monuments M. Menant recognises a representation of human sacrifices: the most marked scene of this kind shows us a sacrificer, who, raising his right hand, brandishes a dagger over a kneeling child, whom he seems to prepare to slay, in the presence of a pontiff and of the statue of the god. One of the commonest figures on Chaldæan cylinders is that of the goddess Istar, sometimes decked with rich ornaments, sometimes entirely naked, in full face, with her hands clasping her breasts: this last type, profusely reproduced by the modellers in clay, was perpetuated all over the East up to the time of the Greek and Roman supremacies.

CHAPTER II.

ASSYRIAN ARCHITECTURE.

ASSYRIA, because she lies nearer to the mountains than Chaldæa, and because the use of stone, without ever being exclusive, was more frequent in northern than in southern Mesopotamia, has left us important ruins which have already been partly explored, and which allow us to reconstruct the forms of her architecture, without material gaps, from the ninth to the seventh century before our era. In temples, palaces, staged towers, and fortresses, the art of building is revealed to our eyes by means of the excavations of which Nineveh and its environs have been the object. But nothing is left of private architecture, and the same must be said of sepulchral architecture, or rather this latter did not exist in Assyria, which has only yielded to our explorers a few jars filled with bones. The corpses were generally carried away into Lower Chaldæa, which continued to be for long ages a sort of *Campo Santo*, or vast cemetery at the service of the inhabitants of all Mesopotamia. Down to the present day, the Persians, even of the most distant provinces, make a point of having their dead buried at Nejef and Kerbela, near the mosque of Ali, the great saint of the Shiitè Mussulmans. This traditional superstition is turned to profit by a company of carriers, who annually

transport more than ten thousand corpses. The necropolis of Mugheir and the surrounding tells belongs therefore both to Chaldæa and to Assyria; corpses are piled up there by hundreds of thousands, but beyond the system of drainage, organised in order to catch the rain-water, it offers nothing of great interest. There were no sepulchral monuments; and as for the tombs themselves, they are generally little brick structures with nothing remarkable about them; the furniture consisting of terra-cotta vases and figurines, amulets and cylinders, is of the most wretched description.

The principal buildings of Assyria, which have been methodically and almost completely explored, are those of Khorsabad, some leagues to the north of Nineveh, and those of Kouyunjik and Nimroud.



Fig. 36.—Tomb at Warka (after Taylor).

Several hillocks in which a collection of important structures would with equal certainty be found, such as the hill of Nebi Yunus, where Arab tradition fixes the tomb of the prophet Jonah, and Arvil on the site of Arbela, have not yet been tested by the explorer's pick; others, such as the artificial mounds of Kalah Shergat, Balawat, and Karamles, have only been incompletely explored, and though epigraphic material, extremely valuable for history, and bas-reliefs of the highest artistic interest, have been extracted from them, from the architectural point of view at least their imperfect excavation teaches us nothing new.

The Babylonian buildings of the epoch of Nebuchadnezzar and Nabonidus must have resembled the Ninevite palaces and temples in form and architectural arrangement ; but up to the present time we can only speak of them by conjecture, or according to the inexact descriptions of Greek travellers, and we cannot regret too much that the enormous Babylonian tells, such as those called the Kasr or Palace, Tell Amran, Babil and Birs Nimroud have yielded hardly anything yet of their archæological treasures. We must, then, for the present, confine ourselves to the description of the ruins of Khorsabad, Nimroud, and Kouyunjik, in order to reconstruct the principal forms of Mesopotamian architecture at the most splendid period of the Ninevite empire.

§ I. PRINCIPLES OF CONSTRUCTION.

The limestone which is furnished in abundance by the lowest spurs of the mountains of Kurdistan enabled the architects of Nineveh not to employ brick exclusively, and sometimes to erect walls of trimmed ashlar. They used limestone especially for the basements of the buildings, which were more particularly exposed to the action of damp, so fatal to crude brick ; they also had recourse to it for the construction of the ramparts of the royal palaces. But even here, on account of the dearness of the materials, which it was necessary to seek at a distance and to spend much time in hewing, stone is only employed for the outer facing of the wall ; the builders use it sparingly, and are as niggardly of it as they are prodigal of brick. Accordingly, the

walls which enclose the terrace of Sargon's palace at Khorsabad are only of stone on the surface; the interior, or rather the nucleus of the structure, is of brick. The blocks on their external and visible surface are of variable length, but are placed upon one another in very regular courses of equal height and with crossed joints. Headers penetrate like wedges into the mass of the terrace to ease the layers of brick and bind them to the stone structure. In the lower courses of the rampart of the palace



Fig. 37.—Masonry at Khorsabad (after Place).

at Khorsabad there are regularly hewn blocks from 8 ft. 2 in. to 9 ft. 10 in. square; the blocks diminish in volume in proportion to the nearness of the layers to the summit of the rampart, which was 59 ft. high, including the battlements, which formed a parapet all round the terrace.




Fig. 38.—Section of wall at Khorsabad (after Place).

The interior or exterior walls of the building which stood upon this gigantic base had no need to fear the infiltration of water or the attacks of enemies: their solidity might be lessened without inconvenience, by economising the stone. As a matter of fact, they are of brick, baked or crude, and stone is scarcely employed in them except for the lining and paving of a few rooms. In that case great slabs of limestone or gypsum are set upright as a plinth against the lower part of the wall, to preserve it from corrosion; they are adjusted end

to end by the edge, and it was sufficient, in order to fix them, to pour between their posterior surface and the wall mortar which often only imperfectly adhered : the outer and only visible surface of these slabs was decorated with bas-reliefs which served for the adornment of the halls. As for the walls themselves, they were straight and perpendicular in contrast to those of the Egyptian buildings, which, seen from without, seem to lean inwards, and give to the whole building the appearance of a truncated pyramid. The Assyrian walls rise vertically, even when they enclose vaulted chambers, or when they form part of staged pyramids ; each stage forms a perpendicular terrace, not a sloping one.

It has been observed that the partitions which separate the halls sometimes look like one block set up on end ; the joints and the courses of the brickwork cannot be detected, to such an extent have the constructing materials been soldered together in a perfect amalgam of beaten clay. This peculiarity, noticed by Victor Place at Khorsabad, can only be explained by admitting that the bricks were employed in the building while they were still saturated with water, and before the process of drying was finished. Their natural dampness, added to that of the clayey mortar which bound them to one another, has formed a sort of muddy paste which must have taken years to harden, but which was particularly effective against the disintegration of the wall, since it became in this way entirely homogeneous. It was the extraordinary thickness of these walls which prevented them from giving way under their own weight, and even allowed them to uphold those heavy

beds of clay which form the vaults and terraces of the houses. They thus protected the halls most effectively from the ardent heat of the sun. At the present day the inhabitants of Bagdad and Mosoul take refuge, during summer, in their *sirdab*, a half-underground room with extremely thick brick walls, the single opening of which looks to the north. The people of Nineveh and Babylon, subject to the same climatic conditions, certainly acted in the same manner. As for the princes, they had, to defend them against the sun, walls from 13 ft. to 26 ft. thick, and vaultings as enormous as the walls. Nevertheless, the mode of building with clay which we have just noticed was very defective ; this is the weak side of Ninevite and Babylonian buildings, and we understand why the kings are unceasingly obliged, as they relate in their inscriptions, to repair or rebuild walls which crumble under the dissolving action of water from the sky.

The unusual thickness of the walls, the long, narrow form of all the chambers, are also justified by the employment of the vault as the essential element of the Assyrian buildings. V. Place unearthed at Khorsabad a great doorway surmounted by a semicircular arch. The sides of the doorway, as well as the arch itself, are of brick ; there are three rows of voussoirs one above the other, forming as it were three concentric door-frames half-fitting into one another. All the voussoirs, which have issued from a single mould, have a slightly trapezoidal shape, like the stone voussoirs of our most carefully built edifices. The height of the doorway, under the keystone, is 19 ft. 8 in., and the breadth 11 ft. At other points, Place recognised that the enormous

accumulation of materials which filled up the halls could only come from the falling in of the clay vaults. Some blocks still, at the time of the excavations, formed an arch, sometimes several yards in diameter, solid enough to serve as shelter for the shepherds of the neighbourhood; they were, on the concave side, covered with carefully laid stucco, or with paintings in fresco—a circumstance which proves positively that these blocks are sections of crumbled vaults.




Fig. 39.—Vaulted and domed houses
(after Layard).

The square chambers were surmounted by a dome; there are in the palace of Sargon two of these rooms as much as $44\frac{1}{2}$ ft. square. In a bas-relief discovered at Kouyunjik (fig. 39) a group of houses figures, among which some are surmounted by hemispherical cupolas, others by elongated domes in

the form of sugar-loaves. The houses of Babylon were vaulted, as Strabo tells us. The Mesopotamian palaces of the Achæmenid, Parthian, or Sassanian epoch, the halls of which are surmounted by domes which scarcely yield in boldness to those of St. Sophia, evidently only handed on the Assyro-Chaldæan tradition which is also represented before our eyes by the modern houses of Mosul, Bagdad and southern Persia. The technical methods of contemporary masons also do not fail to make known to us what steps their ancestors of the time

of Sargon or Nebuchadnezzar took to supply the want of wood, and in consequence to do without a previous arched framework: travellers tell us that they have observed the commonest workmen of the country erecting their hemispherical or elliptical cupolas by layers in rings, laid one above the other, and narrowing in proportion to their nearness to the keystone; it is the same principle as that of the corbelled vaulting.

The place where it has been possible to observe the employment of the vault in the architecture of the Assyrian palaces, is in the very bowels of the basements of these edifices. A vast corridor, surmounted by a semicircular vaulting, was discovered by the English



Fig. 40.—Vaulted drain (after Layard).

explorers, in the flanks of the mound of Nimroud; the lower courses are of enormous slabs of stone, all the rest is brick. In the scientific system of drains which carried off the sewage of the palace of Sargon, Place distinguished every kind of vaulting: the pointed or ogival vault, the semicircular vault, the flat-arched vault, the shallow vault, the elliptical vault.

Never, at any point in their history, did the Egyptians

or the Romans push the application of the vault to an equal degree of perfection. In most of the halls of Sargon's palace a slab pierced with a hole was remarked in the middle of the bricks which form the pavement: this was the orifice of a vertical conduit opening into a vaulted drain concealed in the terrace. One of these drains had an ogival vaulting, the description of which we will borrow from MM. Perrot and Chipiez.* "The bricks composing it are trapezoidal in shape, two of their sides being slightly rounded—the one concave, the other convex. The radius of this curve varies with each




Fig. 41.—Vaulted drain at Khorsabad (after Place).

brick, being governed by its destined place in the vault. These bricks go therefore in pairs, and as there are four courses of bricks on each side of the vault, four separate and different moulds would be required, besides a fifth, of which we shall presently have to speak. The four narrow sides of these bricks differ sensibly from one another. The two curved faces, being at different distances from the centre, are of unequal lengths; while, as the lower oblique edge is some inches below the upper in the curve, these two edges have different directions. In their disinclination to use stone voussoirs the Assyrian

* *History of Art in Assyria and Chaldæa*, vol. i., p. 228 f. [Eng Ed.]

builders here found themselves compelled to mould bricks of very complicated form, and the way in which they accomplished their task speaks volumes for their skill." The two upper voussoirs meeting and touching one another by one of their corners, the triangular space left empty between their edges was filled up either by wedge-shaped bricks or by mortar. The drain which we have just given as an example is 4 ft. 7 in. high under the keystone and 3 ft. 8 in. broad ;

the explorers were able to follow it to a length of 216 feet. To facilitate its construction the architect conceived the ingenious idea of building it upon an inclined plane—that is to say, that all the rows of voussoirs,

instead of being perpendicular, lean considerably backwards, and are supported one upon the other ; this system, which did not at all affect the solidity of the vaulting, allowed the builders to do without circular wooden frames.

So much technical skill devoted to the construction of simple subterranean conduits makes us particularly regret that the deplorable quality of the material did not allow the vaults and domes of the palaces to exist till our day. However, there were not only vaulted halls in the Ninevite buildings ; a certain number of them were




Fig. 42.—Vaulted drain at Khorsabad.
Slope of the bricks (after Place).

covered by flat roofs formed of beams of palm-wood, poplar-wood or cedar-wood, which supported light terraces. The bas-relief at Kouyunjik which we cited above shows us flat roofs side by side with parabolic and spheroidal cupolas. Nevertheless, what we said about the use of stone in the Ninevite structures we can repeat here on the subject of timber. Nineveh, not being too remote from the wooded mountains of Armenia, Kurdistan and Masius, where forests of pines, beeches, and oaks grow, did not deprive herself of the use of these woods in her structures; she had panelled halls in her palaces, and, at the apogee of her power, when thousands and thousands of slaves placed their strength at the service of her monarchs, she had the timber of the Amanus and the Lebanon transported into her buildings. The king Assur-nasir-pal (B.C. 882-857) relates in one of his inscriptions that he had an enormous quantity of pines, cedars, and oaks cut down in the Amanus and the Lebanon in order to have them carried to Nineveh, and to employ them in the construction of his palace and the temples of his favourite gods. Other princes, such as Sargon, Sennacherib, Assurbanipal and Nebuchadnezzar, make the same boast of having utilised, in the buildings which they erected or repaired, beams brought from the Amanus and the Lebanon. "I caused the tallest cedars of Lebanon," says Nebuchadnezzar, "to be brought to Babylon; the sanctuary of E-Kua, in which the god Marduk dwells, was freshly covered with beams of cedar-wood."* This is the wood of resinous nature, "the odour of which is good," add the inscriptions.

* Lenormant and Babelon, *Hist. Anc. de l'Orient*, vol. iv., p. 411.

At the British Museum fragments of a cedar beam, collected among the ruins of Assur-nasir-pal's palace at Nimroud, are preserved. Who will ever be able to say what efforts and how many human lives were required to transport these gigantic rafters across a rough country without any roads for traffic, from the Lebanon as far as the banks of the Tigris and Euphrates? Accordingly it may be affirmed that the use of wood was always exceptional in the Chaldæo-Assyrian structures; it was never introduced except as an exotic element, of which the monarchs boast on account of its rarity. The climate and the nature of the Mesopotamian soil were better suited by thick vaultings, which, then as at the present day, never ceased to be the rule there.

Quite as little as the Chaldæans, and for the same motives, did the Assyrians make a frequent and regular use of the column as an element of their architecture. Victor Place notices, like the explorers of Lower Chaldæa, several façades in the palace of Sargon adorned with pilasters and half-columns of brick, projecting beyond the plane of the walls, and having no object except to relieve the monotony of the structure. Perhaps, too, these half-columns, which are found in groups of seven, had, like the two famous pillars in the Temple of Solomon, a mystical and symbolical meaning, the number seven playing an essential part among the mythological conceptions of the Chaldæo-Assyrians. Elsewhere a few bases of columns and a few monolithic capitals have been found, which prove that the Assyrians used stone supports for monumental porches, as we ascertained in the palace of Tello. A fragment of a bas-relief preserved at the British Museum, and coming

from the palace of Assurbanipal, shows us (fig. 43) the façade of a great building adorned with a projecting roof, supported by four pilasters and four columns.




Fig. 43.—Façade with pilasters (from bas-relief in British Museum representing Babylon).

The base of these columns rests on the back of gigantic lions, which seem to advance to meet one another, two and two. On the back of the lion the architect has placed a coussinet, surmounted by a torus and by the stem of the column. In the ruins of the palace of Kouyunjik, four bases of columns were found still in place, and seeming to belong to a covered gallery; there were also two small winged bulls with human heads, crowned with the tiara, and supporting on their back a spheroidal base decorated with geometrical designs in relief. At Nimroud Sir A. H. Layard noticed also two crouching sphinxes bearing bases of columns (fig. 44); according to the same architectural principle the foot of the arches rested upon the gigantic bulls which flanked the chief entrances of the palaces.



Fig. 44.—Base of column (after Layard).

The stem of the columns was probably of wood, painted or covered with a metallic envelope. Round the inner courtyards there were, as in the courts of oriental palaces in our own day, porticoes formed of cedar beams resting on bases analogous to those which we

have just noticed. Strabo* reminds us that in Babylon beams of palm-wood were used in the construction of houses: "They are careful," he says, "to wrap round each palm-wood pillar with rush-cords, which are then covered with several coats of paint." Things were not done quite in this way in the houses of the rich and in princely residences. A fragment of a cedar beam of the size of a man was discovered at Khorsabad.




Fig. 45.—Assyrian capital (after Place, *Ninive et l'Assyrie*, pl. 35).

It was still overlaid with a plating of bronze decorated with designs in *repoussé*, which imitate the bark of a palm-trunk.

An enormous block of limestone, 39 ft. 3 in. high, brought to light at Khorsabad, comprises an entire capital and a part of the stem at the same time (fig. 45); it is almost the only Assyrian capital known. It affects the spheroidal form, and its convex part is decorated with a double line of curved festoons in relief; there was a similar ornament, no doubt, at the base. Several capitals



Fig. 46.—Capital of Sassanian period from Warka (British Museum).

from Warka are also preserved at the British Museum, but they were found among ruins of the Sassanian epoch. Nevertheless the resemblance which some of

* xvi., 1, 5.

them bear to the architectural features of the bas-reliefs is so close that they are probably representatives of a style inherited from a former period. They are of that form, so well known in the sculptures, which has the character of the Ionic order, and was probably its original.

In imitation of their southern neighbours the Assyrians used the column especially in chapels of little importance, in which the supports had no vault or terrace to uphold. Bas-reliefs from Khorsabad and Kouyunjik represent sanctuaries the roof of which is supported by small columns with a base and a capital, which partake at




Fig. 47.—Shrine with columns (Botta, *Les Monuments de Ninive*, pl. 114).

once of the Ionic and of the Doric order of the Greeks (fig. 47). These little structures recall the Chaldæan shrine of the god Samas (fig. 29). An object which appears to be the base of a small column exists in the Nimroud Gallery of the British Museum. It is of sandstone, and, to judge from its size, it must have formed part of a small chapel or shrine, such as we see in the sculptures. The ornamental design upon

it is partly similar to that of the large capital figured above, but presents some variations from it. There is a small hole into which the pillar was doubtless fastened by a peg or metal dowel.

The Assyrian palace, like Arab houses, developed itself entirely in area, and not in height; there was rarely a second story on the platform. Nevertheless such a second story exists sometimes; it is then open at the sides, and the roof is supported by small columns.

These columns, of wood rather than of stone or brick, form a gallery over the façade, and they are adorned at their upper extremity with a double volute as a capital. Bas-reliefs show us houses thus surmounted by a colonnade, which



Fig. 48.—Base of small column
(British Museum).

supports a light, flat roof of wooden beams. At the present day, houses in Kurdistan are still built on the same lines, and show an identical arrangement in two stories; the lower without windows, the upper open at the sides.

In a word, the Assyrians, like the Chaldæans, not having at their disposal building-stone in great abundance, were obliged to construct their edifices almost exclusively of brick, the capabilities of which they tried to the utmost. The result of this was that they never had those halls of columns which are the triumph of

Egyptian architecture. However thick one may suppose pillars of brick, or columns formed of bricks moulded in the shape of segments of a circle, to be, these supports will never offer the same guarantee of solidity as the stone column. Wherever a heavy burden, such as a vault or a terrace, had to be supported, great walls were raised of an extraordinary thickness, which it would have been imprudent to pierce with windows capable of diminishing its resistance. Air and light only penetrated into the apartments by the doors; often, too, an opening was contrived at the summit of the vault or dome, formed of a cylindrical pipe of burnt clay carried through the entire thickness of the structure.

§ II. PALACES.

The town of Dur-Sarrukin (the Fortress of Sargon) stood three leagues north of Nineveh, on the Khaswer, one of the branches of the Tigris, where the Kurdish village of Khorsabad has been built. Discovered in 1843 by E. Botta, French Consul at Mosoul, it was almost completely excavated by this illustrious explorer and his successor, Victor Place, and it is from Khorsabad that most of the Assyrian monuments in the Louvre come. It was the custom that each of the Ninevite monarchs should have a special palace built at some distance from the great Assyrian capital, and this became the royal residence round which stood the dwellings of the court-officers, the guards, the servants, and all persons who depended upon the prince or lived at his expense. Dur-Sarrukin was built by Sargon, the father of Sennacherib, about the year 710 before

our era. The palace and the town which was annexed to it formed a group of structures contained within a fortified enclosure (fig. 49) the plan of which was a square of 5905 feet.

The wall of circumvallation, the angles of which pointed to the four quarters of the heavens, as in the Chaldæan buildings, was crowned with battlements and pierced by eight gates protected by towers.

The king's palace (fig. 50) stood almost in the middle of the north-eastern façade, and a part of its structure which projected beyond the ramparts had the appearance of an enormous bastion. The structure of this palace was supported by a platform which formed




Fig. 49.—Plan of Dur-Sarrukin
(after Place, pl. 2).

an acropolis nearly twenty-five acres in area. The mass of clay which had to be brought to raise the terrace and the walls of the palace has been estimated at 48,233,000 cubic feet. The platform overlooked the town, and was reached by staircases, destroyed at the present day, but which must have been analogous to the monumental staircase which formed the ascent to the palace of Sennacherib, and

the traces of which Sir A. H. Layard recognised. As at Tello, a gentle ascent on an inclined plane was formed for the passage of vehicles. The royal apartments built upon the terrace comprised no less than



Fig. 50.—Plan of the palace of Sargon (after Place, pl. 7).

two hundred and nine more or less spacious rooms, the walls of which, laid bare by Botta and Place, are still sometimes twenty-six feet high and always reach at least ten feet in the parts most demolished. It was not easy to determine the destination of these different halls. However, by comparison with the

present Turkish and Persian palaces, in which an analogous arrangement has been perpetuated, with the same usages, the following parts have been distinguished at Dur-Sarrukin as in the palace of Tello: the *seraglio*, that is to say, the reception-rooms and the dwelling-rooms of the prince and the men attached to his person; the *hareem*, or apartments of the women and their children; the *khan*, or the residence of the slaves, the kitchens, the stables, and the offices. The *seraglio*,




Fig. 51.—South-eastern façade of the palace of Sargon (restoration by Place, pl. 20).

the most luxurious and most highly decorated part, included ten courts and more than sixty rooms, adorned with those bas-reliefs in stone which are now the glory of the Louvre. They were paved with square bricks fixed in bitumen. Where the ground was not to be covered with carpet, as before the door, there was a stone pavement in which the designs, skilfully carved in relief, imitated those of the carpets themselves. To the buildings of the *seraglio*, situated on the north-east, is attached the staged tower of which we shall speak farther on. The principal court of the *seraglio* had an

area of 3,202 square feet, and eight doors formed a means of communication between it and the rooms of this part of the palace ; most of these openings are flanked with colossal lions or bulls supporting the feet of semicircular arches. The *hareem*, which occupied, on the south, a surface of more than 94,726 square feet, formed a group of structures communicating with the rest of the palace by two doors only. It was, with its lofty blind walls, a sort of prison in the very bosom of the fortress. Within, there were several courts and isolated suites of rooms, in which the apartments of the women were separately arranged. The walls of the principal court must have been decorated with true Asiatic luxury, for the foot of these walls, when they were laid bare about fifty years ago, was still covered with a lining of enamelled bricks representing animals and mythological scenes. It was here that the shaft of a column was found, of wood covered with a bronze sheath, so that it is not rash to affirm that this court was furnished with a portico all round, and perhaps even with an upper story with open sides. The *khan*, situated towards the eastern angle of the structure, occupied an even larger space than the *hareem* ; the treasury or *bit kutalli*, the cellars, granaries, and storehouse of domestic utensils, have been distinctly recognized, as well as magazines of objects of all sorts, carried off as plunder by Sargon in his expeditions, and weapons of the chase and of war : in the very stables, the presence of iron rings fixed in the wall has been ascertained, to which horses and camels were attached : lastly, the small but numerous rooms of the servants and slaves have been excavated. Ctesias brings the number of persons attached to the service of the palace of the




Fig. 52.— Bird's-eye view of the palace of Sargn at Khorsabad (restoration by Place, pl. 18 bis).

kings of Persia up to fifteen thousand : it may easily be supposed that an equal number of hands was employed at the court of the haughty king of Nineveh.

The palace of Sargon, the best-preserved of Assyrian edifices, and that of which the excavation was directed with the greatest consistency and method, deserved to be taken as the most perfect type of the Ninevite palaces. The researches of the English explorers, Sir A. H. Layard, Sir H. Rawlinson, G. Smith, and H. Rassam, have procured, it is true, for the British Museum the incomparable galleries of Assyrian monuments known as those of Nimroud and Kouyunjik from the name of the principal tells explored ; they have made known the site of the royal residences of Assur-nasir-pal, Shalmaneser, Sennacherib, Esarhaddon, Assur-bani-pal, and exhumed the fine sculptures which decorated their halls ; but from the architectural point of view these excavations teach us nothing remarkable and original, or rather they only confirm what we know of the art of building among the Assyrians from the study of Khor-sabad ; the elements and principles of building show themselves to be identical throughout, and, save for secondary modifications and variable proportions, it may be said that the arrangement and adornment of Assyrian palaces were everywhere the same, and issued from an uniform type created in Chaldæa, which was never remarkably modified.

§ III. TEMPLES AND STAGED TOWERS.

It was also in Chaldæa, as we have seen, that those towers in stages (*sikkurat*) were invented, painted in


bright and varied colours, which constitute one of the original features of Mesopotamian architecture. If the staged towers of Mugheir, Tello and Abu Shahrein, are too much destroyed for us to be able to restore their different steps except in thought, we are sure, nevertheless, that these old Chaldæan edifices were similar to the towers the lower stories of which were excavated at Kouyunjik, Nimroud, Khorsabad, and finally at Babylon, where stood, from the remotest antiquity, the two famous temples called E-saggil and E-zida and where Nebuchadnezzar built, according to the testimony of his inscriptions, the famous Tower of the Seven Lights. Who can say whether this architectural form was not inspired by the sight of the pyramids in steps of the Nile valley? In any case the Greek historians agree in affirming that the staged towers were of a height comparable to that of the loftiest Egyptian pyramids, and the mass of the mounds of débris which represent the ruins of these towers is a sure warrant of this assertion. Birs-Nimroud at Babylon is still, at the present day, 235 feet high, and it has certainly lost at least half of its primitive height. The ruin of Babil is still 130 feet high. What European monument is there, even if built of hewn stone, which, after crumbling in upon itself, would reach 130 feet after thirty centuries of ruin and decay? It is improbable, then, that Strabo deserves to be taxed with exaggeration when he assigns the height of a stadium or 591 ft. 9 in., to the temple of Bel at Babylon. Herodotus describes the same building in the following manner: "This temple is square, and each side is two stadia in length (1,183 ft. 6 in.). In the centre is a massive tower, of one stadium in

length and breadth; on this tower stands another tower, and another again upon this, and so on up to eight. A spiral staircase has been built outside leading round all the towers. Towards the middle of the ascent there is a room, and there are seats upon which visitors rest; upon the last tower stands a large shrine, in which is a large bed with rich coverings, and near it a golden table." Modern excavations enable us to affirm that this description is exact in all points, and that all the staged towers of Assyria and Chaldæa were constructed upon the same principle.

The *zikkurat* of the palace at Khorsabad, placed to the east of the seraglio buildings, has still at the present day three complete steps and the beginning of a fourth; the first describes on the ground a square of 141 ft. each way; each stage is 20 feet high, which gives us reason to believe that the structure was as high as it was broad at the base—a peculiarity already noted by Herodotus and Strabo in the temple of Bel. The stages laid bare by the French excavations were still partly coloured by means of enamelled stucco, the lowest stage white, the second black, the third reddish purple, the fourth blue. Among the ruins of the tower were found numerous fragments of enamelled bricks, coloured vermilion, silver grey and gold, which proves that the tower had seven stages of different colours. It has been remarked that Herodotus (i. 98), gives to the fortress of Ecbatana, in Media, the arrangement of a gigantic tower in stages, the colours of which are similar to those of the *zikkurat* of Khorsabad. There were, according to him, seven concentric enclosures, the most spacious being as large as Athens, while the

battlements of each enclosure rose higher than those outside them. "The battlements of the first wall are of white stone; those of the second of black stone; those of the fourth blue; those of the fifth vermilion. . . . The two last walls are plated, the one with silver, the other with gold."

The explorers of Mugheir thought that they recognised, in spite of the bad state of the ruins, that the *zikkurat* of Ur was constructed in such a way that the stages did not rise exactly in the middle of the square platform of the lower stage which served as their base; they were nearer to one of the sides, so that they present on one side much narrower terraces than on the other three. This



observation is confirmed by a bas-relief

Fig. 53.—The staged tower of Khorsabad (restoration by V. Place).

in the British Museum, unfortunately very rough, in which, however, we distinguish clearly the greater width of the terraces on one side and their corresponding narrowness on the other. On the other hand the slope of each terrace proves that it ascended like a screw, and that there was no staircase cut in each of the stages to put them in communication with each other. This is, moreover, what is observed at Khorsabad: the ascent to the summit of the ruins of the fourth stage is by a quadrangular sloping path which mounts gently as it winds round in a spiral form.

Diodorus Siculus informs us that the top of the staged towers was occupied by statues, for which the zikkurat would only form a sort of pedestal: "At the summit of the ascent," he says, "Semiramis placed three golden statues wrought with the hammer." These statues were perhaps in the interior of the sanctuary which generally crowned the building; everything makes it probable also that little chapels were constructed at each stage in the thickness of the structure, and that each of them was consecrated to the stellar deity of whom the colour of the stage was emblematic. The chapel on the summit was covered by a gilded cupola, which glittered under the glorious sunlight of the pure eastern sky, and dazzled all beholders. Nebuchadnezzar relates in his inscriptions that he overlaid the dome of the sanctuary of Bel Marduk "with plates of wrought gold so that it shone like the day." Does not Herodotus tell us that the last stage of the citadel of Ecbatana was gilded? Finally, Taylor picked up among the ruins on the summit of the *zikkurat* at Abu Shahrein, a large quantity of thin plates of gold, still furnished with the gilded nails, which had served to fix them to the walls.

Besides these sanctuaries erected on the top of staged towers, in which the priests passed the night in watching the courses of the stars, there were other temples not provided with similar basements. Thus, on a bas-relief from the palace of Sargon, we see a representation of the pillage of the temple of the god Haldia at Musasir, in Armenia (fig. 54). This sanctuary, built upon a terrace like that of a palace, has a façade decorated with a triangular pediment, like a Greek

temple. Instead of a portico with columns to support the pediment, there are thick pilasters to the number of six, adorned at intervals with projecting horizontal lines, and with disks, which are seen upon the façade also, and may be taken for votive bucklers. Between the two middle pilasters is the door of the temple, the opening of which is enclosed by an architrave in stone; on each side of the door and of the same height as it, are two colossal genii in human form, carved in stone and hold-



Fig. 54.—Temple of the god Haldia
(after a bas-relief at Khorsabad, Botta, pl. 141).

ing lances, the points of which rise even higher than the pillars; behind them are lions; lastly, some distance in front of the door, two gigantic basins, probably of bronze, resting on tripods, recall the great vessel found before the façade of the palace of Tello, the brazen sea in the temple of Solomon, the vase from the temple of Amathus: they were basins for lustral water.

The description given by Herodotus and the author of *Bel and the Dragon* of the famous temple of Bel-Marduk,

in Babylon, acquaints us somewhat closely with the interior arrangement of the chapel which crowned the *sikkurat*. There was nothing, Herodotus relates, in the way of furniture but a bed and a golden table ; the walls were panelled with plates of gold, silver, and ivory. The evidence of the Greek historian is confirmed by the text of the cuneiform inscriptions : " I conceived the idea," says Nebuchadnezzar, " of restoring E-saggil, the temple of Marduk. I had the tallest cedars brought from Lebanon ; the sanctuary of E-kua, in which the god dwells, was covered with cedar beams and overlaid with gold and silver." Elsewhere relating the construction of the tower of Borsippa, where stood the temple of E-zida consecrated to the god Nebo, the same prince expresses himself as follows : " In the middle of Borsippa I rebuilt E-zida, the eternal house. I raised it to the highest degree of magnificence with gold, silver, other metals, stone, enamelled bricks, beams of pine and cedar wood. I covered with gold the wood of Nebo's resting-place. The posts of the door of oracles were plated with silver. I encrusted with ivory the posts, the threshold and the lintel of the door of the resting-place. I covered with silver the cedar posts of the door of the women's chamber." On the golden table in the temple of Marduk, Nebuchadnezzar lays, as he recounts himself, offerings of every kind : honey, cream, milk, refined oil ; to draw upon himself heavenly blessings he pours out great draughts of the wine of different countries into the goblet of Marduk, and Zarpanit the Babylonian Astarte.*

* Lenormant and Babelon, *Hist. anc. de l'Orient*, v. iv., p. 412.

§ IV. TOWNS AND THEIR FORTIFICATIONS.

In his description of Babylon, as Nebuchadnezzar and the kings of his dynasty made it, Herodotus expresses himself as follows: "This city, situated in a vast plain, forms a perfect square of which each side is 120 stadia long, so that the circumference is 480 stadia." Pausanias says that Babylon was the greatest city that the sun had ever seen in his course; Aristotle seems to compare it to the Peloponnese in size.* Classical authors also assign to the walls of the Chaldæan capital a height of 200 royal cubits (342 ft.) and a thickness of 85 ft. They are said to be pierced by a hundred gates, flanked by two hundred and fifty towers and protected by a large moat, into which the waters of the Euphrates were turned. The exactness of these descriptions, which at first might seem hyperbolic, has been confirmed, as far as the thickness of the walls is concerned, by the excavations at Khorsabad, the ramparts of which are 78 ft. and even 90 ft. thick where they are furnished with bastions. The extent of the city itself was verified on the spot between 1852 and 1854 by the French expedition to Mesopotamia. The great enclosure of Babylon, that is to say, the enlarged Babylon of Nebuchadnezzar, according to M. Oppert, is 199 square miles in area—that is to say, seven times the extent of the fortified enclosure of

* What Aristotle really says is: "It is not a wall that makes a city, for the Peloponnese might be enclosed within a wall. Babylon, perhaps, is a city of such sort, and so is any other, the walls of which enclose a nation rather than a city. They say that when Babylon had been taken for three days part of the inhabitants were unaware of the fact."—Pol. i. 3.

Paris. A raised road, 196 ft. broad, ran along the interior of this rampart, and separated it from the interior wall, itself four times as long as the circumference of Paris; the two concentric walls bear in the cuneiform texts the names of *Imgur Bel* and *Nimitti Bel*. A view of the walls of Babylon seems to be given in one of the bas-reliefs from Kouyunjik, which represent




Fig. 55.—Walls of Babylon (British Museum).

the campaign of Assurbanipal against his brother Samas-sum-ukin, king of Babylon (B.C. 651-648). Nebuchadnezzar says that his own father Nabopolassar began to build the walls, and that he himself finished them; but this does not mean that the earlier city, called by Herodotus the Royal City, was not surrounded, as in the bas-relief, by a double wall like the later. Diodorus says that Semiramis surrounded the western part of the city with three walls, and two of these are

identified by M. Oppert.* Fifty principal streets, twenty-five of which were parallel to the Euphrates, and twenty-five at right angles to it, leading to the hundred gates, divided the city into regular squares; a single bridge, formed of wooden planks resting on stone piles, was thrown across the Euphrates, which cut the city in two diagonally. The limits of the wall of Nineveh are not yet exactly known; but the testimony of the Bible gives us reason to believe that this city scarcely yielded in point of size to Babylon. The best mode of reconciling the statements of modern explorers with those of the Book of Jonah and the historian Ctesias, is, perhaps, to adopt the suggestion of Schrader,† and to suppose that “the Great City” of Genesis x. 12 was a group composed of the four towns




Fig. 56.—Chaldæan plan of a fortress.

there enumerated, of which Nineveh proper was the chief, and gave its name to the whole group.

In the absence of textual evidence, the very sculptures of the Assyrians place before our eyes numerous fortresses in plan or in a bird's-eye view. One of the statues from Tello represents the patesi Gudea as an architect, holding on his knees a tablet on which is carved in outline the plan of a stronghold (fig. 56). There are six gates flanked by towers, and the walls are surmounted by battlements. In all the bas-reliefs

* *Exp. en Mésopotamie*, t. i., p. 194 ff.

† *Cun. Inscr. and the O. T.*, vol. i., p. 79.

in which sieges are represented, the fortress is seen to be composed of several concentric walls supported by towers of greater elevation than the rampart from which they project, and surmounted by denticulated battlements (figs. 58 and 74), which stand out on corbels beyond the perpendicular surface of the wall.

Might we not imagine ourselves in presence of a naïve miniature of the middle ages, representing the siege of a feudal castle, when we examine in the



Fig. 57.—Assyrian plan of a fortress (from a bas-relief in the British Museum).

galleries of our museums these Assyrian bas-reliefs, on which are carved the sieges of fortresses, which to defend themselves against battering-rams, arrows, and projectiles of all sorts, are provided with redans and round towers, battlemented, pierced with loopholes, and furnished with a system of defence which looks like *ourdeys* and machicolations?

As in the middle ages, a gate is never opened in the wall of a fortified enclosure without being provided with a drawbridge, sheltered by two strong towers, and defended by a projecting structure composed of another rampart and two new bastions. The gate is the weak point; it is the flaw in the cuirass, the natural breach by which the enemy might enter: every system of defence is there ingeniously accumulated, and the walls are thicker at that point. These tall towers, these thick walls were guarded by bodies

of soldiers always on the look-out, who found here a pleasant shade to protect them from a scorching sun, to which even the inhabitants of the city found their way when they met to discuss their affairs or to converse upon the news of the day. On each side of these long passages recesses were made, and even actual halls for the guards. Several of the dramas related in the Biblical books are developed in such places, under such vaults. The present state of one of the entrances of Khorsabad enables us to ascertain that the custom of assembling at the city gate goes back to the time of the Chaldæo-Assyrians. This gate was still surmounted by its semi-circular arch decorated with an archivolt in enamelled bricks. The structure formed a projection of 82 feet from the wall ; built on a rectangular plan, it was itself pierced by an opening defended by two projecting bastions. After passing through this first structure, a court was reached which gave access to the opening



Fig. 58.—Siege of a fortress (from a bas-relief in the British Museum).

in the rampart proper flanked by two square towers. Through this gate a second court was reached, separated




Fig. 59.—Plan of a gate at Khorsabad (after Place, pl. 18).

again from a third court by a new opening; lastly, the wall at the bottom of this third court had again an aperture which gave access to the town. Thus it was necessary to pass successively through

four doors to penetrate into Dur-Sarrukin, and a structure, symmetrical with that on the outside, projected from the wall into the interior of the fortress. These massive structures formed by themselves a real stronghold, 22,965 feet square, with vaulted passages and galleries, the chief of which is not less than 278 ft. long. It is clear that such buildings, which would invariably serve as




Fig. 60.—Gate of Khorsabad (restoration by Place, pl. 8).

meeting-places, form fresh and cool retreats in countries where the heat is such that it was impossible to gather in the Forum or in the Agora, as at Rome or Athens.

CHAPTER III.

ASSYRIAN SCULPTURE AND PAINTING.

§ I. STATUES, STELÆ, AND OBELISKS.

THE brilliant period of Chaldæan statuary, which reached the apogee of its development in the monuments of Tello, came to an end with the fall of the petty principalities which flourished in Lower Mesopotamia before the Ninevite supremacy. Chaldæan statuary did not emigrate to Assyria with the other arts, or rather the Assyrians disdained to receive it. The principal cause which prevented this art from developing among the Ninevites was the nearness of the alabaster quarries, and the absence of marble, diorite, porphyry and other kinds of stone which allow of being carved in the round. Alabaster can only be hewn in thin, flat pieces, which, for this reason, lend themselves admirably to be carved in bas-relief, but are unsuitable for statuary. An alabaster statue of ordinary human proportions would be extremely fragile, and would run the risk of crumbling away in flakes, at any rate in the thinnest parts, such as the feet and hands. On the other hand, the abundance of alabaster in the neighbourhood of Nineveh caused the Assyrians to dispense with the importation from distant countries, at great cost, of blocks of diorite and porphyry like those which the Chaldæans, who

possessed neither alabaster nor any other stone, were obliged to procure at any price. At least we must admit that up to the present time the excavations in Assyria have scarcely yielded to our curiosity anything that can enable us to assert that statuary flourished in



Fig. 61.—Statue of Assurnasir-pal (British Museum).

Northern Mesopotamia. On the contrary, the few Assyrian statues that have come down to us prove the poverty and neglected condition of this branch of sculpture. The principal objects that can be cited are two statues of the god Nebo at the British Museum, a statue of the King Assurnasir-pal (B.C. 882—857), and two other figures of priests which took the place of Caryatids at Khorsabad.

The statue of Assurnasir-pal represents this king dressed in a long robe without folds and devoid of ornament, which almost gives him the appearance of a cylindrical Terminus. His beard and hair lie close to his head and neck, and in each part it is evident that the artist, through want of skill or on account of the difficulties he felt in dealing with the block which he had to fashion, did not dare to attribute to the limbs a suppleness and ease that would have damaged their solidity, nor to give to the beard and the delicate parts

of his work a finish which would have run the risk of splitting the stone.

The fringes of the robe are only indicated by slight strokes of the burin ; the arms are united to the bust, and so are the sceptre and the crook which the monarch holds in his hands.

The Atlantes found in front of the enamelled walls of the hareem at Khor-sabad seem to have been employed in the structure as true columns ; on their head-dress they support a square plinth which bears witness to their architectural function ; their figures are of more than human stature. From the sacred vase which they press reverently to their



Fig. 62.—Statue in the hareem at Khor-sabad (after Place).

breast, and which we have already seen in Chaldæa, flow four streams, which recall the four rivers of Paradise in Genesis ; two of these liquid jets fall directly upon their feet, while the two others, rising over their shoulders, fall down their back to their feet in slightly undulating bands.*

* Heuzey, *Un Palais Chaldéen*, p. 81.

The scenes upon the bas-reliefs in the interior of the palace chambers sometimes represent processions in which deities, standing or seated, are carried upon litters by priests or slaves (fig. 114): so there were statues at Nineveh. It is doubtful, however, whether these discoveries give any other impression of Assyrian statuary than that which we have described.



Fig. 63.—Stela of Samsi-Rammanu (British Museum).

Instead of statues, the Assyrians often erected stelæ and obelisks—a kind of monument which holds, so to speak, the middle place between statues and bas-reliefs. Among the stelæ the most finished type is that of King Samsi-Rammanu III. (B.C. 822—809). It is a monolith of slightly trapezoidal form, rounded in the upper part. The sides are covered with a cuneiform inscription which relates year by year the

military exploits of the prince. On the anterior surface, surrounded by a border which forms a frame, the king, in high relief and seen in profile, stands in adoration before the planetary symbols. It is clear at the first glance that the artist has been bolder than he would have been in dealing with a statue in the round. The

feet and arms are freer and not held so closely to the figure; far from treating the details of the costume roughly, he takes pleasure, on the contrary, in laying exaggerated stress upon them.

In the British Museum are small stelæ of a later date, bearing figures of Assur-bani-pal (B.C. 668—666). They show the king holding a basket upon his head, in



Fig. 64.—Stela of Assur-bani-pal (British Museum).



Fig. 65.—Obelisk of Shalmaneser (British Museum).

the same attitude as the early Canephoræ of Chaldæa (see above, p. 37, fig. 25).

Assyrian obelisks, which have nothing in common with the gigantic Egyptian monoliths to which this name is given, are, like the stelæ, large boundary stones set up in honour of the exploits of some prince, sometimes on the very field of battle, or on the ruins of a conquered town. The most complete and best preserved of these monuments is the obelisk of

Shalmaneser III. (B.C. 857—822) found at Nimroud. This is a monolith scarcely more than $6\frac{1}{2}$ feet high ; it is a square pillar, slightly pyramidal in form. The upper part is arranged in steps which recede from one another on all sides ; the summit forms a platform, and has nothing to surmount it : perhaps a statuette of the king or his favourite deity formerly stood there. The four faces of the obelisk are covered with inscriptions and bas-reliefs arranged in rows one above the other. The lower part, which is entirely bare, must have been buried up to a certain point in the ground.

As we see, the stelæ and obelisks, which take the place of statues, are in a technical point of view derived from the bas-reliefs. If any Assyrian statues are brought us by future discoveries, they will always be few in number, and poor and timid in style ; there is nothing among them to be compared to the Chaldæan statues, and above all nothing to be placed side by side with the innumerable Egyptian statues, the style of which sometimes almost attains to the perfection of Greek art ; Assyria also was destined to approach this ideal, but only in bas-relief.

Such was the logical consequence of the natural difference of the environments in which the empires of Egypt and Assyria, those two poles around which the whole of the ancient East gravitates, were evolved. On the banks of the Nile, stone suited for sculpture exists in profusion, and as there was abundant material in the hands of the artist, he was able to devote himself to incessant experiments, essays and trials, which, progressively repeated from generation to generation, only stopped at the threshold of Greek art. In Mesopotamia

there was little or no stone to carve; it was only rarely and at great expense that precious blocks were brought with much trouble from a long distance, and these were too dear and too scarce to allow of numerous experiments.

§ II. BAS-RELIEFS.

To conceal the poverty of the material of their brick or clay structures, the Assyrians, as we have said, conceived the idea of lining the walls with thin slabs of limestone or gypseous alabaster of a yellowish shade,



Fig. 66.—Assur-nasir-pal sacrificing a bull (Bas-relief in the British Museum).

which they extracted at small expense from the neighbouring mountains of Nineveh. These slabs could be sculptured and polished with marvellous ease.

The most ancient bas-reliefs that the excavations in Assyria have brought to light come from the palace of Assur-nasir-pal (B.C. 882—857) at Calah (Nimroud). What a distance there is between this epoch and that of the ruins of Tello! But from the reign of this prince to the fall of Nineveh, towards the end of the seventh century—that is to say, during three centuries—there is an abundance of documents for the history of

sculpture; they have been disinterred principally from the palaces of Assur-nasir-pal, Shalmaneser, Samsi-Rammanu, Rammanu-nirari, Tiglath-Pileser, Sargon, Sennacherib, Esarhaddon and Assurbanipal,—palaces which these princes had built in order to immortalise their fame, and the walls of which they covered with the scenes of their valour and the narrative of their exploits.

Besides the interior walls of the chambers, no bas-



Fig. 67.—Genius with the beak of an eagle (Bas-relief at the Louvre).



Fig. 68.—Two-winged genius (Bas-relief at the British Museum).

reliefs were found in the palaces except on the principal façade. These sculptures on the façade have peculiar characteristics upon which we must lay stress. In the first place, they are exclusively devoted to religious and mythological subjects: not the smallest allusion is found to the exploits of the prince. They represent especially divine heroes, winged genii with human bodies and eagles' claws and beaks, winged lions and bulls which guard the royal residence and defend the approaches to it, whether against evil spirits or against

foreign invasion. Accordingly the figures in these exterior sculptures are of colossal proportions, as it is fitting for gods and heroes. There was also a reason drawn from the laws of perspective in this enlargement of the figures, since the façade of the palace was intended to be seen at a greater distance. The winged bulls at the Louvre, which come from Khorsabad, are from 13 ft. to 16 ft. high. The groups which represent Izdubar, the Assyrian Hercules, strangling a lion under his arm, are as much as 19½ ft. The Assyrians multiplied their winged bulls at the entrance of the doors. Twenty-six pairs of them were found in the palace of Sargon, and as many as ten in a single façade of the palace



Fig. 69.—Four-winged genius, Khorsabad (Louvre, 9 ft. 10 in. high).

of Sennacherib. Assyrian texts speak of them as *kirubi* (cherubim?) or *sedi* (genii). The considerable projection of their figures from the walls makes them partake of the bas-relief and of the statue in the round at the same time. Some of these bulls have a relief of about 8 in.; placed at the corner of the doors to support the archivolt, they seemed, like Atlas upholding

the world, to bear upon their heads the whole mass of the building. Carved on two sides, they are like statues half-buried in the thickness of the wall. They were generally arranged in fours, two being on the plane of the wall, facing one another on each side of the door, and the other two facing the visitor as he entered, while their heads stood out from the façade and their hinder parts remained inside the passage. The visitor arriving from without saw before him at



Fig. 70.—Winged and human-headed lion
(British Museum).

once the bodies of the first two in profile and the full face of the two others. Before the building or within the doorway he still saw at the same time full faces and bodies in profile. By an illusion, he seemed to behold continually, and in every position, the whole of a

bearded monster, with his thick mane on his chest, his neck furnished with tufts of hair, his legs, in which the muscles, speaking emblems of material strength, are powerfully marked, his wings formed of rows of plumes, and reaching, like gigantic fans, as high as the archivolt.

Except in the palace of Sennacherib, these winged bulls, in order that the illusion may be more complete, are represented with five legs; two hind legs and three fore legs, of which two are straight and one is bent.

The object of this trick was always to show four legs, whatever might be the position of the spectator. In fact, standing before the beast, the spectator sees his two fore legs; on the side, one of these two being no longer visible, the artist has replaced it by a third which is seen in profile in the background. This quaint device of the Assyrian sculptor is never met with in Egypt.

The philosophical idea expressed in these bulls and lions, these impassible and majestic sentinels, is that of physical strength, calm and sure of itself; it is the conception of the Egyptian sphinxes and of the Græco-Roman Hercules in repose, with a half-smile upon his face. Only, while in the Greek Hercules the human element alone comes in, and in the Egyptian Sphinx there are only two elements, the man and the lion, four, and even more, are found in the Assyrian *Kirubu*: the man, the bull, the lion, and the eagle. The artist's chief merit is that he was able to give fair proportions to this fantastic beast, and to combine these various elements which he borrowed from nature, so as to create a figure of harmonious forms, in which nothing shocks the taste, and the expression of which is noble, majestic, and natural. To us, though we are the children




Fig. 71.—Front face of a winged bull from Khorsabad (Louvre).

of another civilisation, nothing seems grotesque or deformed in these fine and vigorous creations of the Assyrian genius, which could, as skilfully as the Egyptian genius, associate the human form with the animal form in the symbolic representation of deity and of supernatural beings. It is on the banks of the Tigris that we find the prototypes of the Loves, the Centaurs, the Chimæras, the Sphinxes, the Gryphons, the Pegasi, the Hippocampi of Greek art.

It has been calculated that the series of bas-reliefs



Fig. 72.—Battle scene (Bas-relief from Nimroud, British Museum).

from the halls of Sargon's palace at Khorsabad, placed end to end, would form a line a mile and a half long. Those who have visited the British Museum will remember the Nimroud and Kouyunjik galleries, and the Assyrian Basement, each one of which is larger than the Assyrian gallery at the Louvre. What a quantity of material for writing the history of Assyrian sculpture during three centuries is here in our hands ! In the interval between every campaign, that is to say, between two springtides, the king had bas-reliefs sculptured to exhibit before men's eyes his prowess in the

chase or in war, and the manifold episodes of official life. Taken as a whole, the sculptures in the interior of the palaces are always in honour of the prince. Everything is for the king, who symbolizes the life of his whole people; he does everything, and nothing is accomplished except by his hands or by his orders; nowhere is the ferocious egotism of Eastern monarchs more conspicuous than in these bas-reliefs. Egyptian sculptures often contain scenes of civil life from which



Fig. 73.—The Assyrian army in a mountainous country (Bas-relief from Nimroud, British Museum).

the Pharaoh is excluded: agricultural labour, games, festivals, public markets, and many other episodes in the existence of the ancient Egyptian Fellaheen. In Assyria we find nothing of this sort; the speaking walls repeat, without a moment's pause, the warlike chronicle of the kings.

This exclusively official side of the Ninevite sculptures compelled art to confine itself to abstract types, created once for all, which, multiplied to satiety, produce a certain fatigue in our minds. There is no more pro-

portion or scale in the Assyrian bas-reliefs than among the Egyptians or the Chinese ; perspective is absent, or rather the artists made vain efforts to calculate and reproduce its effects. Men are taller than the chariots that they mount and the horses which draw them ; they even overtop the fortresses that they besiege. As in Egypt, the king is always represented as taller than his ministers, and in general the Assyrians are taller than



Fig. 74.—Siege of a fortress (Bas-relief from Khorsabad, Louvre).

their enemies. Greek heroes, in classical art, are also often taller than the warriors who surround them ; the same facts have been remarked in Chinese art. The practice is naïve, but it is common to all arts and easily explained by the absence of perspective. At the present day, when our artists can at their pleasure arrange several planes in their pictures, and produce distances and backgrounds in the scenes which they wish to render, they are satisfied to make the important scene stand out and place the principal actors in the fore-

ground. Before perspective was understood and many planes could thus be created, there was no means of bringing out the principal actors except the device of a disproportionate enlargement.

Generally speaking, the Assyrian artist shows a fondness for picturesque spots, mountains, and rivers. But he renders them with the strangest errors in the relative proportions of the objects: for instance, the




Fig. 75.—Navigation scene (Bas-relief from Khorsabad, Louvre).

fish among the waves are as large as the boats; the birds in the forests are as large as the trees or the hunters; the vultures on the field of battle are as big as the horses.

When the artist wishes to reproduce the human countenance, he always places the eye in full, even when the face is in profile. When the sculptor is obliged to represent his figures in full face, or in any other attitude than the simple profile, he is much embarrassed, and shows his hesitation and his in-

capacity; unable to foreshorten the feet, he draws them entirely in profile, while the whole of the upper portion of the body is in full face—an error which gives an appearance of dislocation to the figure. He turns the heads round as if they were put on the wrong way; the hands present the same deformity: it might sometimes be supposed that the artist has put them on backwards.

The principal efforts of the sculptor were aimed at the head, the legs, and the arms. He makes the muscles stand out enormously, while they are not always in their proper anatomical position. Bold curves form the outline of the knee-cap and mark the leg-muscles and the biceps; the feet and hands are not only clearly carved out, but chiselled to an excessive depth. The Assyrians scarcely knew more than two types of the human head, which they constantly reproduce: the bearded head and the beardless head. An attempt may be made, however, to establish more exact definitions and distinctions. The bearded head may wear its hair curled in very short ringlets, or else the beard and the hair may be twisted in parallel and symmetrical tresses: this last form is reserved for figures of gods, heroes, kings, the chief functionaries of the court, and soldiers. The beardless heads must be recognised as the type set apart to represent eunuchs. These personages, some of whom played an important part at court, like the Kishlar-Agha, or chief of the black eunuchs at Constantinople, are characterised by their fleshy and sensual countenances.

Among the works of Chaldæan and Egyptian art there are faces which belong to old men, to young men,

and to children. In Assyria it may be said that the faces never change, or rather three or four fixed types are exclusively met with : kings, officers, slaves, and even gods, have all the same physiognomy, which belongs to the age between youth and maturity. When children are met with, they have a prematurely old appearance, and their stature alone distinguishes them. The Ninevite artists rarely represented women, and when they did so proved their absolute inexperience. Their veiled women have vulgar features, from which all ideas of physical beauty are banished. Examine the scene in which King Assurbanipal and one of his wives are drinking from goblets (fig. 77).



Fig. 76.—Eunuchs (Bas-relief from Khorsabad, Louvre).

The face of the queen is almost masculine in appearance ; even her hair is dressed like that of men ; she wears a peculiar diadem, and is draped in sumptuous robes, embroidered and enriched with jewels.

The Assyrian sculptor had not the skill to draw a true portrait and to study individual likeness, except perhaps in certain royal heads.* Nor had he the skill

* Menant, *Remarques sur les portraits des rois assyro-chaldéens*, 1882.

to give to the types which he created the least expression, betraying any motion whatever of joy or sadness : his figures remain impassive, whether taking part in joyous banquets, in the excitement of hunting, in battle, or even amidst the most atrocious tortures.



Fig. 77.—Assurbanipal and his queen (Bas-relief from Kouyunjik, British Museum).

The countenance of the Assyrian is always imperturbable, never laughs and never weeps ; the gestures of his arms alone are designed to express and interpret his impressions. The hand raised and drawn back to the height of the nape of the neck is a sign of introduction or of an appeal ; the hand raised in front of the mouth is a sign of mourning and of violent grief ; the

hands held in such a way that one grasps the wrist of the other, make a gesture which implies an acknowledgment of servitude and absolute submission, due only to the sovereign or to the gods. Assyrians are sometimes seen in the act of prayer, raising one hand as high as the face, while the other hangs loosely by the side; but some adopt the Christian posture in prayer, raising their two hands and pressing the palms against one another.

As the bas-reliefs of the Ninevite palaces are specially devoted to the representation of the military campaigns of the kings against foreign nations, the artist has often been led to draw men or women of distant countries, distinguished from the Assyrians by their national costume or by certain ethnographical characteristics.

It is sometimes possible to understand these distinctions between Assyrians and foreigners

in the sculptures: for instance, the Jewish type could scarcely be better expressed at the present day than it is in the figure of one of the captives coming to make their submission to King Sennacherib in his camp before the walls of Lachish (fig. 78).

Moreover, with regard to the human form, the scope of Assyrian sculpture was greatly limited in conse-



Fig. 78.—Jewish type, from a bas-relief from the palace of Sennacherib (British Museum).

quence of the false modesty of the East, which was in



Fig. 79.—Assurbanipal in his chariot (Bas-relief from Kouyunjik, Louvre).

existence in ancient times as it is in our own day among

the Arabs, and prevented the artist from studying the human frame in the nude and in the living model. The Assyrian, like the Arab, is always draped in his thick burnoos, and this fashion, observed with religious strictness, contributed to no small extent to the sudden arrest of the progress of art. The long linen tunic, garnished with embroideries, only allows the head, feet and fore-arm to be seen; the working dress of the slaves, or sometimes the tunic of the soldiers, descends no further than the knee; the large fringed shawl, when it is worn, envelops the body like the Arab burnoos and the Roman toga.

The Assyrian, therefore, in consequence of a Semitic prejudice, could never

express natural and ideal beauty: herein lies his inferiority in comparison with the Egyptian sculptor; we know from thousands of examples how the artists of Thebes or Memphis treated the human torso, and several of their statues and even of their bas-reliefs are masterpieces. Rarely has the Ninevite sculptor ventured to represent the human form in the state of



Fig. 80.—Sargon (Bas-relief from Khorsabad, Louvre).

nudity, except in the case of the goddess Istar, and in that of a few figures of slaves or of corpses lying on the battle-field; and these exceptional cases betray his complete want of experience.

He tried to remedy the defect which we have just indicated by striving after perfection in details. No art has treated with greater complaisance and refinement all the features of the costume, not forgetting a single tress of the hair or a single fringe in the drapery. Here is, for instance, a bas-relief from Khorsabad (fig. 80), which represents Sargon attended by an eunuch. Observe with what inimitable perfection the embroidery of the tiara, of the mantle decorated with rosettes, and of the robe with its elegant diaper pattern is rendered; the silky softness of the fringes in the eunuch's dress is almost to be felt. The hands and feet, beard and hair, of the two figures, are treated with the delicacy of a cameo. Secondary matters thus assume an exaggerated importance detrimental to the effect of the whole; the muscles are so strongly marked that they become monstrous; the relative proportions of the different parts of the body are no longer conformed to nature. In this respect again Assyrian sculpture remains greatly inferior to its rival on the banks of the Nile. It cannot be too often repeated that the minute study of detail and devotion to the infinitely little ruined Assyrian art by helping to make it forget the general features of the work; the sculptor, led astray by this false object, looked at his figures too closely, omitting to improve their proportions and to give them more suppleness, life, and movement; even when most finished, they always give us an impression of geometrical stiffness.

If the direct study of bodily forms was neglected by the Assyrian artist in the case of human beings, it was not so in the case of animals. Accordingly Ninevite sculpture shows itself to far greater advantage in the representation of the animals of different kinds found in Mesopotamia. In this province it may claim a considerable superiority over Egyptian art, and reaches, in the time of Assurbanipal, that is to say, at the moment before the fall of Nineveh, a degree of perfection which




Fig. 81.—Wounded lioness (Bas-relief from Kouyunjik, British Museum).

may sustain comparison with the finest creations of Hellenic art. Its masterpiece is the figure of a lioness succumbing to the shafts of the hunters, from the palace of Assurbanipal at Kouyunjik. Her spinal column is broken by an arrow which pierces it through; the blood gushes in streams from the wound, but though on the point of expiring, the savage beast makes a heroic effort to raise herself upon her forelegs and to utter a last roar. In order to render this dramatic attitude with so much truth, the artists must often have followed the

royal hunting expeditions and witnessed terrible scenes in the deserts where the wild beasts had their haunts. Other bas-reliefs show us, with an almost equally successful execution, lions springing on to the royal chariot, dashing boldly towards the boats which plough the waters of the river, or, on the other hand, lying carelessly asleep on the plain, and lazily stretching out their limbs, the modelling of which is free and truthful.

Next to the lion, the Assyrian artist takes the greatest pleasure in representing the horse. In one scene it is



Fig. 82.—Slaves carrying a lion and birds.
Bas-relief from Khorsabad (after Place).

the wild horse, starting and bounding as he is caught by the lasso of the hunters; in another it is the war-horse, dashing at full gallop towards the enemy, and ridden by a warrior who draws his bow or brandishes

his lance; or again it is the draught-horse, harnessed to the royal chariot, trampling corpses under his feet, or drawing the heavy waggons in which the booty from the enemy's country is transported into Assyria. Such was the skill of the artist, that naturalists have been able to decide from the study of the bas-reliefs what breeds of horses were produced in Assyria. The dog, the goat and the sheep, the ibex and the wild boar, the bison and the wild ass, the deer and the gazelle, the camel and the dromedary, are also among the animals which frequently occur in the bas-reliefs designed to perpetuate the memory of particularly successful hunting

expeditions, or of the capture of herds belonging to a vanquished people. The artist took pleasure in placing them in the most fanciful attitudes, sometimes with the happiest effect. It was also his delight to introduce in procession the figures of foreign animals, sent to the King of Assyria by tributary nations, such as the elephant, the ape, and the rhinoceros. But the rarity of such animals in Mesopotamia explains the peculiar clumsiness of the Assyrian sculptor in the reproduction of them. Here are apes treated with an almost grotesque *naïveté*; they look like men disguised in the skins of animals, and trying to walk on all fours (fig. 83).

Among birds we find the eagle, the vulture and the gerfalcon hovering heavily and ungracefully over the battlefields, though the anatomical details of these birds are sometimes executed with skill.* The ostrich, a sacred bird, appears on cylinders and among the embroidered designs on official robes. Locusts, that plague of the whole East, figure in the character of offerings to the gods, and, no doubt, represent legions of evil spirits. In the rivers eels, crabs, and fish are placed. In the field, on the mountains, or on the



Fig. 83.—Envoy bringing apes as tribute (Bas-relief from Nimroud, British Museum).

* Layard, *Monuments of Nineveh*, vol. i., pl. 26, and *passim*.

river-banks we find palms and trees of every species, onions, ears of corn, lotus-flowers, vines, marsh-plants. But if the scrupulous imitation of nature sometimes leaves nothing to be desired in these sculptured forms, ignorance of the laws of perspective has forced the artist to employ devices of childish simplicity. Thus, to indicate that trees grow on each side of a stream, he has placed them upright on the further bank, and stem downwards on the nearer.

In the same way, when he wishes, for instance, to show us what passes within the enclosure of a fortress (see fig. 57), he is reduced to display it on the ground with the bastions and battlements in profile around it, turned outward like the points of a coronet; at the same time he arranges all his scenes within this enclosure in divisions one above the other, without regard for the laws of proportion, and without even taking the trouble to contain himself, as he has done with regard to the enclosure, within the spaces marked out by radii starting from the centre. By a further neglect of perspective, in the representation of an ox or other horned animal, he places the horn in profile projecting forwards from the head.

Besides the bas-reliefs which were displayed upon the walls of the palace-chambers, there were secondary pieces of sculpture in which the originality of the Assyrian genius comes to light. A notable example is found in the decoration of the thresholds of the palaces, which were carved in such a way that they looked like rich carpets. One of the most remarkable of these is a large slab of gypsum found at Kouyunjik, (fig. 84), in which the lotus or tulip-flower is combined

with rosettes, open daisies and geometrical designs most harmonious in effect; nothing more elegant in decorative sculpture has ever been conceived.

To sum up, Assyrian sculpture triumphs in the bas-relief, and in the patient and minute labour of ornamental design. If the work of the Ninevite chisel is compared to that of the Greeks in the archaic period, down to the appearance of the Æginetan school, a surprising affinity will be observed between them.

The stela of Aristion, that primitive Athenian bas-relief, known under the incorrect name of the *Warrior of Marathon*, looks, at first sight, as if it had been taken from the walls of Sargon's or Sennacherib's palace. At Khorsabad a cippus, acquired by Victor Place, is adorned with parallel




Fig. 84.—Fragment of threshold Kouyunjik (British Museum).

flutings terminating in a hemisphere of elegant palmettes; it presents the appearance of a Greek stela.*

If we compare the sculpture of Kouyunjik, Nimroud, Khorsabad and Kalah Shergat with one another, we observe, beneath the general uniformity that we have indicated, differences important enough to enable us to characterise the progress of art during the three centuries before the fall of Nineveh, and not simply

* Perrot and Chipiez, *History of Art in Chaldæa and Assyria*, vol. i., p. 257.

the result of the varying talent of the artists. We seem to be able to distinguish in Assyrian art, as we learn to know it in the bas-reliefs, three periods or three successive developments. Under Assur-nasir-pal the figures are already bold and powerful, but thick-set, and they appear in small numbers in the scenes represented; their motions are sober, but full of truth




Fig. 85.—Slaves dragging a winged bull. Bas-relief from Kouyunjik (British Museum).

The artist has the singular habit, only observed in Assyrian art, of covering a portion of his figures with long inscriptions explaining the scenes which he intends to portray (see fig. 83); we have already seen that the Chaldæan statues of Gudea are covered with inscriptions, and Herodotus' statement* that the figures of "Sesostris" in Ionia, doubtless the Hittite figures described below, bore inscriptions across their breasts

* Herod. ii. 106.

is probably based on a confusion with the Assyrian figures in Syria and elsewhere. Under Sargon and Sennacherib, the sculptors became more experienced and more ambitious. In their works the figures are far more numerous, and concur more visibly in a common action; they have more life and movement; the scenes representing battles, hunting expeditions, the worship of the gods, or slaves engaged in public works are more varied; the gestures of the figures are more marked and more energetic, the muscles of the legs and arms more deeply outlined; lastly, the human forms are no longer covered with inscriptions; these are placed at the side, as explanatory legends.

In the time of Assurbanipal, a more natural art, and one which conformed




Fig. 86.—Deer hunt. Bas-relief from Khorsabad (after Place).

more to the true principles of sculpture in bas-relief, came into being. Instead of giants, we find on the contrary small figures forming a series of pictures, containing the greatest variety of scene, and full of freshness and action. This art reaches its apogee in the figure of the lioness which we have cited (fig. 81). It must be added that all the parts of the same bas-relief are seldom sculptured by the same artist, and that figures of very unequal merit are met with. The master's chisel reserved for itself the principal personages, the royal train and the officers who surrounded it; the disciples worked at the secondary portions, the

corpses of the enemy, the processions of prisoners, the background of the landscape. Matters were not managed differently with regard to the sculptures of the Parthenon.

§ III. PAINTING AND ENAMELLING.

The bricks which composed the structure of the walls in Chaldæan or Assyrian edifices were nowhere visible. Above the slabs sculptured in bas-relief and under the spring of the vaults a white stucco was applied, made of plaster and lime, like that still used by the Orientals to coat their houses; this custom explains the phrase "whited sepulchres" in the Gospels. It was doubtless on a plaster of this nature that the mysterious hand of which the Book of Daniel speaks traced out Belshazzar's sentence of condemnation on the night of the ill-famed banquet: the sacred writer says that the hand wrote "on the plaster of the wall." This stucco was often decorated with paintings in distemper, at any rate in the principal chambers, above the line of the bas-reliefs.

Modern explorers have collected some fragments of these frescoes or decorative paintings; at Warka, among the ruins of the temple called Wuswas, Loftus acquired some which belong to the remotest Chaldæan period. At Khorsabad, V. Place found on some pieces of stucco elegant rosettes formed by the application and juxtaposition of very decided colours: white, yellow, green, red, and black. One of the most remarkable examples of this painting is a border of bulls painted white on a yellow ground, their form being

relieved by a broad black outline (fig. 87). Above is a row of blue battlements; below festoons of many colours. The effect is harmonious, though the tints are flat, and in spite of the absence of all modelling in the figures.*

The application of stucco of different colours is particularly conspicuous in the construction of the staged towers, the terraces of which are, beginning from the lowest, white, black, red, yellow, vermilion, silver and gold. In the interior of the chambers, to avoid the disagreeable contrast between the uniform whiteness of the stone bas-reliefs and the brilliancy of the many-coloured paintings, the fashion was to colour the figures in the bas-reliefs



Fig. 87.—Painting on plaster, Nimroud (after Layard).

themselves. Some traces of colouring may still be recognised in the sculptures preserved in our museums, and though it is true that they are being gradually effaced, they were quite evident when the slabs were disinterred. The beard, hair, weapons, and even the face and costume of the figures were coloured in a similar manner to the paintings on plaster, so that this painted stucco seemed to be the continuation of the bas-reliefs. There are, for instance, evident

* Perrot and Chipiez, *History of Art in Chaldæa and Assyria*, vol. ii., p. 294 ff.

traces of vermilion paint* on the figures of demons in the Assyrian basement of the British Museum. The Assyrians obeyed the same laws of æsthetics as the mediæval artists, who applied polychrome colouring to their marble or stone statues, to bring them into perfect harmony with the rich decoration which filled their cathedrals from the floor to the keystone of the vault.

Enamelled brick played the same part as painting in




Fig. 88.—Portion of an enamelled archivolte at Khorsabad (after V. Place).

fresco, only it was more solid and was better able to resist the action of damp. In Chaldæa, where it rains oftener than in Assyria, greater use has been made of enamelled brick than in the latter country. The Ninevite artists scarcely ever employed this method of decoration, except round the principal doorways and to make an elegant border for the archivolte. The bricks of brilliant colours, which are conspicuous from a distance, are ornamented with floral designs and rosettes in exquisite taste. In Sargon's palace

* Cf. Ezekiel xxiii. 14.

V. Place found nearly all the bricks of the archivolt of a door. Between two borders of white rosettes is a broad frieze containing winged genii and symbolical animals bearing the same attributes as the similar figures in the bas-reliefs (fig. 88). On the lower plinth of the chief door of the hareem there figured on the enamelled bricks a lion, an eagle, a bull, and a plough; at the turn of the angle stood the king. At

Nimroud most remarkable enamelled fragments were also discovered depicting portions of soldiers, weapons and chariots, and even parts of inscriptions. On a single brick, found by Layard, a king is seen offering a libation and attended by two warriors (fig. 89). But in



Fig. 89.—Enamelled brick, Nimroud (after Layard).

general each figure was made up of a large number of bricks, since the restricted dimensions of a baked brick did not allow more than a part of the subject to be placed upon it. The design was executed and the vitrifiable colours applied before the baking; the artist had to apportion to each brick the different parts of a figure in such a manner that when they were put together there might be perfect agreement in the lines which had to join; the marks to indicate their position, set on the backs of the tiles, made this operation, which

required great technical skill, much easier. At Babylon, where enamelled brick played a far greater part in the decoration of buildings than at Nineveh, the device was adopted, in order to replace coloured sculpture in stone, of stamping bricks with figures or parts of figures in relief. Imagine a slab of soft clay several square yards in size ; on the surface of this the whole picture was modelled in relief as it might have been carved on stone. When this operation was finished, the slab of clay was cut into rectangular pieces of the size of ordinary bricks. These pieces, provided with a mark to indicate their position, were then separately coated with colour and varnish, and afterwards baked. Subsequently they were joined together with bitumen, which formed a strong mortar, and in this work of reconstructing the design the workman was guided by the position-marks. This was the first origin of the mosaics in relief made by the Greeks and Romans. The Achæmenid palaces of Susa were decorated by the same methods, and Persian artists imitated the Babylonians in their execution of the great brick bas-reliefs with which the expedition conducted by M. Dieulafoy has enriched the Louvre.

Unfortunately only unimportant fragments of bricks modelled in relief have been, down to the present time, brought to Europe. Travellers pick up hundreds of fragments of flat enamelled bricks like those at Nineveh on every mound which covers the ruins of Chaldæa. Those which have been deposited in our museums represent floral designs, rosettes, genii, animals, and human figures. Only skilfully directed excavations could bring to light complete pictures and scenes

analogous to those displayed upon the walls of the Ninevite and Susian palaces. Diodorus, following Ctesias, relates that at Babylon, on the walls of the palace built by Nebuchadnezzar, but which he attributes to Semiramis, there were scenes of every sort painted on brick. "Animals of every kind," he says, "were here to be seen, copied according to all the rules of art with regard both to form and colour. The whole represented the hunting of various animals, the dimensions of which exceeded four cubits. In the midst was Semiramis on horseback, hurling a javelin at a panther, and beside her, her husband Ninus striking with his lance a lion which he is attacking at close quarters." Berosus is no doubt speaking of enamelled bricks in his description of the paintings in the Temple of Bel, in which were seen "marvellous monsters of every sort presenting the greatest variety of forms." Lastly, the prophet Ezekiel, who lived at Babylon, says, speaking of Jerusalem: "she saw men pourtrayed upon the wall, the images of the Chaldæans pourtrayed with vermilion, girded with girdles upon their loins, exceeding in dyed attire upon their heads, all of them princes to look to, after the manner of the Babylonians of Chaldæa."

The art of enamelling brick, handed down by the Babylonians to the Persians of the Achæmenid period, long remained flourishing in the East. The decoration of the mosques of Broussa, Tabriz, and Ispahan, which excites the admiration of every traveller, is based on the same principles as that of the Ninevite, Babylonian, and Susian palaces. Only, instead of figures of living beings, which the Koran does not tolerate, the enamelled

tiles bear religious inscriptions in ornamental Cufic characters, and elegant designs of flowers and trees. Every one has had the opportunity of seeing specimens from the workshops which were still flourishing in the last century in Asia Minor, and the productions of which adorn the palaces and the richest mosques of the Mussulman world. This art is directly derived from the Chaldæo-Assyrians, and it is interesting to observe that their successors, down to our own times, have not made the smallest progress in it.

CHAPTER IV.

INDUSTRIAL ARTS.

§ I. CERAMICS.

THE causes which impeded the development of pottery in primitive Chaldæa had the same unhappy influence on Assyrian pottery and on Chaldæan pottery in the age of Nebuchadnezzar. Though a few terra-cottas are fashioned with a certain elegance and present graceful features, their walls are always extremely thick, on account of the friable nature of the clay, and the types created by the modeller are totally wanting in variety. Botta found under the pavement of the courtyards at Khorsabad little cavities containing, besides cylinders and other amulets, terra-cotta statuettes of talismanic character, intended to conjure and drive away the infernal powers. "These statuettes," says M. Heuzey, "are designed with a remarkably sure hand, in grey clay, which is almost crude, and pitted with small holes, as if it had been mixed with chopped straw or hay, according to the process followed in the manufacture of bricks."* The example which we reproduce represents the hero Izdubar, so often drawn upon the bas-reliefs and

* L. Heuzey, *Les Figurines de terre cuite du Musée du Louvre* p. 1.

cylinders as he is here, that is to say, with curled beard and long hair in ringlets. His countenance is



Fig. 90.—Izdubar. Terra-cotta (Louvre).

expressive, and shows signs of careful work. The same praise must be given to the head of a fantastic animal, also found at Khorsabad (fig. 91); this head, in whitish clay, is covered with a glaze of a fine bluish green, resembling, and perhaps imitated from, Egyptian pottery; a similar figure of a monster roaring at winged genii appears among the bronze monuments; in both cases the art is realistic, and has rendered ugliness and ferocity with all the force of ideal expression.

The terra-cotta vases discovered during the excavations in Assyria no doubt denote a real progress when compared with Chaldæan ceramics; but they are still nothing but heavy amphoræ, with or without handles, with a more or less elongated neck and a more or less broadened body, and they could never be compared to any but the most archaic productions of Greece. They are sometimes decorated with brown or yellowish paintings, or with designs in relief, representing floral scrolls, geometrical lines or diapers, but never with anything that reflects the beauty of the Ninevite sculptures. Among them all there are no vases which



Fig. 91.—Head of a monster. Terra-cotta (Louvre).

formed part of the luxuries of a refined civilisation, as the Greek vases did; neither in Assyria nor in Chaldæa have any clay vessels been discovered except vulgar jars and pots. This is, perhaps, the place to notice fragments of two small circular vases of steatite or soapstone discovered at Nimroud and Sherif Khan, near Kouyunjik. They are probably of the age of the Sargonids, and are dedicated to certain deities. The thin walls give these vessels almost the appearance of porcelain, of which Layard supposed them to be, and the figures carved upon them in relief, give them an artistic character which the Assyrians could never impart to their pottery. One of the fragments is engraved by Layard.*



Fig. 92.—Tablet with figure of boar in relief (British Museum).

At Babylon, whither the seat of government was transferred after the fall of Nineveh, the modellers seem to have made a great artistic effort. Mr. Rassam obtained from the ruins of the southern capital a small terra-cotta tablet, $1\frac{3}{4}$ in. by $2\frac{3}{4}$ in., on which the figure of a boar, such as lived among the reeds and marshes of Mesopotamia, is modelled in relief. The forms of the animal are here reproduced with all the excellence of the later Assyrian artists, by Azaru, of the tribe Esaggilai (doubtless connected with the great Chaldæan Temple), whose name inscribed on the back adds to the interest of the little work. Solid figurines have

* *Nineveh and Babylon*, p. 358.

been found in Chaldæa, like those in Assyria, moulded on one side only in greenish clay, forming remarkable examples of Babylonian art. The chronological position of these figurines is, however, difficult to determine, but they seem to us to be, perhaps, contemporary with Nebuchadnezzar. They represent priests or gods, standing upright in their long robes, with their hands



Fig. 93. — The
Divine Mother.
Terra-cotta
(Louvre).



Fig. 94. — Istar.
Terra-cotta
(Louvre).

clasped in the attitude of respect; women dressed in fringed garments, carrying a vase upon their breast; nude goddesses, standing upright, and suckling the divine child. One of these last (fig. 93) is, says M. Heuzey, "A purely Asiatic type, the rather full forms of which are modelled with charming truth and rare delicacy; I do not fear to describe it as a little wonder of its kind."* Another and commoner ex-

* Heuzey, *op. cit.*, p. 2.

ample is the goddess Istar, nude and holding her hands against her breasts, adorned with bracelets and necklaces, with her hair elaborately dressed : this naturalism and immodest freedom in the representation of Istar form a contrast with the ordinary habit of Chaldæo-Assyrian art. This series of figurines is chronologically terminated by the statuettes of the Achæmenid or Parthian epoch, modelled of the same clay, but showing all the characteristics of decadence. The forms are less carefully studied ; sometimes Istar, the goddess of Erech, is represented in these figurines of terra-cotta or alabaster, half-reclining on a banqueting couch, like that described by Herodotus in the temple of Bel-Marduk at Babylon ; her head is often crowned with the crescent, her proper symbol, in the centre of which a garnet or other sparkling stone is set. In short, these coarse images of the voluptuous goddess condemn at once the art and the manners of the people who produced them.

§ II. METALS.

The art of working in metals, which was already so highly developed among the primitive Chaldæans, reached its apogee under the Sargonids. We find statuettes, bas-reliefs in repoussé, vases and utensils of every sort, weapons and ornaments, so that there is no use of the precious metals, or of iron and bronze, to which they were not put by the industry of Ninevite craftsmen. Among the ruins of Sargon's palace, objects of iron and bronze, such as hooks, rings, chains, pick-axes, hammers, plough-shares, weapons, fragments of chariots, and tools of all sorts, were picked up. From

the strictly artistic point of view, we have already described the wooden pillars plated with overlapping scales of bronze, so as to imitate the bark of the palm tree.

The most important of the Assyrian monuments in




Fig. 95.—Gates of Balawat. Restoration.

bronze hitherto discovered is the famous decoration of the gates of the palace of Shalmaneser III. (857—822), at Balawat. It consists of metal bands, 9 in. broad, decorated in repoussé with reliefs representing the campaigns of Shalmaneser. They were fixed horizontally, at intervals, on wooden gates, which may have been quite 7 or 8 yards high; the scenes are reproduced upon them with the same ease and the

same details as on the limestone slabs: battles, landscapes, trees, rivers and mountains are to be seen; the figures, however, are treated more roughly, and the muscles are marked with less precision and delicacy. Each band (fig. 96) is divided into two compartments by a row of rosettes, imitating the heads of nails. "Taking

them all in all," says M. Perrot, "these bronze reliefs are among the works which do most honour to Assyrian art."*

The perfection of the work in certain Assyrian bronze vessels makes these monuments real master-




Fig. 96.—Fragment of metal band of Balawat gates (British Museum).

pieces. Pateræ found at Nineveh, sometimes incrustated with gold and silver, present on their inner surface, in an exquisite style, concentric zones of rosettes and symmetrical festoons of figures engraved in outline or standing out in relief (fig. 97). Symbols are encountered

* *History of Art in Chaldæa and Assyria*, vol. ii., p. 217.

which have evidently been borrowed from Egypt, such




Fig. 97.—Bronze dish, Nimroud
(British Museum).



Fig. 98.—Assyrian archers.
(Bas-relief in British
Museum.)

as the winged scarabæus and the figures of Hathor and



Fig. 99.—Various forms of the Assyrian helmet.

Bes. Similar in form, in the metal of which they are composed, in the gold and silver incrustations, and

even in the choice of subjects, to the Phœnician vessels from Cyprus (figs. 233 and 234), the pateræ of Nineveh are not, for the most part, of Assyrian manufacture; they were brought thither by Phœnician commerce, and were probably fashioned in the workshops of Tyre or Sidon, where the artistic traditions of Egypt and Assyria were united. The glass found among the Assyrian ruins was also probably of Phœnician manufacture, as it will be seen in the chapter on Phœnician art. Much more exclusively Assyrian are the bronze seals which the bas-reliefs show us in the hands of priests or genii. We find among them lions' heads, flowers and elegant rosettes on the bottom, on the border, or at the point at which the handles are attached.



Fig. 100.—Bronze lion (Louvre).



Fig. 101.—Bronze siren.

The equipment of an Assyrian soldier consists of a bow and arrows, a lance or javelin, a club, a sword, a dagger, a helmet, a coat of mail, and a buckler; the battering-rams which sap the walls had a metal carapace and head. Might it not be imagined that these Assyrian soldiers, wearing the conical helmet, and entirely covered, with the exception

of their arms, nose and eyes, with a long coat of iron




Fig. 102.—Bronze siren.

mail, were mediæval knights? The shape of the Assyrian helmet varies according to the time, and perhaps also according to military rank. There is the helmet formed of a conical basin, without ornament, the helmet provided with cheek-pieces, as among the Greeks, the helmet decorated with an elegant crest bearing an aigrette of feathers or of horsehair. But the essential form is always that of a hemispherical basin, covering the head, but leaving the face bare. A votive shield, preserved at the British Museum, has, like those represented in the bas-reliefs, the form of a large round disk, convex in its central part; this metal disk, 34 in. in diameter, is decorated like the pateræ with a central rosette and several concentric zones containing lions and bulls in relief.



Fig. 103.—The demon of the South-west wind, Bronze (Louvre).

The preceding examples prove the existence of a manufacture of metals which had reached a high degree of perfection, and was in possession of all the technical methods. Accordingly, we believe that the scanty number of statues or statuettes in bronze of human beings or of Assyrian deities must be attributed to an unfortunate chance. They must have been produced in large numbers, as in ancient Chaldæa, and a good proof of this is the large cow's head disinterred near Bagdad and preserved at the British Museum* ; another example is the statuette of a lion found at Khorsabad (fig. 100) ; this has, doubtless, serious defects, such as a singular disproportion between the head and



Fig. 104.—Bronze plaque. De Clercq collection.

the body, between the fore legs and the hind legs ; but what truth of expression in the muzzle with its gaping mouth, and in those powerful claws !

A statuette in M. de Vogüé's collection, found at Van, represents a sort of siren which seems to have

* Perrot and Chipiez, *History of Art*, vol. ii., p. 143.

acted as an ornament attached to a vessel or a piece of furniture (figs. 101 and 102). The oriental appearance of the head, the hair in ringlets, the large eyes, the bracelets upon the outstretched arms behind the wings, and the artistically marked feathers, make of this little



Fig. 105.—Bronze plaque. De Clercq collection (other side).

monument one of the most precious relics of the art of working in bronze among the Assyrians. A similar figure is preserved in the British Museum, and in this instance the loose ring by which the vessel was held is still in place.

The Louvre possesses the figure of a monster with four wings which represents the demon of the south-west wind, as the cuneiform inscription upon it teaches us (fig. 103). Nothing can be im-

agined more hideous and more expressive than the head with its glaring eyes, roaring throat, horned brows, crooked fingers and fleshless body with lion's claws. It leads us naturally to cite a bronze plaque from the collection of M. de Clercq, in which M. Clermont-Ganneau has recognised a representation of the Assyrian hell. One

side (fig. 104) is occupied by a monster with four wings and eagle's claws, looking over the top of the plaque; on the other side (fig. 105) the monster's head is seen, and under it scenes arranged in four rows: first the symbolical figures of the stars, then a procession of seven creatures dressed in long robes and having the



Fig. 106.—Standard in a bas-relief from Khorsabad (Louvre).



Fig. 107.—Foot of a piece of furniture. De Vogüé collection.

heads of various animals: these are the heavenly genii called Igigis. Below this we witness a funeral scene: two creatures with human bodies combined with the head and body of a fish, like the god Oannes, stand by a bed on which a corpse is laid out, swathed in its mummy-clothes; near them stand two monsters like the demons which appear in a battle scene belong-

ing to the campaigns of Assur-nasir-pal, and, of larger size, on the walls of Assurbanipal's palace; they face one another in the same attitude here as there, and seem to be disputing or quarrelling. The lowest row shows a stream of water in which are fish. In a boat is a kneeling horse; on his back is a monster holding serpents in his hands; lion-cubs are springing forwards towards him; another monster stands on the brink of the water; in the background are trees and fragments of different kinds, looking like the remains of a banquet. There is some artistic merit in several portions of this curious scene. The monster on the other side is boldly designed, and his form is vigorous and supple.

In the chiselling of a royal standard (fig. 106), the artist really attained to the highest technical skill: the bulls' heads and the lions' heads arranged along the pole are masterpieces of taste, and might be proposed as models at the present day. In the palaces fragments of thrones have been found formed of bronze plating. One of the most remarkable pieces, found at Van, belongs to M. de Vogüé (fig. 107); the deep sculpture in the claws of the crouching lion reminds the spectator of a bronze statuette from Tello (fig. 26).

§ III. WOOD AND IVORY.

No people of antiquity carried as far as the Chaldæo-Assyrians their taste for elegant furniture, which is as delicately sculptured among them as the most precious bronze utensils. We shall never know, doubtless, except through the testimony of literature, what that

carved wood-work was, and what those ceilings of cedar were, to which the prophets of Israel allude with such jealous enthusiasm, and which the kings boast of having had executed, speaking to us in their inscriptions of palaces in which "the gates are of ebony, with fittings of silver plating and polished iron, the pillars of cypress-wood, the posts of cedar carved by skilful craftsmen, and coated with plates of wrought metal." But the bas-reliefs place before our eyes wooden furniture in which the superiority of the Assyrian genius is conspicuous, and which reveal to us a people gorged with wealth, among whom luxury in furniture holds an important place. The animal and vegetable kingdoms are turned to profit by the craftsmen with astonishing skill in the decoration of the tables, stools, beds, tripods, umbrellas and fly-flaps. At every opportunity lions' heads and claws, goats, panthers and bulls occur, fancifully arranged, but always in perfect harmony and excellent taste; flowers, festoons, undulating and interlacing lines, rosettes and geometrical figures are all found in endless variety and in perfect equilibrium; nowhere has such work been better done, neither in Egypt nor in Greece.

The bas-relief (fig. 77), which represents Assurbanipal drinking with one of his wives, shows us some of the furniture of a royal palace. The prince reclines upon a divan, the queen sitting upon a chair, with a stool under her feet; before them is a table. Are not the sculptured couch, the table with its feet carved in the form of lions' claws, and the chair, lavishly decorated with sculpture and ivory ornaments, as rich and as skilful in workmanship as any such objects to be found

in European drawing-rooms? Another bas-relief (fig. 108) shows a tent erected in the open plain during a



Fig. 108.—Tent serving as the royal stable (Bas-relief in British Museum).

it is simply the stables, as it seems. Notice the elegance of the wooden pillars, the shafts of which are decorated with geometrical designs, and terminate in floral ornaments on which slender kids, ready to spring, are poised. Wood formed the framework of these chairs, coffers, and shrines, but disappeared more or less completely under the bronze or gold plating, the incrustations of ivory, coloured glass, lapis lazuli, and brilliant stones, or, lastly, the embroidered rugs and the carpets. In the camp before Lachish, Sennacherib sits upon a throne, the sides of which are composed of three rows of figures, raising their arms to sustain the bars of the chair.



Fig. 109.—Sennacherib's throne. Bas-relief (British Museum.)

Wood was the essential part of the structure of the chariots, the wheels of which have spokes turned in the

lathe, and the body of which is of woven wicker-work, while the pole, describing a graceful curve, ends in an elegant horse's head or in the head of a deer, a bull, a lion or a swan.

The very weapons, lances, daggers and bows have shafts, hilts, and handles carved into figures of animals, crouching, sleeping, springing or folded in two, similar to the figures drawn and carved by the mediæval decorators.




Fig. 110.—Assyrian chariot (from a bas-relief).

These objects, however, are not always of wood; oftenest, perhaps, they are of bone or ivory, as it is proved by the ivory tablets and the toilette articles, such as combs and pins, which the excavations have brought to light.*



Fig. 111.—Ivory plaque (British Museum).

But side by side with these knick-knacks in the Ninevite style, there are others which, though found in Mesopotamia, seem to be of foreign origin. Witness to this is borne by an ivory plaque found at Nimroud, which was certainly part of the incrustation of a piece of furniture (fig. 111). The relief is clear, the work highly finished; the figure, which holds in its hand a large lotus-stalk, has woolly hair like an Ethiopian, and bears the Egyptian Uræus on its brow.

* Perret and Chipiez, *op. cit.*, vol. ii., p. 319 ff.

Another tablet from Nimroud represents the head of a woman, whose hair is arranged in Egyptian fashion. She is enclosed in a frame which resembles a window with a balustrade, the capitals of which, original in style, seem to have been coloured. An ivory statuette of the goddess Istar, found at Nimroud, has the same heavy coiffure in successive rolls, and resting upon the shoulders; here we have again the Egyptian style with an exaggerated naturalism proper only to the Phœnicians. We may conclude that these ivories were fashioned, like the bronze dishes, in the workshops of Phœnicia. Thence caravans transported all these small objects as far as Nineveh; we know that the merchants of Tyre and Sidon had numerous stores in the very heart of Mesopotamia. Phœnician commerce was the great vehicle by which Egyptian and Assyrian art was carried abroad.

§ IV. LEATHER AND STUFFS.

The art of embroidery and tapestry, which we have seen so highly developed in primitive Chaldæa, and a most remarkable example of which was furnished us in the costume of *Marduk-nadin-akhi*, did not cease to flourish during the whole existence of the Ninevite empire, and was more prosperous than ever at Babylon in the time of *Nebuchadnezzar*. Can robes of greater richness be imagined than those worn by *Assur-nasir-pal*, *Sargon*, *Sennacherib*, or *Assurbanipal*? Are there, even at the present day, any embroideries or tapestries of more wonderful delicacy or in more exquisite taste? Assyrian stuffs are celebrated throughout the ancient

world for the beauty of their varied tints, and above all for the marvellous embroideries which the chisel of the Assyrian sculptor has so delicately reproduced? All this decoration, in which we find figures in adoration before the sacred tree or the symbol of the supreme deity, genii struggling with lions, fights between animals, the mystical pine-cone, flowers, and a hundred other varied designs elegantly and symmetrically arranged, reveals extraordinary manual skill. History, mythology, botany, and real or fanciful zoology are turned to profit with inimitable perfection, and we are forced to take



Fig. 112.—Assur-nasir-pal* offering a libation (Bas-relief in the British Museum).

everything literally that has been related by ancient authors about the tapestries which adorned the palace-chambers. In the banqueting-hall of Ahasuerus, king of Persia, there were, according to the

* Wrongly called Sennacherib by M. Babelon.

Book of Esther, white, green, and blue hangings, fastened with cords of fine linen and purple to silver rings and pillars of marble. In the description of a picture portraying the adventures of Themistocles, Philostratus the Elder also speaks of the various subjects embroidered by the Babylonians upon their stuffs, and of the golden threads skilfully mingled with the tissue; we have seen that the Babylonian stuff called




Fig. 113.—Richly caparisoned horse and rider (Bas-relief in the Louvre).

kaunakes, and characterised by rows of long fringes, was still celebrated among the Persians and the Greeks. Pliny, the natural historian, claims for the tapestry-weavers of Babylon the honour of having been superior to all their rivals in other countries in the art of harmonising colours and representing figures. "In fact," says M. E. Müntz, "the words, Babylonian tapestries, —*Babylonica peristromata*, recur constantly in the Latin

poets, who are never satisfied with praising them. Roman connoisseurs bought such hangings for their weight in gold. Metellus Scipio spent 800,000 sesterces in *triclinaria Babylonica*. Nero paid, for the same stuffs, an even higher price: 4,000,000 sesterces."*

Thus the East, which remains to our days the classical land of embroidery and tapestry, has only perpetuated the traditions bequeathed to her by Nineveh and Babylon when they ceased to exist.

The industries of saddle-making and working in leather, which are still so flourishing among the Turks, Persians, and Arabs, can be traced back, according to tradition, to the Assyrians who raised them to the dignity of an art. Notice the harness of the king's chariot horses. The leather straps, embroidered with red and yellow threads, form variegated trimmings. Sometimes a leather band, crossing the chest and fastened on the withers, is decorated with a double row of tassels, and finished off by bells. Another embroidered band descends from the top of the head, and sustains under the jaw a tassel formed of three tufts, one above the other, also adorned with bells. Above the head rises a superb plume with a triple crest. The head-piece is adorned with rosettes, and above the horse's eyes there is a band formed of overlapping scales, joined to the head-stall by a double tassel. Everything, including even the strap which holds the bit, and that passed under the nostrils, is relieved by rosettes and brilliant trimmings, and probably also by metal disks, perhaps of gold and silver.

* E. Müntz, *La Tapisserie*, p. 22.

§ V. ORNAMENTS AND CYLINDRICAL SEALS.

The excavations in Chaldæa and Assyria have, down to this day, scarcely furnished us with any ornaments of gold or silver. However, we know from the inscriptions that these metals occupied the first rank, and were abundantly employed in the ornaments of the Ninevites and Babylonians. The tombs of primitive



Fig. 114.—Assyrian deities carried in procession. Bas-relief (after Layard).

Chaldæa contained bronze bracelets and ear-rings of the simplest form. These are circular rings, sometimes thinner at the two ends, which are both pointed. At Khorsabad Botta found necklaces formed of precious stones pierced with holes, which were spheroidal in form or elongated like olives; these balls of marble, jasper, chalcedony, amethyst, lapis lazuli, were sometimes mixed with cylinders or other seals of conical shape. At Kouyunjik a necklace was discovered, formed of little golden balls alternating with little cylinders of the same metal. A bronze bracelet at the Louvre has lions' heads at the two extremities.

But we learn more from the bas-reliefs about the taste for ornament among the Assyrians, and about the goldsmiths' work at Nineveh and Babylon. Kings

and genii wear necklaces, ear-rings, diadems, and bracelets. Their forms are always elegant and present great variety. The diadems are circles, perhaps of gold, broader in the middle, and generally decorated with a rosette, in the centre of which a glittering gem was doubtless conspicuous. Deities carried in procession wear high tiaras also surmounted by a rosette, the essential element of which is a precious stone. Bracelets are worn above the elbow and on the forearm; these are circular disks, sometimes closed and decorated with rosettes, at other times ending in two lions', deers', rams', or serpents' heads; some are twisted two or three times round the arm. Among the ornaments which hang from the necklace, the cross, of that form which we call the Maltese cross, must be cited; the same symbol, which reminds us of the Egyptian *crux ansata*, is also found in the ear-rings (fig. 63).

As for seal-engraving, its abundant examples do not surpass in artistic merit the Chaldæan work which we have already described. Assyrian cylinders, that is to say, those which were especially manufactured at Nineveh, are distinguished from those of Babylon and Chaldæa by a drier and more commercial style of work.* Inscriptions are rarer, and engraved in Ninevite characters: the myths represented by the engravers are the same as at Babylon, but the figures have a more modern appearance: for instance, the winged bulls with human heads, and the genii with eagle's beaks and four wings, are copied from the bas-reliefs in the palaces of Khorsabad, Nimroud and Kouyunjik. The

* See especially J. Menant, *La Glyptique Orientale*, t. ii.

Assyrian cylinders of the archaic epoch present the technical characteristics that we have already indicated in Chaldæa: the joints of the limbs are rendered by



Fig. 115.—Archaic Assyrian cylinder (after Menant).

means of a drill producing small hemispherical holes, and the rest of the body is executed with another instrument which hollowed out parallel lines. These peculiarities are clearly distinguished on a fine cylinder which we give after M. Menant (fig. 115): it represents three figures who seem to sacrifice upon a tripod to the sun, the moon, and the seven planets.

The cylinders of the Sargonid epoch prove a progress parallel to that of Chaldæan glyptics; the traces left by the action of the saw and the drill have disappeared to make room for the modelling of the figures, which sometimes reach a degree of suppleness true to nature. We will cite as examples a cylinder




Fig. 116.—Assyrian cylinder. De Clercq collection (after Menant).

of the De Clercq collection, representing two genii in adoration before the sacred tree (fig. 116), and a cylinder in the British Museum (fig. 117) on which the god Rammanu is seen, armed with a bow and arrows, standing upon a crouching lion and receiving the homage of a pontiff.

The two cylinders are very fine : on the first, extreme exactness is to be noticed in the details of the costume, and great delicacy

in the features of the two genii. On the second, on the contrary, the forms have a freer and easier pose, and the scene has more life; the palm is remarkable for truth; the ibexes,



Fig. 117.—Assyrian cylinder. De Clercq collection (after Menant).

above all, are absolutely pure in design; the modelling of their thighs and flanks reminds us of the lions on the Chaldæan cylinder which we admired before (see fig. 35);



Fig. 118.—Assyrian cylinder. De Clercq collection (after Menant).

it also reminds us of the famous lioness among the sculptures of Assurbanipal's palace (fig. 81), which is probably contemporary with it. Assyrian glyptics has produced nothing more highly finished; like sculpture on a larger scale, it excels in the rendering of animal forms.

CHAPTER V.

PERSIAN ART.

THE most ancient * monuments of Persia date from no earlier period than the reign of Cyrus (B.C. 549—529). If any Persian art existed in the previous epoch, when the country was no more than a satrapy of the Median empire, its traces have not yet been found. Median art is scarcely known at all, except by a cylindrical seal at the British Museum, bearing a Median inscription,



Fig. 119.—Median cylinder
(after Menant).

upon which a rider is seen fighting with a lion: the rider's high tiara is characteristic, but the lion is copied from a Ninevite cylinder (fig. 119). No doubt this monument would not be enough by itself to prove that Median art was tributary to Assyrian art; but the description given us by Herodotus of the fortress of Ecbatana confirms the hypothesis. On the other hand, it is natural to suppose that the Persians, who were the vassals and consequently the political and religious heirs of the Medes, should have borrowed from the latter certain artistic traditions, if Median art had any originality of its own. Now, while a threefold foreign influence—that of the Chaldæo-Assyrians, the Egyptians, and the Ionic

* For the recent discoveries at Susa and discussion of Elamite remains, see Chapter IX. of this volume.

Greeks, is conspicuous in Persian works of art, there is nothing that can be referred to Media.

The monuments of the Achæmenid dynasty are gathered together upon three principal sites, the ruins of which have been explored in a fairly complete manner: Susa, where the Achæmenids, including Darius and his successors, erected their palaces at the spot on which the old capital of Elam, destroyed by Assurbanipal, formerly stood; Persepolis, the imposing remains of which form two groups, called at the present day Takht-i-Jemshid and Nakhsh-i-Rustam; lastly, the pile of ruins at Meshed-Murgab and Madar-i-Soleiman, two Persian villages in the valley of the Polvar, on the road from Ispahan to Shiraz, where, without doubt, the ancient city of Pasargadæ must have been.

§ I. CIVIL ARCHITECTURE.

When Cyrus had his new capital, Pasargadæ, built in the valley of the Polvar, he had completed the destruction of the kingdom of Cræsus, finished the conquest of Asia Minor, and made himself master of Babylon. The precise date of the monuments of Meshed-Murgab is fixed by the cuneiform inscriptions, which, while they are all composed in honour of Cyrus, are written in three versions, Persian, Medic, and Assyrian, and consequently we cannot place them earlier than the conquest of Chaldæa in B.C. 538. In his victorious expeditions through regions remote from the table-land of Fars, his native country, such as Mesopotamia, Lydia, and the coasts of Asia Minor, Cyrus had the opportunity of observing monuments which must have astonished him

by their architecture, and palaces which seemed to him far finer than those inhabited hitherto by his ancestors, princes of proverbial austerity and simplicity. He conceived the idea of constructing for himself a royal residence as sumptuous as those of Cræsus and Nabonidus, and of importing into the heart of Persia the architecture of Babylon and the Hellenic architecture of Asia Minor. His military successes assisted him wonderfully in this undertaking. The prisoners of war whom he captured at Babylon and in the Greek cities of Ionia became the workmen who built his palaces; and he allured the architects, whom he could not carry away by force, by loading them with wealth and honours. The successors of Cyrus continued, like him, to appeal to the artists of Greece, whose voluntary exile from their native country has often been remarked by historians. Pliny, for instance, cites a worker in bronze, Telephanes of Phocæa, who passed among his contemporaries as a worthy rival of Polyclethus, Myron, and Pythagoras, and whom the kings of Persia, Darius and Xerxes, attracted to their court, where he exercised his craft during the greater part of his career.*

The structures begun by Cyrus at Pasargadæ, which were never finished on account of his death, which abruptly ended the work, receive their inspiration both from Greek and Assyrian art; there is nothing to be referred to the architectural types of Egypt, not yet invaded by the Persian conquerors. The palaces stand upon platforms like those of Nineveh and Babylon; but these substructures follow the Greek method of building.

* Heuzey, in the *Revue politique et littéraire*, 1886, p. 661.

The monument called by the modern Persians *Takht-i-Madar-i-Soleiman* ("throne of the mother of Solomon") is nothing more than the platform of Cyrus' palace (fig. 120). It is a structure built of large stones, in which mortar is replaced by iron clamps. The facings are seldom trimmed, but only rough hewn, and surrounded by a double moulding like rusticated stonework with marginal draftings. The courses are alternate rows of headers and stretchers. The nucleus of the structure is a mass of blocks arranged in horizontal layers, always level with




Fig. 120.—Platform of the palace of Cyrus (after Dieulafoy).

the facing courses. M. Dieulafoy* observes that the Lydians practised this method of building from the eighth century before our era. The Assyrians did not proceed in the same manner. At Khorsabad, for instance, no clamps bind the stones of the facing to one another; the wall is straight and absolutely vertical, while in the *Takht-i-Madar-i-Soleiman* the upper courses recede from one another like steps, in order to give greater thickness to the base. Over the greater part of the facing, position marks have been detected,

* *L'art antique de la Perse*, t. i., p. 8.

carved upon them by the stone-cutters, in order to know the place of each hewn stone. These marks are conventional signs, which do not belong, it is true, to any alphabet, but which—a matter worthy of remark—are the same as those discovered in Greek buildings.




Fig. 121.—Basement at Persepolis (after Flandin and Coste, *Perse ancienne*).

The palaces of Persepolis were erected by Darius and Xerxes only fifty years after those at Pasargadæ; but in this short interval Egypt had been conquered by Cambyses; and after that event the monuments of the Pharaohs were destined, for the same reason as those of Assyria and Asia Minor, to exercise a direct influence upon Persian art. The latter, however, could never fuse these heterogeneous elements together and assimilate them to its own character, but could only group them in a hybrid style. The buildings of Persepolis are still standing to a considerable extent, and its ruins, rising in the midst of a vast amphitheatre of grey marble rocks, are an object of enthusiastic admiration to all travellers. The palaces rest upon a platform built on the model of that of Takht-i-Madar-i-Soleiman. The

outer coating of this basement is formed of carefully trimmed ashlar, and the blocks, fitted together without mortar, are fixed by iron clamps. Better preserved

than the ruins of Pasargadæ, those of Persepolis enable us to reconstruct more perfectly the principal forms of



Fig. 122.—Gate and windows of the palace of Darius (after Dieulafoy).

Achæmenid architecture. The platform of the Persepolitan palaces was ascended by a flight of a hundred and eleven steps, broad enough to be mounted by ten men abreast ; a gently inclined roadway, formed on one

side of the platform, enabled carriages to reach the summit: here we have precisely, except in point of material and manner of construction, the platform of the Assyrian palaces. The summit of the terrace was crowned, as at Khorsabad, with a row of battlements. The peculiarity of the artificial mound called Takht-i-Jemshid by the Persians is that it is only an immense basement supporting three other terraces of smaller area upon it. These terraces are of unequal height, and communicate with one another; they are reached by stone staircases. The grand staircase, leading to the second platform, is adorned with a colonnade and flanked by gigantic human-headed bulls, similar to those at Nineveh. Upon the highest of these three platforms were built four palaces, upon the walls of which the names of Darius, Xerxes and Artaxerxes Ochus have been found.

In the buildings at Persepolis and Susa, the doorways and window-frames take the form of a rectangular parallelogram, and in their architectural decoration, besides the traditional influence of Chaldæa and Assyria, the new exotic element, that we have indicated above, may be recognised; it is the intrusion of Pharaonic art. The doors, framed in three Græco-Ionian architraves, projecting one beyond the other, are surmounted, as well as the windows, by an Egyptian ornament above a line of alternate ovals and disks. In the thickness of the doorway sculptures in relief, copied from those of the Chaldæo-Assyrian palaces, show us the king in close combat with a lion or fantastic animal, or else the king sitting on his throne rendering justice at his palace gate, or again the prince

solemnly advancing, surrounded by his officers and dressed in his ceremonial robes.

M. Dieulafoy* recognised that the greater number of the windows were condemned to lessen the air and light in the interior of the rooms; these windows filled up by a thinner wall, formed, on the exterior, niches which broke the uniformity of the façade. Doors, windows, staircases and the pilasters arranged at the corners, are of white limestone or of grey porphyry with blue veins; but the walls in which these architectural features occur are of baked brick coated with enamelled tiles.

The architecture of the Achæmenid palaces includes the pier and the column as the supports of the structure. Among the ruins of Pasargadæ at present only three piers and one column, the height of which still exceeds 36 feet, are standing. But at Persepolis and at Susa, the Persepolitan capital, with all its elegance and



Fig. 123.—Persepolitan capital
(after Dieulafoy).

* *L'art antique de la Perse*, t. ii., p. 37.

originality, has been studied in all its varieties. It is found in every part, but notably in the great state saloon or *apadâna* of the palaces. It is thirteen times as high as its diameter at the base : its slender form reveals the imitation in stone of an original structure supported by light trunks of trees. The apadâna of the palace of Xerxes at Persepolis, situated on the middle platform, covered an area of nearly an acre and a quarter, and its roof was sustained by a hundred columns.




Fig. 124.—Plan of the *Apadâna* of Artaxerxes (after Dieulafoy).

Before the anterior façade rose a portico guarded by two gigantic bulls with human heads, partly built into the structure like those in the Assyrian edifices. The apadâna of the palace of Artaxerxes at Susa (fig. 124) was of no less gigantic proportions, and had a double portico on three of its sides; it covers an area of an acre and a half. The columns are not less than 18 feet 4 inches in diameter; slightly conical in shape, they are composed of long cylindrical drums, placed end to end, the base and capital being separated from the shaft. Two varieties may be distinguished.* The simplest type is to be seen in the interior halls of the palace of Xerxes at Persepolis. The base is formed of two tori placed one above the other on a square pedestal; the shaft is decorated all round with forty-eight flutings; the capital includes a series of ornaments borrowed from the architecture of Egypt; it is

* Dieulafoy, *op. cit.*, t. ii., p. 80.

developed in a succession of bells and inverted volutes, above which two bulls' heads are arranged, even with the intercolumniations; this is the bicephalic capital, characteristic of the Achæmenid architecture, which has never been employed except in Persia.



Fig. 125.—Susian capital restored (Louvre).

Other columns differ, but only in the base, from that which we have just described; the double torus supporting the shaft is sometimes placed, not on a square pedestal, but on a cylindrical drum, decorated with twenty-four vertical lines and growing gradually broader in the lower part, so as to present the form of a much elon-

gated ogee or of a bell. At Susa, instead of lines, the ornament of the base is sometimes formed of elegant inverted foliage (fig. 126). The comparative study of the Achæmenid column, together with the monuments of Egypt and Greece, has led M. Dieulafoy to conclude that the outlines of the Persepolitan column are Egyptian, but that its structure is composed of Græco-Ionian elements. These volutes, strings of ovals, and




Fig. 126.—Base of a column (after Dieulafoy).

tori at the base, had already become classical in the Hellenic world long before Cyrus, since they are found everywhere, at Mycenæ, Segesta and Selinus, in Attica and in Ionia: here again we are forced to recognise that the architect, even when he copies motives

derived from Egypt or Assyria, is imbued with the principles of Hellenic art.

Besides columns, the Persepolitan and Susian palaces had pilasters placed at the extremities of the porticoes, as continuations of the façades. In the façades of the palace of Darius at Persepolis two square pilasters of porphyry are seen, so perfectly preserved that in the upper part they still have holes, cut to receive the ends of the entablature. They would suffice to prove, if any proof were wanting, that in these structures, the

columns, which are placed at long intervals and are tall and slender, did not support stone but wooden architraves. These were enormous beams which formed a line even with the tops of the columns, and, running from capital to capital, and placed in grooves contrived with this object, contributed to give homogeneity and solidity to the structure. Upon these great beams the rafters of the roof were arranged, and then a flat ceiling supporting neither a terrace nor a second story.

It is important not to lose sight of the fact that the palaces, the elements of which we have just described,



Fig. 127.—Façade of the *Apadâna* of Artaxerxes
(restoration by M. Dieulafoy).

constitute an official kind of architecture implanted in Persia by the "kings of kings" who were pleased with the monuments that they had observed in Egypt, Assyria, and Asia Minor. Springing from the caprice of sovereigns, this foreign architecture never took root in the country, and was not required by the nature of the ground and the necessities of existence on the mountainous table-land of Persia; it disappeared with the Achæmenid dynasty. But by the side of this conventional architecture there was that created by the natives of the country, because it had been imposed upon them

as a condition of life. As well as the people of Chaldæa and Assyria, the Persians must have known how to build vaulted houses, alone capable of protecting them from the rays of a too ardent sun ; they also built, at least in the cantons of Susiana, houses with terraces, supported by palm beams and trellis-work arranged over the rooms which were narrow like passages. Strabo tells us this while speaking of Susiana : “ To protect the rooms from the excessive heat, the roofs are covered with two cubits’ depth of earth ; the weight of this earth obliges the people to build all the houses long and narrow, because, although the beams must not be very long, nevertheless the rooms must be spacious ; otherwise the people would be stifled.” Even at the present day, since the climatic conditions of the country have not changed, the method of building houses is the same as that practised by the ancient inhabitants of Iran. Travellers find houses, according to the wealth of the owner, surmounted by vaults, domes, and terraces, wonderfully suited to local requirements. It is, then, quite certain that the Iranians in the time of the Achæmenids knew the vault and the cupola as well as their neighbours on the banks of the Tigris.

But have the vaults and domes of Persia, more fortunate than those which rose above the Mesopotamian edifices, come down to us, at least in a few instances ? M. Dieulafoy believes so. The ruins held to be of the Sassanian epoch at Sarvistan, Firuzabad, and Ferashbad, would date, in his opinion, from the Achæmenid period. A certain reserve, however, is required, from the chronological point of view, in speaking of these monuments in which the traveller can still see brick cupolas supported

by pendentives,* these cupolas being 97 ft. high and 49 ft. in diameter, semicircular vaults, pointed vaults nearly similar to those of our Gothic churches of the thirteenth century—in short, all the elements of Sassanian and Byzantine architecture. On the other hand, the decoration of these buildings seems to have been remarkably poor; at Sarvistan the interior columns are heavy and badly hewn, the cornice placed at the foot of the vaulting is composed of nothing but a serrated ornament; the interior walls must have been coated with red paint; the exterior walls were smooth, and even the façade showed no decoration except groups of half-columns buried in the masonry. Not the smallest trace has been remarked among these ruins of bricks, whether enamelled or bearing figures in relief, or of those slabs imitating the wall sculptures of Assyria which were such characteristic elements of Achæmenid art. The same reflections are applicable to the monument of Firuzabad, the architectural decoration of which has preserved, perhaps only by tradition, elements of Persepolitan origin.

§ II. SCULPTURE.

In sculpture, even more than in architecture, the triple influence, Chaldæo-Assyrian, Egyptian and Græco-Ionian, which is dominant among the works of the Achæmenids, is to be traced. Like the sculp-

* Pendentives are generally held to have been introduced into architecture several centuries after our era, and to have first appeared in a perfect form in the Church of St. Sophia at Constantinople, the dome of which, as Procopius says (*De Edificiis*, Bk. I., c. 1.) seems to hang by a golden chain from the sky.

tures of Ninevite palaces, those of Pasargadæ and Persepolis are in low relief, the figures being always placed in profile, and arranged for the purpose of lining the lower portion of the walls. In the execution, however, the chisel of a Greek artist is felt, or at least of one who has studied under Greek masters.



Fig. 128.—Cyrus. Bas-relief
(after Dieulafoy).

M. L. Heuzey* reminds us that an archaic Greek school existed in Thessaly, which was remarkably flourishing, and the productions of which, such as the bas-relief known under the name of the Exaltation of the Flower, were closely analogous in the details and the finish of the work to the Persepolitan and Susian sculptures; there are the same draperies with broad flat folds, and the same methods of treatment in the muscles of the face and limbs. The most ancient Persian sculpture known is the famous bas-relief in which the full-length portrait of Cyrus himself has been preserved for us (fig. 128). Cyrus, of Iranian origin, has a face like that of an European; he has nothing in common with Egyptian and Assyrian faces; the top of his head is bald or shaved, his beard

* *Revue politique et littéraire*, 1886, p. 661.

is slightly curled, his hair is short and matted. But everything else in this royal figure is of foreign importation.

His head is crowned with a triple disk surrounded by Uræi, in the fashion of Egyptian deities; the king is furnished with wings, like the genii of Assyria and Chaldæa, and these wings, with rows of well-marked feathers, are like those of the Ninevite monsters. Even the border of the robe is decorated with a broad



Fig. 129.—Bas-relief at Persepolis
(after Flandin and Coste).

Assyrian fringe; finally, the king holds in his right hand a statuette, the headdress of which is surmounted by the Egyptian Uræus.

After the portrait of Cyrus in chronological order

come the bas-reliefs of Persepolis. These are some-



Fig. 130.—Bas-relief at Persepolis (after Flandin and Coste).

times episodes in the Chaldæo-Assyrian epic of Izdubar, which, imitated not only in Persia but also in the Greek world, gave birth to the legends of Heracles and Theseus, so often represented on archaic Greek monuments. In other bas-reliefs the court-officers walk in procession with the tributary satraps, or else (fig. 129) the "king of kings" him-

self, calm and impassive like a Colossus whom nothing can terrify, plunges his dagger, without moving a muscle

of his face, into the heart of a lion, a bull or a fantastic animal, which rises erect upon its hind legs, ready to devour him. Do not the exaggerated muscles of the beast betray a servile copy of the Assyrian monsters? Elsewhere, on the wall which borders the staircase of the palace of

Darius, a lion devours a bull (fig. 130); he bites him on the thigh, and furiously digs his powerful claws into his haunches. Though the lifelike attitude of the two animals strikes us, it reminds us, at the same time, of the Chaldæo-Assyrian cylinders in which a similar subject



Fig. 131.—Bas-relief from Persepolis (after Flandin and Coste).

is reproduced. Farther on, on the same wall of the staircase, servants appear to mount the stairs, with their hands loaded with presents of all kinds which they are about to offer to the "king of kings"; Assyrian sculptures contain analogous scenes. The same must be said of the bas-relief of the central door

of Darius' palace, in which the prince is seen attended by two servants, one holding the umbrella and the other the fly-flap (see fig. 122); how many times this subject is repeated on the Ninevite walls, with the same naïve representation of the king, like a Greek hero, as of colossal stature in comparison with the



Fig. 132.—Bas-relief at Persepolis (after Flandin and Coste).

persons of his suite, in order to exhibit his superiority and strength! On one of the walls of the apadāna of Xerxes' palace, the prince sitting on a high throne, with a canopy above his head and his feet upon a footstool, is seen surrounded by his guards. He is receiving a personage of high rank, doubtless a satrap, who is bringing on his shoulder the tribute of his

province. In the compartments below rows of Persian soldiers are drawn up in line, probably those that composed the famous guard of the *Immortals*; they carry lances, bows and quivers, and have swords at their sides. The throne is of a truly Assyrian form. "The canopy, made of woven stuff," says M. Dieulafoy,*




Fig. 133.—Bas-relief at Persepolis (after Flandin and Coste).

"is decorated with a very curious design. Each strip is composed of two similar bands heavily embroidered. A band covered with rosettes is followed by a band adorned with bulls like those which decorate the cornice of the royal tombs; in the centre appears the winged emblem of Ahura-Mazda. The lower band ends in a trimming covered with rosettes, and a thick

* *Op. cit.*, t. iii., p. 186.

fringe ; round patches adorn the angles. The position of the winged emblems on the top give this piece of drapery the appearance of an Egyptian tent, but the procession of bulls, the trimmings, the fringes, and the rich embroidery are of Assyrian origin."

The symbolic figure of Ormuzd, with his winged disk, is a reproduction of the similar divine figure so often seen hovering over the king and his soldiers on the



Fig. 134.—Portico at Persepolis (after Flandin and Coste).

Assyrian bas-reliefs. Scenes of most significant cruelty also passed from Chaldæo-Assyrian sculpture into Persian sculpture. On the bas-relief which Darius caused to be carved upon the rock of Behistun, to recount his exploits to distant posterity, the king is holding his bow as Sennacherib does, and placing his foot on the breast of a prisoner who holds out his hands in supplication, while nine other kings stand bound with chains, with

their hands behind their backs and cords around their necks.*

Like the porticoes of Ninevite palaces, those of Persepolis are garnished with human-headed bulls; the latter have preserved the walking attitudes, the curled hair, and often even the high tiara decorated with rosettes and feathers, which characterise their elder brothers on the banks of the Tigris. Only, while the Assyrian bulls are sometimes placed even with the surface of the façade and facing one another in the doorway, the Persepolitan bulls, on the contrary, are always placed parallel on each side of the opening and look outwards, facing the terrace. Finally, in the sculpture of these gigantic monsters the Persian artist shows himself superior to the Assyrian artist: while preserving the animals in the same hieratic posture, he has had the skill to soften the modelling of the limbs, and to give to the wings a more elegant and graceful curve; the bulls have only four legs instead of five; their flanks are more supple and plumper; the horns, emblems of strength, which surround the head of the Ninevite monsters, are suppressed; the anatomical forms and the respective proportions of the different parts of the body are more closely studied; we have here Assyrian art interpreted by artists formed in the school of the Greeks.

§ III. PAINTING AND ENAMELLING.

The art of enamelling brick, invented by the Chaldeans, did not perish with Babylon. The Achæmenids

* Lenormant and Babelon, *Hist. anc. de l'Orient*, t. vi., p. 18, f.

adopted it, and seem to have brought it to perfection; the same is true, as it seems, of that ingenious and delicate process which consisted of stamping scenes in relief upon bricks, a number of which thus formed an enamelled frieze, intended to replace the sculptured slabs of Nineveh. It was at Susa that this system of decoration seems to have reached its ideal perfection; at any rate, it is only among the ruins of this




Fig. 135.—The lion frieze; restoration by M. Dieulafoy (Louvre).

capital that we can study it in detail, thanks to the discoveries of M. Dieulafoy, which add a new chapter to the history of art. It has been possible to reconstruct at the Louvre two entire friezes disinterred at Susa before the façade of the apadana of the palace of Artaxerxes Mnemon. That of the lions (fig. 135) is composed of bricks in relief, 1 ft. 2 in. long by 7 in. high and 9 in. thick. The lions, nine in number, are each 11 ft. 3 in. long by 5 ft. 6 in. high. The ground, on which the figures stand out, is a flat surface of a

turquoise-blue colour; the lions, which are, for the most part, of a greyish-white colour, have certain parts of their body, for instance the mane, of a watery greenish blue; and others, for instance the swell of the muscles, of a deep yellow. They are treated in the Assyrian manner, to such an extent that, if i were not for the relief, they would exactly resemble the enamelled lions on flat bricks at Khorsabad. As at Nineveh, the muscles are exaggerated, the head and forepart of the lion too small. The procession of wild beasts is framed in several lines of elegant symmetrical designs: rows of chevrons, of Egyptian palmettes, and of Assyrian daisies.

The frieze of the archers (fig. 136) represents a procession



Fig. 136.—Susian archer (Louvre).

of warriors in relief, like those on the marble slabs of Persepolis; this is the most wonderful specimen

of polychrome Persian enamelling. The materials of which the composition is formed, instead of being, as in the lion frieze, baked bricks in the form of elongated parallelepipeds, are little squares, of which each side is 1 ft. 1 in. long, and 3 in. thick, made of artificial concrete, which combines the whiteness of plaster with the resistance of limestone. The soldiers are represented in profile and on the march. They carry on the left shoulder a bow coloured yellow, and a quiver of reddish brown. They hold in their hands a pike, the shaft of which ends in a silver knob. Their tunics, the colour of which alternates from one figure to another, is golden yellow or white; the shape of it is the same for all,—narrow, open at the side, with very broad gathered sleeves; it falls to the ankles and shows a certain variety of ornament; the stuff is spangled sometimes with green or blue daisies, sometimes with designs in the form of lozenges; the border is embroidered. A greenish turban, twisted into rolls, is placed on the head of these oriental soldiers, who wear bracelets, ear-rings, and yellow or sky-blue leather boots; their beard and hair are dressed in ringlets, in the Assyrian fashion. This is doubtless the rich costume which provoked the declamations of Greek rhetoricians against the effeminacy and corruption of the Persians. According to the testimony of Herodotus (vii. 83), the twisted turban on the hair, the golden ornaments, and the silver knob on the javelin, were the distinctive marks of the thousand knights and the ten thousand immortals who formed the escort of the "king of kings." There can be no doubt, then, that we are in presence of a group of this famous troop of janissaries, whom the Achæmenpi

monarchs recruited in great part from among the blacks of India ; a certain number of the figures on the frieze acquired by M. Dieulafoy actually have a skin coloured of a deep brown.

It is observed, from a technical point of view, that all the figures of one frieze came out of the same mould, and that they are exact repetitions one of




Fig. 137.—Polychrome decoration of the palace of Artaxerxes (Louvre).

another, though variously coloured. The vitreous coat is transparent and iridescent, like the enamel on porcelain ; the gamut of the colours is poor : blue, green, yellow, black, and white. These decided tints must, on account of their brilliancy, have produced a striking effect ; and under the hot sun of Susiana, the portico walls of Artaxerxes' palace sparkled more marvellously than even the richly decorated tiles of

Mussulman mosques and palaces. The interior of the apadāna seems to have been simply coloured by means of a red monochrome stucco, almost completely concealed, however, by the rich carpets and embroidered draperies with which the walls of all the chambers were hung.

§ IV. RELIGIOUS AND SEPULCHRAL MONUMENTS.

Ormuzd (Ahura-Mazda), the great deity of the Persians, was not to have, according to the regulations in the Avesta, either temples or statues. The conception of the supreme and only God, perfect in all things, was too vast to suggest any shelter for him except the vault of heaven in which he dwelt. Herodotus did not fail to observe this characteristic of Mazdeism and this absence of temples among the Persians: "The custom of the Persians," he says, "is not to raise statues, temples and altars to the gods; on the contrary, they treat those who do so as madmen: in my opinion, this is because they do not believe, like the Greeks, that the gods have a human form." However, Ormuzd is often represented on the monuments of the Achæmenid dynasty; he has the form of a man crowned with the tiara and enclosed in a winged disk (fig. 141). This is exactly, except in the modifications brought about by the progress of art, the figure of the deity in the Assyrian monuments.* Thus this symbol, borrowed from Mesopotamia, is a transgression of the precepts

* The existence of a supreme god, Ilu, among the Assyrian deities is not proved, though assumed by M. Babelon, who supposes that the winged figure on the Assyrian bas-reliefs is Ilu.

of the Avesta, and an act of tolerance which only penetrated into the monumental sculpture of palaces and tombs, and into the glyptic art. The only symbol admitted by the Avesta is the all-purifying flame. Hence the cultus of the sacred fire and the fire-altars, called pyrea or *atesh-gahs*, erected in the open air on heights. The *atesh-gahs* are the only monuments which represent the religious architecture of the Persians. Their remains are numerous, but they do not present many features of archaeological interest. Several of them are seen at a short distance from Nakhsh-i-Rustam which seem to be earlier than the time of Cyrus. On a platform reached on all sides by a few steps, an altar is erected in the form of a truncated pyramid, with four sides. At the corners small columns, attached to the structure, support semicircular arches, which sustain the stone slab on which the sacred fire was lighted.




Fig. 138.—The tower of Jur. Restoration by M. Dieulafoy.

After the conquest of Asia the Achæmenids generally gave to the fire-altars the form of Græco-Lycian chapels. In the sculptures of a royal tomb at Nakhsh-i-Rustam we see a king in adoration before Ormuzd, and a fire-altar, which has the form of a square block of masonry with projections in imitation of pilasters, supporting an entablature formed of three steps one above the other ;

the highest, larger than the other two, forms the platform on which the fire is lighted (fig. 141).*

The architectural influence of Assyria is manifest in the construction of certain fire-altars. Near Firuzabad are the ruins of Jur, particularly interesting on account of the remains of an *atesh-gah* ninety-one feet high, described by travellers, and apparently a copy of the staged towers (*sikkurat*) of Chaldæa and Assyria, a type of which, the most complete in existence, is here handed down to us. M. Dieulafoy remarks that the atesh-gah at Jur resembles the minaret of the mosque of Ibn Tûlûn, one of the oldest Mussulman edifices. Thus types of religious architecture invented by the Chaldæans exercised their influence even on the modern art of the East.†

The funeral rites imposed by the Avesta had another consequence—that of creating a kind of architecture unknown in any country besides Persia. Human corpses might neither be committed directly to the ground, nor burnt, nor thrown into the river, for this would have caused pollution to water, earth, and fire. Cities of the dead had been established in remote and deserted spots: these were tall round towers called *dakhmas*, built of masonry, and showing no architectural ornament even round the top. These towers supported a wooden trellis-work on which the corpses were laid; birds of prey came and tore these abandoned bodies to pieces: they often carried off separate limbs to a distance, where wild beasts devoured what was left of them. That which remained in the charnel-house was

* Coste and Flandin, *La Perse ancienne*, pl. 164.

† Dieulafoy, *L'art antique de la Perse*, t. iv., p. 79.

buried, but previously covered with wax to avoid all direct contact with the ground. Herodotus has preserved a reminiscence of these distressing practices. "The corpse of a Persian," he says, "is not buried until it has been torn to pieces by dogs or birds of prey. . . . The Persians cover the dead body with wax, after which they inter it." There is still at the present day in Persia a certain number of ruins of the sepulchral towers of the Mazdeans, and one of the best known is not far from Teheran.

But the dakhmas only served for popular burials; for the Achæmenid kings, at any rate, broke the Mazdean law, which perhaps itself made in practice an exception in favour of the royal family. The tombs of the Achæmenid princes can be divided, from the architectural point of view, into two large classes, according as they are or are not anterior to the conquest of Egypt. The former are conceived according to the style and plan of Græco-Ionian tombs, the latter according to the Egyptian hypogæa.

In the valley of Polvar-Rud, two and a half miles to the south of Takht-i-Madar-i-Soleiman, stands a small rectangular edifice, the probable burying-place of Mandane, the mother of Cyrus; the Persians call it Gabr-i-Madar-i-Soleiman, "tomb of the mother of Solomon" (fig. 139). The archaic Greek character of this monument is striking. Constructed of large blocks in regular courses, without mortar, the stones being cut and fitted with the greatest exactness, it is provided with a triangular pediment, the only one ever observed in a monument of ancient Persia; it is reached by six steps running all round the little building. The roof is formed

of flat slabs, sloping on each side according to the inclination of the pediment. Round the roof is a cornice composed of a reversed ogee enclosed within two fillets, an architectural decoration found repeated round the door, the double frame of which is copied from that of the Greek buildings in the Ionian style. The inner chamber measures scarcely six square yards. Round Gabr-i-Madar-i-Soleiman was a courtyard surrounded by a portico; the chapel was not exactly in the centre of the courtyard, but stood at the bottom of it, so

that an open space was left in front.



Fig. 139.—The Gabr-i-Madar-i-Soleiman (after Dieulafoy).

Not far from this is the tomb of Cambyses the First, the father of Cyrus. It is so dilapidated that only one façade is almost intact; this is enough, however, to enable us to compare

it with another tomb at Nakhsh-i-Rustam in a good state of preservation. Both of them were square towers, constructed of fine and regular masonry, the mortar being replaced by iron clamps. The tower, solid at the base, contains in its upper part a chamber, the ceiling of which is formed of large slabs fitted together; a staircase built outside gave access to a small door. The exterior façade is furnished on its four sides with false windows; the idea has even been adopted of building the back of these niches of black basalt, in order to give them the appearance of true

apertures. The summit of the edifice is composed of a cornice adorned with a row of denticulations.

When to all these details we add the rustication of the stones and the position-marks found on the blocks, it will be recognised that the architect and workmen came from Asia Minor and copied in servile fashion the sepulchral structures of that country. The architectural form of these towers reminds us of the Lycian tombs at Telmessus, Antiphellus, Aperlæ, and Myra, and above all of the celebrated Harpy tomb at Xanthus.

The descriptions given by Strabo (x. 3, 7), and Arrian (vi. 29), following Aristobulus, of the tomb of Cyrus, enable us to assert that it was like the square




Fig. 140.—Tomb of Cambyses I.
(Restoration by M. Dieulafoy).

towers of Meshed-Murgab and Nakhsh-i-Rustam : "The tomb stood in the middle of the king's gardens ; it was surrounded by trees, running water and soft turf. It was a square tower, low enough to be hidden under the thick trees which surrounded it. The base was solid and composed of large cubical blocks. In the upper part was the sepulchral chamber, covered with a stone roof. It was entered by a narrow door. Aristobulus saw in it a golden couch, a table with cups

for libations, a gilded tub for washing and bathing, and a quantity of garments and ornaments. There was a communication, by means of an inner staircase, with the chamber in which lived the priests who guarded the tomb." It is not permissible, then, to




Fig. 141.—Façade of tomb at Nakhsh-i-Rustam (after Flandin and Coste, *Perse ancienne*).

doubt that, in the time of Cyrus, the kings of Persia had tombs built like those of Lycia, and that the towers which we have described preserve for us specimens of them.

But after the conquest of Egypt, Darius, who, as we saw, admired the monuments in the valley of the Nile,

resolved to have a sepulchral cave hewn for himself, in the form of a *speos*, in the side of the rock, and analogous to the sepulchral hypogæa of the Pharaohs. His successors acted like him. The caverns of Darius and the princes of his dynasty, which are to be seen in the rocks of Nakhsh-i-Rustam and Takht-i-Jemshid, near Persepolis, differ in all points from the tombs of Cambyses I. and Cyrus : while the latter are square towers of masonry, those of the second Achæmenid dynasty are cut out side by side in the vertical wall of the mountain, and the façade, like that of the hypogæa at Beni-Hassan, is decorated with bas-reliefs. To reach these chambers it was necessary in the time of the Achæmenids, as in our own day, to be hoisted by ropes to a level with the aperture. The exterior sculptures are interesting. A colonnade with bicephalic capitals supports an architrave, the frieze of which is adorned with a procession of lions and surmounted with bas-reliefs. Two rows of soldiers fully armed raise their hands to sustain a sort of platform, the borders of which are decorated with two symbolical figures of lions provided with bulls' horns. These Persian warriors remind the spectator of the Assyrian soldiers who form the decoration of Sennacherib's throne. On the platform stands Darius on a pedestal in steps, dressed in the *persis* described by Herodotus, crowned with the *cidaris*, resting the end of his bow on the ground and stretching out his hand. Opposite him is a lighted fire-altar and the image of Ormuzd. Round this bas-relief and serving as its frame stand the figures of the satraps who helped Darius to slay Gaumates. The door of the cave is opened in the central intercolumniation. The

interior of the chambers was as severe as possible ; the roof is hewn into the form of a vault ; in obedience to the law of Ormuzd there is no trace anywhere of painting or inscription. The cavities for the sarcophagi are formed in the side walls, as in the sepulchral caverns of Egypt, Palestine, and Phœnicia.

§ V. ENGRAVED GEMS AND ORNAMENTS.

The glyptic art and the jewellery of the Persians maintain nobly and without any sign of decadence the artistic traditions of Chaldæa and Assyria. Assurbanipal and Nebuchadnezzar, when they made expeditions into the most distant provinces of Persia, Media, and Armenia, had spread through all these countries the productions of Assyrian industry and the taste for luxury and works of art ; their artists recruited their disciples there : like Alexander, they carried the torch of civilisation everywhere by their arms, and when the Achæmenids took up their residence at Susa and Ecbatana, they found the inhabitants profoundly impregnated with Chaldæo-Assyrian ideas and customs. To as high a degree as the Babylonians, the Persians love full dress and ornaments : each citizen of distinction has his cylinder or his seal hung from his neck ; he is covered with bracelets, rings, necklaces ; his tiara is decorated with pearls and sparkling stones ; his tunic, delicately embroidered, is encrusted with gems. In his house he displays a luxury in furniture which, handed on to the Parthians, will astonish the Romans and Byzantines : cups of gold and silver enriched with crystal and coloured glass, and adorned with figures in

relief; chairs, couches and tables overlaid with silver, gold, and carved ivory. In short, everything begotten of the passion for luxury among the Chaldæans in the matter of tapestry, embroidery, and goldsmiths' work, is also found among the Persians.

Only, the Persians were not servile imitators; they could give an original turn to the productions of their industry, even when they copied the Assyrians. There is in their cylinders and their seals a dry and nervous execution which characterises them as distinctly as the bulls of Persepolis are distinguished from the Ninevite monsters. It goes without saying also that the inscriptions and the details of costume give an absolutely precise character to the classification of the productions of the



Fig. 142.—Cylinder of Darius
(after J. Menant).

glyptic art under the Achæmenids. Here is, for instance, the cylinder of Darius, preserved at the British Museum. The whole scene is evidently copied from Assyrian seals, but the figure of the rampant lion and those of the horses are quite different in treatment from Ninevite art; the denticulated tiara of the prince, the disk of Ormuzd hovering in the air, and finally the inscription traced with mathematical regularity, complete the proofs of Persian origin in this fine cylinder.

As we remove ourselves chronologically from the origin of the art, more perceptible modifications are introduced into the *technique*, and new foreign influences

are revealed in Persian work. A cylinder (fig. 143), which belongs to a Russian collector, represents a scene which might be supposed to be imitated from the bas-relief at Behistun.



Fig. 143.—Persian cylinder
(after J. Menant).

Darius is here seen slaying with his lance a kneeling enemy, whose head-dress is Egyptian.

The special distinctions of the productions of the gem-engraver's art

under the Achæmenid dynasty are the sobriety and exactness of the work and the conventional character of the figured scenes; besides this, in consequence of the influence of Egypt and Phœnicia, the fashion spreads more and more of substituting for cylinders



λ

Fig. 144.—Persian seal. Conical.



Fig. 145.—Seal of Artaxerxes (Louvre).



λ

Fig. 146.—Persian seal. Conical.

conical, rhomboidal or spherical stones, flattened on one side, in order to form a field for the engraving. On these cones of chalcedony or agate the most common subjects are: the "king of kings" standing or kneeling, crowned with the denticulated tiara or

cidaris, and drawing his bow—a type analogous to that of the coins known under the name of Daries; the king stabbing a lion which stands erect before him; a pontiff before the fire-altar, adoring Ormuzd; sphinxes and gryphons which remind us of the Assyrian *kirubu*. An opal seal (fig. 145) obtained at Susa by M. Dieulafoy, shows two sphinxes crowned with the tiara of Upper Egypt in adoration before the winged disk of Ormuzd; in the centre, in a little medallion, is the portrait of the Achæmenid prince, no doubt Artaxerxes Mnemon. The delicate execution of the royal portrait is striking, and the elegant forms of the sphinxes are no less worthy of remark. As among the

Assyro-Chaldæans, it is in the representation of animals—lions, deer, antelopes, sphinxes, and gryphons—that the genius of the Persian engraver reveals its full strength. The winged and horned



Fig. 147.—Persian seal (Cabinet des médailles).

gryphon found on an engraved gem (fig. 147) is significantly analogous to a small limestone bas-relief in the De Luynes collection (fig. 148) which shows in what fashion Persian art interpreted the Assyrian *kirubu*, and the modifications which it required. The monster has the body and fore paws of a lion; his hind legs, armed with powerful claws, are those of an eagle; he has the ears of an ox and the horns of a wild goat; his eye, face, and half-open beak belong to the falcon; a bristling mane adorns a neck proudly arched like that of a horse; he has a lion's tail; his great wings with well-marked feathers resemble in their development those of the Persepolitan bulls. We

know nothing in Persian art superior to this figure, the symbol of strength and power, in which so many discordant elements are combined with so fortunate a harmony.* At Susa and Persepolis, as at Nineveh



Fig. 148.—De Luyne's bas-relief (Cabinet des médailles).

and Babylon, minor sculpture was not inferior to sculpture on a grand scale, and the style of the engraver sometimes produced as noble and as striking effects as the chisel of the statuary: the copy did not yield to the model.

* Compare Flandin and Coste, *Perse ancienne*, pl. 152.

See "Nations" No 240, p. 20 (July 6, 1911).

CHAPTER VI.

THE HITTITES.*

THE name of Hittites (Khatti, Kheta) appears simultaneously in the Bible, the hieroglyphic documents, and the cuneiform texts. It is given to populations of different origin who inhabited Syria from the Euphrates to the borders of Egypt, and also Cappadocia and the greater part of Asia Minor from the mountains of Armenia to the banks of the Halys and the Hermus. But the country which was particularly the centre of the Hittite dominions, and in which they established a homogeneous and lasting empire, is Northern Syria, that is to say, the territory which extends from the great bend of the Euphrates to the Orontes, and from the limits of the Aramæan oases of Palmyra and Damascus to the mountains of the Taurus. On the Euphrates they built the fortress of Carchemish (Jerablus), which remained like a threatening challenge in the face of Nineveh until the day when, about the year B.C. 710, the Assyrians gained possession of it; on the Orontes their chief towns were Kadesh and Hamath. It is among the ruins of these cities or in the neighbouring country,

* See especially W. Wright, *The Empire of the Hittites*, 8vo, 2nd ed., London, 1886; Perrot and Chipiez, *Hist. de l'art dans l'antiquité*, t. iv., pp. 483 to 812; O. Hirschfeld, *Die Felsen-reliefs in Kleinasien und das Volk der Hittiter* (*Abhandlungen der Berliner Akademie*, 1886).

including Cilicia, a geographical appendage of Syria, and also among the sparsely scattered ruins of Cappadocia and Asia Minor, that the remains of Hittite civilisation have recently been discovered, and that the works of its peculiar art have been found which we are about to describe in a few words.



Fig. 149.—The lion of Marash (after Wright, pl. 27).

§ I. HITTITE MONUMENTS IN SYRIA.

The Hittite art of Syria is derived from Assyrian art; it has nothing original either in the conception of its forms or in its technical execution. To characterise it in one word, we might call it Assyrian art interpreted by barbarians. In all its manifestations it is inferior to its model, like the works of the barbarians who copied Greek and Roman art. In imitation of the Assyrians, the Hittites confined themselves almost exclusively to sculpture in bas-relief. At Marash, on the Pyramus in Cilicia, it is true, a fragmentary torso has been obtained; but this is almost the only example of a Hittite statue in the round that we can cite. This figure, of coarse workmanship, is dressed in a fringed cloak like that which is to be seen everywhere on the walls of Ninevite palaces.*

* Perrot and Chipiez, *op. cit.*, t. iv., p. 547.

The bulls and other winged monsters, placed at the entrance of Assyrian and Persian palaces, which keep the mean between statuary and the bas-relief, also find their parallel among the Hittites. There is at the Imperial Museum at Constantinople a basalt lion, found at Marash, the head and neck of which are completely disengaged from the stone block; the fore paws are even with the front surface of the wall, and the body of the beast is continued round the corner. Thus it is sculptured on two sides in imitation of the Ninevite bulls, and the extent of servility in the copy is finally proved by an inscription in Hittite hieroglyphs covering the fore paws, in accordance with the singular fashion observed at Nineveh.

Assyrian influence is even more obviously conspicuous at Carchemish, a fact to which witness is borne by two figures standing on a crouching lion, which remind us of the rock sculptures of Sennacherib at Bavian and Maltheiyah.* Is not a pseudo-Assyrian style also to be detected in this figure† (fig. 150) surmounted by



Fig. 150.—Stela from Birejik (British Museum).

* Perrot and Chipiez, *op. cit.*, t. iv., p. 549.

† There is some doubt whether this figure is Hittite at all. It may be of Babylonian origin. (See Perrot and Chipiez, *Hist.*, t. iv., 550 f.) The boots are so slightly turned up at the points that they are more like those worn by Babylonian kings than the characteristic boots of the Hittites. The stela was brought from the castle of Birejik, not from the site of Carchemish, as M. Babelon states.

the winged disk, with his tunic open in front? However, his cylindrical tiara, his twisted hair, and the peculiar disks which he holds in his two hands, are features which the artist did not copy from Mesopotamia.

Like the Babylonian Istar, the Hittite Astarte is represented standing, in full face and entirely nude; she holds her breasts with the same indecent gesture, the first example of which belongs to the plastic art of Chaldæa. Nevertheless Astarte is



Fig. 151.—Fragments of sculpture from Carchemish
(from the *Graphic*, Dec. 1880).

winged and crowned with a conical tiara which are peculiarities of Hittite symbolism. The priestess performing adoration before her is veiled, like the figures of Assyrian women.

Sculptures in debased imitation of the Ninevite reliefs were ranged on a series of slabs in the Hittite palaces, as at Khorsabad or Kouyunjik. At Sinjerli, M. O. Puchstein found still in place, that is to say, lining the lower portion of the wall of an edifice, a complete set of bas-reliefs representing a deer hunt, a man struggling with a fantastic genius, and a train of

prisoners of war.* In another tell in the same region, three slabs placed end to end contain a scene from a lion hunt; the king is in his chariot with his charioteer, and draws his bow. Everything here—the form of the chariot, the harness of the horses, the costume of the prince covered with his coat of mail—betrays a copy of Ninevite sculpture. Even the lion, the anatomical forms of which are learnedly reproduced, brings to our memory the hunting expeditions of Assurbanipal. But at the same time the inferiority of the imitator is conspicuous in the arrangement of the scene, which lacks life and movement: the lion allows the javelins to be thrust into his eye and haunches in the most benevolent manner. What a difference from the vigour and litheness of the terrible beasts which bound roaring around the hunters, true sons of Nimrod!

When we leave the regions which lie near the Euphrates, the imitation of Assyria, though equally perceptible, is, perhaps, less servile and more free; a larger number of original elements enter into the composition of the scenes. At Rum-Qalah a bas-relief represents a bearded personage, wearing a cap, and dressed in a long tunic, drawn apart as if in imitation of the form of the drooping wings of




Fig. 152.—Bas-relief at Rum-Qalah. (*Gazette archeol.* 1883.)

* Perrot and Chipiez, *op. cit.*, t. iv., p. 534.

Assyrian genii. At his girdle he carries a dagger; in his left hand is a sort of lyre, in his right a palm-branch; the handle of a leathern bag is passed over his arm. The coarseness of the workmanship makes the imitation itself almost unrecognisable. On a basalt stela at Marash (fig. 153) two women, sitting on chairs with backs, are separated by a table similar to those that we have seen in Assyria; the costume of these women has also much analogy to the



Fig. 153.—Stela at Marash
(after Hirschfeld).

Ninevite garments; however, their high tiara, under their long veil, seems to be indigenous. The same characteristics of imperfect and coarse imitation are to be observed in other pieces of sculpture from the same place; the only features which are particularly original are the expression of the faces, the diadem, and the arrangement of the hair: the spectator feels that he is on the

confines of a territory which is already coming under the direct influence of the Hellenic art of Asia Minor.*

According to these examples, two groups of clearly distinguished Hittite monuments may be established in Syria itself: those of Carchemish and the region of the Euphrates, which are colourless copies of Assyrian works; and those of western Syria and

* Perrot and Chipiez, *op. cit.*, t. iv., p. 559.

especially of Cilicia, which, though also derived from Ninevite art, separate themselves from it to a greater extent, are ruder, and contain elements at once more original and more barbarous. As peculiar characteristics of the Hittites, we will point out the diadem, the high cap of the women, to which a long veil is fitted, and, above all, the shoes with turned-up points. These shoes, worn by men and women, have been described as the chief mark of the Hittite monuments; however, it must not be forgotten that these shoes are still worn, in our own day, not only in Syria but throughout Asia Minor, by the most various races.

§ II. HITTITE MONUMENTS IN CAPPADOCIA,

A canton of ancient Cappadocia, the Pteria of Herodotus, on the Halys, where the first meeting between Cyrus and Cræsus took place, contains a considerable number of Hittite ruins which have been particularly explored by MM. Perrot and Guillaume, and form a group by themselves in the history of oriental art. The village of Boghaz-Keui, the ancient capital of the Pterians has still, besides its fortifications $3\frac{1}{2}$ miles in circumference, bas-reliefs carved upon rocks which are called Iasili-Kaia, "the inscribed stone," and remains of buildings not completely indistinguishable. The royal palace, almost raised to the level of the ground, is a parallelogram 136 ft. by 185 ft. In the blocks which compose the wall, holes are observed for iron clamps, as in the Achæmenid edifices; as in the latter also, the stones are large but irregular; the upper portion of the wall was of brick-

work, as at Nineveh and Persepolis ; lastly, the palace of Boghaz-Keui was built on an artificial terrace. In the arrangement of the rooms, details peculiar to princely residences in all oriental countries are to be

recognised. The principal door forms an independent structure, to be compared to that of the palace at Khorsabad: it is 58 ft. high; two lions' heads, original in style, project on each side of the aperture, above monolithic door-posts.



Fig. 154.—The sphinx of Euyuk (from Perrot and Guillaume*).

The palace of Euyuk, as well as that of Boghaz-Keui, presents striking features of resemblance to those of Nineveh; its terrace, 812 ft. square, still rises to the height of 39 ft. The corners are turned towards the four cardinal points. The principal doorway is 11 ft. broad,* and on each side stand two

sphinxes, in place of the human-headed bulls. Next to these, all along the façade, was a series of bas-reliefs, the arrangement of which was the same as that upon the façades of Khorsabad and Kouyunjik ;

* Perrot and Guillaume, *Exploration archéol. de la Galatie, etc.*, pl. lxxv.

only, the sphinx, which is not Assyrian, discloses another foreign influence—that of Egypt. Cappadocian art was able to interpret the Egyptian type, and, on this occasion, did not limit itself to a dull copy. "In Egypt," observes M. Perrot, "the sphinx, to whatever variety of the type it belongs, is always represented in the reclining posture, never standing as here: instead of being treated as a bas-relief and placed in front of the doorway, it is sculptured in the round and set on both sides of the entrance, perpendicular to the path, towards the axis of which it looks." * Besides, in the sphinxes on the banks of the Nile, the extremities



Fig. 155.—Rock sculptures at Iasili-Kaia
(after Perrot and Guillaume).

of the hair, on each side of the head, fall straight without forming the curls which we see here. At Euyuk, the Egyptian sphinx is treated in the Assyrian style; the place which it occupies on the sides of the doorway, and the position of its paws, turn it into a sort of compromise between Egypt and Assyria, which vied with one another in this land of Cappadocia, in artistic influence as in political preponderance.

This double tendency is also observed at Iasili-Kaia. Here a rectangular chamber has been found 81 ft. by 37½ ft., hewn in the rock on three sides; the walls are covered with bas-reliefs forming a plinth.

* *Hist. de l'art dans l'antiquité*, t. iv. p. 667.

Another smaller chamber and a corridor contain similar sculptures; the height of the figures varies from 4 ft. 6 in. to 2 ft. 3 in. Two processions of




Fig. 156.—Rock sculptures at Iasili-Kala
(after Perrot and Guillaume).

figures go round the larger chamber and meet one another: on the right, women dressed in long robes with trains, their hair falling upon their shoulders, wearing a round tiara like the women at Marash; on the left the men, with the conical cap assigned by




Fig. 157.—Rock sculptures at Iasili-Kala
(after Perrot and Guillaume).

Herodotus to the Cimmerians, and a short tunic reaching no lower than the knees in front, but longer behind. In each group the figures grow larger in proportion to their nearness to

the centre. Many of them are not human beings, but winged genii, satyrs with goats' feet, dog-headed monsters. Nearly all hold in their hands sceptres, curved staves, two-edged hatchets; some stand upon quadrupeds. Two are seen perched upon a two-headed

eagle ; another, accompanied by a kid, stands on the shoulders of two porters.

Close to the entrance of this vast hall, a separate relief represents a giant standing on two mountains. This personage holds in his right hand a shrine, and in his left hand has a sort of long staff, the lower end of which is curved like a crosier ; he wears a hemispherical skull-cap, and is dressed in a long robe open at the side. The shrine which this deity holds is provided with two Ionic columns supporting the winged disk ; beneath the disk is a figure between two bulls seen in full face. At some distance a group of two figures is observed. One of them, of colossal proportions, is found elsewhere standing upon a quadruped. Here, he wears a highly decorated conical tiara, and is armed with a sword and clothed in a short tunic. He stretches out his right hand as if to carry or to seize a child standing before him. The second figure, protected by the deity,



Fig. 158.—Rock sculpture at Iasili-Kaša (Perrot and Guillaume).



Fig. 159.—Rock sculpture of Iasili-Kaša (after Perrot and Guillaume).

before him. The second figure, protected by the deity,

who passes his left arm round his neck and holds his hand, is the same as he whom we noticed just before.

The sculptures which decorate the walls of the vestibule in the palace of Euyuk have so great an analogy to those of Iasili-Kaia that it is impossible not to recognise their common style and origin. We observe among them a woman, seated upon a throne, with her hair flowing down upon her shoulders,



Fig. 100.—Rock sculpture of Iasili-Kaia (after Perrot and Guillaume).



Fig. 161.—Tomb of Gherdek-Kaia (after Perrot and Guillaume).

decorated with a necklace and bracelets, who reminds us of the Assyrian queen sharing the banquet of Assurbanipal; she raises a goblet to her lips, and holds a flower in her hand.

All these scenes are priestly and religious, and not, as in Assyria, devoted to the glory of the king and to the memory of his warlike exploits. They refer to the worship of the god Mên or of the goddess Mâ or Enio, the Cappadocian name of Anaïtis or Astarte,

whose rites Strabo describes as performed in the two towns of Comana.

To this Cappadocian civilisation, again, purely oriental and anterior to Greek influence as it is, the sculpture of tombs observed at Gherdek-Katasi, near Boghaz-Keui and Euyuk, must be referred. The principal of these caves hewn in the rock, like those of Phœnicia and Nakhsh-i-Rustam, has a façade adorned with a portico with three low colonnades, the style of which closely resembles the Greek Doric order (fig. 161). At the extremities of this portico are the doors of two chambers intended to contain sarcophagi. Both of them have windows opened in the wall of rock; the sepulchral couches are hewn in the wall like alcoves. There is something in these monuments which partakes of the character both of the Phrygian tombs and of those of Nakhsh-i-Rustam, and perhaps they are not anterior to the destruction of Pteria by Crœsus in B.C. 549.

To sum up: we must conclude, with M. Perrot,* that the monuments of Boghaz-Keui and Euyuk, witnesses of primitive Cappadocian civilisation, underwent Assyrian influence as well as those of Northern Syria. The palaces look like "a reduced copy of the great royal edifices on the banks of the Tigris and Euphrates." The winged figures, the monsters with eagles' and lions' heads, are Assyrian, and so are the deities borne on the backs of different quadrupeds, the flowers in the hands of the figures and the winged disk, the symbol of the deity. Various elements of the Cappadocian sculptures seem, upon no less evidence, to have

* Perrot and Chipiez, *op. cit.*, t. iv., p. 697.

been borrowed from Egypt, Persia, and even from the Greeks of Asia Minor, but this is exceptional. In any case there is nothing original and individual in this Hittite art of Pteria, except the eagle with two heads (fig. 162), which is evidently connected with the most ancient Asiatic worship, and suggests reminiscences of the Sirens; except also the long curved *lituus*, the robe cut in the form of a chasuble, the peaked tiara, the pointed shoes; details of dress

more interesting for the history of costume than for that of art.



Fig. 162.—Sculpture at Iasili-Kaia.

The connection of the sculptures of Pteria with those of Hittite Syria is quite clear; there are the same hieroglyphs, the same short tunic, the same long robe, the same

shoes, the same peaked tiara, and the same round skull-cap. The female garments are almost identical at Marash and Iasili-Kaia; the deities have similar attributes; the lion and the bull are the animals which both regions prefer to represent. We must conclude that the same semi-barbarous race, powerless to free itself, whether in art or politics, from the yoke of Egypt and Assyria, inhabited both the slopes of the Taurus; we will now examine how far this Hittite race extended its branches towards the west, and what monuments it left in Asia Minor beyond the Halys.

§ III. HITTITE MONUMENTS IN ASIA MINOR.

To the north of the Taurus and beyond the Halys, the monuments belonging to Hittite civilisation are, as in Cappadocia, bas-reliefs carved on the sides of rocks or not.

At Kalaba, near Ancyra, in Galatia, M. Perrot dis-



Fig. 163.—Rock sculptures at Ghiaur-Kalesi
(after Perrot and Guillaume, pl. x).

covered a large slab (4 ft. 4 in. by 2 ft. 6 in.) on which is carved a lion, analogous in style to those which we have met in Syria or in Cappadocia.* A nine hours' journey south-west of Ancyra, among the ruins called Ghiaur-Kalesi, the same scholar found two large figures, cut this time on the side of the rock. These are warriors, like several of those at Boghaz-Keui; both

* Perrot and Chipiez, *op cit.*, t. iv., p. 713.

wear a conical helmet or tiara, to which a piece of stuff is attached behind, which covers the nape of the neck ; they are clothed in a short tunic, drawn in at the waist by a sash ; their feet are shod with curved boots.

The sculpture at Ibriz, in Lycaonia, consists of an inscription in Hittite hieroglyphs and two colossal



Fig. 164.—Rock sculpture at Ibriz (from Wright, *Empire of the Hittites*).

figures, one 19 ft. 9 in. high, the other 11 ft. 9 in. A priest is standing in adoration before his deity. The god holds in his left hand an ear of corn, and in his right hand the branches of a vine which grows from the ground behind him. His tiara is provided with several pairs of horns, and his beard and hair are curled in the Assyrian fashion. The pontiff is thoroughly Assyrian in appearance and costume ; his robe edged with fringes is decorated with square or lozenge-shaped designs, which remind us of the tunic of Marduk-nadin-akhi (fig. 22), and also of the ornaments of the Phrygo-Hellenic tomb called that of Midas.

The ruins of Eflatoun, in Lycaonia, scarcely consist of anything more at the present day than the façade of

a ruined edifice; it is adorned with a bas-relief in which the winged solar disk is to be distinguished, the symbol of the deity in Egypt and in Assyria; below are two other smaller disks; then come two rows of figures with their arms raised above their head, as if to support an entablature.

Hittite monuments grow more rare as we leave Cilicia, Lycaonia, Cappadocia and Phrygia to penetrate into more western regions. However, fresh monuments are met with every day in Lydia and even on the coast of Ionia, accompanied by hieroglyphs which do not allow us to doubt of the origin of the people who carved them on the rocks. Herodotus attributed



to Sesostris two Hittite bas-reliefs, near Smyrna, which are to be seen at the present day. One, at the village of Nymphio, on the side of a rock which overhangs a branch of the river Hermus, rises at least 162 ft. above the ravine. In a niche, 8 ft. high, a warrior is seen wearing the conical tiara and clothed in a short tunic; he carries a lance and a bow; he is shod with the pointed boots. The second monument alluded to by Herodotus has been lately discovered by M. Humann; it is less well preserved,

Fig. 165.—Rock sculpture at Nymphio
(*Revue arch.*, t. xiii, 1866).

and represents an almost exactly similar warrior.* Besides traces of Hittite inscriptions, the style of these rock sculptures, the costume and attitude of the figures connect them inevitably with the bas-reliefs of Cilicia, Lycaonia, Cappadocia and Syria; there is the same indistinct outline and the same lack of modelling. Wherever the Hittite people went, they remained feeble imitators; the works of art which they have left us can be referred to two or three types, copied from Assyrian and sometimes from Egyptian sculpture, but always much inferior to the model.

Less mediocre is the manufacture of models in serpentine which have come down to us, and which were employed by Hittite or Lydo-Phrygian goldsmiths in making metal ornaments or talismanic figures. The two most curious of these matrices are that which is preserved in the Cabinet de Médailles under the name of *Baphomet*, and another, found a few years ago near Thyatira in Mæonia.† The latter, which is $3\frac{1}{2}$ in. high by $4\frac{1}{2}$ in. broad and $\frac{1}{2}$ in. thick, shows us a naked woman, with her hands upon her breasts like the Babylonian Istar; next a man, perhaps Bel-Marduk, clothed in the Chaldæan robe with a series of fringes one above the other. Farther on there is a lion with a ring, intended to hang the ornament when it came out of the mould; a sort of altar; and, finally, the planetary symbols found on a large number of Assyrian monuments.

In the glyptic art, Hittite engravers surpassed themselves, and showed themselves worthy of their Ninevite masters. Far be it from us to treat with disdain the

* Perrot and Chipiez, *op. cit.*, t. iv., p. 750.

† S. Reinach, *Rev. Archéol.*, 1885 (3 se. t. v.), p. 54, ff.

seal-impressions on terra-cotta, the seals of precious stone and the cylinders, the inscriptions and figures upon which have only recently attracted the attention of archæologists. The silver seal, now lost, of the king Tarkudimme, bears a bilingual inscription in Hittite hieroglyphs and in Assyrian cuneiform. A cylinder at the Louvre, found at Aïdin, in Lydia, shows a scene of presentation to a deity (fig. 167). Three figures walk in the same direction, with their hand upon their mouth, carrying the curved sceptre which we noticed in the rock sculptures of Iasili-Kaïa ; a large table, supported by two lions, is laden with offerings. Then comes an Assyrian genius with two faces, a deity sitting upon a throne, and some secondary figures.



Fig. 166.—Boss of Tarkudimme (after Wright).



Fig. 167.—Hittite cylinder (Louvre).

element in it ; this is the decorative part of the cylinder. The ornamental design occupies, indeed, a considerable place on the surface ; it is composed of a double border of interlacing lines and symmetrical scrolls, which are never met with except in monuments of the Hittite glyptic art.

* *Gazette archéol.*, 1887 (t. xiii. p. 60).

M. Heuzey* has observed that though the subject is almost entirely Assyrian, there is, nevertheless, a national

CHAPTER VII.

JEWISH ART.

PALESTINE, which unites Syria to Egypt, was inhabited by numerous Semitic and Canaanitish tribes which have left us very meagre remains of their art. Like that of the Hittites, this art drew its inspiration both from Assyria and Egypt, though it never did more than imperfectly imitate them. Pharaonic influence is, however, more deeply to be felt here than among the Hittites, since Palestine was nearer to the valley of the Nile. The most important inhabitants of this region were the Jews, and in spite of the poverty of our archæological documents, numerous scholars have, for three centuries, taken a special interest in the works of this people who played so extraordinary a part on the stage of the world. It must be added that almost all these researches have been concentrated upon the exploration of the Temple of Jerusalem and its furniture, which in fact were the highest effort of Jewish art ; and though the monuments themselves are no longer in our hands or before our eyes, there is not a single edifice in all oriental or classical antiquity of which we possess written descriptions so circumstantial and so numerous. A hundred restorations of the Temple, taking these as their basis, have been attempted ; the least complicated system, and that which has obtained the greatest scientific

credit, is that of M. de Vogüé. We will correct and complete it by means of the more recent researches of English explorers. Accordingly, all the art of Palestine being concentrated in the Temple of Jerusalem and its furniture, we shall only speak incidentally of the few other ruins anterior to the Macedonian epoch that have been remarked, whether in Judæa or among other nations of southern Syria, and even among the Nabatæan Arabs.

§ I. THE TEMPLE OF JERUSALEM.

The city of Jerusalem occupies at the present day the southern extremity of a plateau bounded on the east by the Valley of Kedron, and on the west and south by the Valley of Hinnom. This plateau is cut in two from north to south by a ravine called the Tyropœon Valley, so that it forms two hills—one on the east, Mount Moriah, the southern extremity of which, called Ophel, was Sion or the city of David; the other on the west, of much larger extent, to which the name of Sion is improperly given at the present day, and to which the city began to extend only under the kings of Judah. When Solomon ascended the throne, Jerusalem consisted only of Sion or the city of David—that is to say, the narrow hill of Ophel, between the Kedron and Tyropœon valleys. Mount Moriah, on the north, was given up to cultivation, and a rich man of Jerusalem, Araunah, possessed some ground there, with a threshing-floor on which camels and oxen trod out the corn at the time of harvest. David had bought the field of Araunah in order to build upon it the Temple of

the true God, and before beginning the construction he had erected an altar on the threshing-floor in order that sacrifice might at once be offered to Jehovah. The materials were collected in great part before the work began; architects, workmen and artists recruited at




Fig. 168.—Site of the Temple on Mount Moriah.*

Tyre, thanks to the assistance of King Hiram, hastened to the spot, and the building began in the fourth year of Solomon's reign (B.C. 1013).

The summit of Mount Moriah, the centre of which formed the threshing-floor of Araunah, had to be levelled in order to serve as the site of the structure of the temple. In one place the hollows had to be filled, in another the ridges had to be cut away. The central

crest was therefore surrounded by an immense quadrangular rockwork bounded by Cyclopean walls of the height of the truncated summit. These supporting walls, extraordinarily thick, formed of enormous blocks fastened

* From Wilson and Warren, *The Recovery of Jerusalem*, p. 298 (1871).

by iron clamps, were also embanked on the outside at the base, and all the empty spaces and interstices between the interior wall and the living rock were filled up with a nucleus of rockwork, so as to form on the upper part a square platform. A F G L is the threshing-floor thus surrounded. At the north-western angle—that is to say, A B C D—it was necessary not to construct a supporting rampart and fill up the declivity of the mount, but, on the contrary, to cut away the natural rock into the form of an angle, so that at this point the enclosure of the temple was bounded by a natural wall rising perpendicularly to the height of 26 ft. A trench dug by the English explorers at the north-eastern angle B L K proved that at this point, on the contrary, the artificial rockwork of the temple basement must have reached the colossal height of 123 feet. On the south, at E F G H, a labyrinth of vaults and corridors, supporting a mass of collected material, was contrived in the substructure, which at the south-eastern angle. at the point G, forms at the present day a terrace 45 ft. high ; and yet the accumulated rubbish causes the foot of the wall to be more than 65 ft. below the present surface of the ground ! By the system of levelling which we have described an irregular quadrilateral was obtained, the eastern and southern sides of which are 1520 ft. and 1611 ft. long, and the northern and southern side 1017 ft. and 921 ft.

As Mount Moriah extended in a northern direction beyond the temple enclosure, the platform was on this side accessible to all comers. To remedy this inconvenience, and turn the new structure into an isolated citadel as well as a temple, a broad trench was hewn in

the rock on the north-east, A B ; and on the north-west, B L, a gigantic moat called Birket-Israil, which at the present day, though filled up to the extent of two-thirds, is still 104 ft. broad and 65 ft. deep. "Thus," concludes M. de Vogüé, "we have a large quadrilateral excavated on the north, supported on the south by vaulted sub-structures, and surrounded on three sides by terraces and on the fourth side by a broad moat. Such is the entirely homogeneous whole of the Haram esh-Sherif; such almost it has existed for long centuries, for successive destructions and rebuildings have little altered the primitive plan."* We shall see directly, in the company of the same scholar, that this immense pedestal, the work of Solomon, was only modified and enlarged by Herod on one of its sides.

However, the platform thus prepared was not quite level with the natural crest of rock which crowns Moriah. The culminating point of this rock, called Sakhra, still rose 16 ft. above the terrace. Instead of sapping this peak of chalky limestone and removing it, it was taken as the level of a second platform above the first, but concentric with it and much smaller. This is the upper terrace which at the present day supports the domed building improperly called the Mosque of Omar, which would better be designated by its true name, *Kubbet es-Sakhra*, "Dome of the Rock." According to M. de Vogüé, the threshing-floor of Araunah, on which David set up the altar of Jehovah, was a little to the north of the Sakhra, where later the altar of burnt-offerings was placed.

After building the platform, Solomon occupied himself

* M. de Vogüé, *Le Temple de Jérusalem*, p. 3.

with the structure properly so called. The temple, or more plainly, the house of Jehovah, was to be enclosed in two concentric courts. Solomon had only time to finish the first court,—that which immediately surrounded the edifice, and then the eastern side of the second ; this was not completed till long after his death, in the reign of Manasseh. As soon as the interior building was ready, Solomon resolved to devote it to the worship of God, without waiting for the completion of the second court. He celebrated the solemn dedication of the temple only seven years after the laying of the first stone of the substructure. The Bible has bequeathed to us the description of the interior magnificence of this sanctuary, built and decorated by Phœnician workmen, and of the works of art collected within it by the most sumptuous of Jewish monarchs. The architecture and the interior ornaments were all Egyptian in style, like the Phœnician temples themselves. But nothing is left of the building of Solomon except the cisterns and the eastern side of the second court. This court is decorated with a portico, under which Solomon had the royal throne placed on which he sat when he was present at public ceremonies ; it was still called, even after Herod, the Porch of Solomon.

Under the kings of Judah there were numerous works of enlargement and restoration ; but all was destroyed in B.C. 588, when Jerusalem was taken by the Chaldæans. Nebuzar-adan, Nebuchadnezzar's lieutenant, caused the temple to be set on fire, and all was over with the legendary magnificence of the son of David.

Fifty-two years later the Jews who had been taken captive to Babylon were set free by Cyrus, and their

leader Zerubbabel at once undertook to restore the temple of the true God. The work, hindered by the jealousy of the Samaritans, was not finished till B.C. 516. Sufficiently similar in plan to that of Solomon, the new temple was less beautiful and less grand in its proportions; the old men wept when they remembered the former house. In the course of centuries the new temple underwent many modifications, at least in its exterior, although the original plan was not upset to any considerable extent. For instance, in the time of the Maccabees, the exterior enclosure was extended on the north, and at the north-eastern angle the fortress named *Baris* was built, which Herod altered in later times and which became the famous tower of Antonia. However, the temple of Zerubbabel lasted for nearly five centuries without being destroyed, and had the good fortune, rare in the ancient East, to pass through the period of Seleucid rule and the Roman conquest under Pompey, without being either pillaged or demolished. Herod, a man of Idumæan race, appointed king of the Jews by the Romans, conceived the project of making himself popular among his people by rebuilding the temple in all the splendour which Solomon had originally bestowed upon it. In the first place, he brought all his efforts to bear upon the enclosure, which he resolved to enlarge; he doubled it, according to Josephus. Instead of four stadia in circumference it grew to six, preserving its former length on the smallest side, so that in fact it became geometrically double in area. This enlargement took place on the south, towards Ophel, so that the actual edifice of the temple, instead of standing in the middle of its peribolus, was removed to the north. The

tower of Baris or Antonia continued to form the northern boundary. In the annexed figure, A B C D is the ancient peribolus, T the temple, and C D E F the square portion added by Herod.

“In order to carry out this plan,” says M. de Vogüé, “Herod had the ancient terraces rased to the ground and rebuilt, as well as the colonnades which crowned them. Only he respected and enclosed the eastern colonnade called the Porch of Solomon and its fine supporting wall. This is the only part of the former temple that he seems to have preserved: all the rest was destroyed in order to be born again, restored to youth, and enlarged; the inner sanctuary was demolished to its foundations.”* The work undertaken by Herod began about the year B.C. 18. Ten thousand workmen were employed upon it under the direction of a thousand priests,




Fig. 169.

who alone might work with their hands in the Holy Place and the Holy of Holies. Eighteen months were enough to raise the inner building, but eight years were required to rebuild the court and the colonnades. The accessory structures were not finished till the year 64 after Christ, in the reign of Nero; at this date the work was occupying eighteen thousand workmen.

The foregoing historical considerations compel us to conclude, with M. de Vogüé, that the Haram-esh-Sherif represents the very enclosure enlarged by

* M. de Vogüé, *Le Temple de Jérusalem*, pp. 21 and 22.

Herod. In fact, the southern side of the Haram is 919 ft. long, the circumference is 5,006 ft., which, with the addition of 508 ft. for the projection formed by the tower of Antonia, make 5,514 ft.—that is to say, six times the length of the southern side. Besides, Herod could not develop the enclosure on the north on account of the tower of Baris and the gigantic moat *Birket-Israël*, which bounded it on that side, nor on the east on account of the abrupt declivity which forms the side of the valley of Kedron, nor on the west where the Tyropœon valley is. The enlargement could only take place on the south, and, moreover, as the ground was sloping, it was necessary, in order to remove the declivity, to proceed as Solomon had done : that is to say, to construct an immense artificial platform, supported on three sides by high terraces. The great substructures of the Haram esh-Sherif are the remains of Herod's gigantic work. If since the time of that prince the structure of the temple has been several times overthrown from top to bottom and continually rebuilt, these successive restorations have not altered the original plan of the substructure ; the fragments of wall which remained in place served as bases for the new edifices. The consequence of this is that in these walls different layers of masonry are perceived one above the other like geological strata, the original Herodian courses being naturally the lowest.

The most ancient masonry visible, the lowest, is formed of the largest blocks ; the courses are from a yard to two yards high ; the length of the blocks varies between $7\frac{1}{2}$ yds. and $2\frac{1}{2}$ ft. One block is to be observed at the south-eastern angle which is 13 yards long.

Each layer recedes 2 in. from that beneath it; the stones, carefully trimmed, are laid without mortar. These large blocks are marginal-drafted—that is to say, each stone is, as it were, bounded by a groove which marks the courses and the joints. Besides the groove, each block is framed in a chiselled band smooth but not deep, which forms a second frame, carved within the groove round the surface of the hewn block. The lower masonry of the temple is, then, drafted and chiselled at the edge; besides, at intervals, the surface of the blocks is provided with projecting tenons, no doubt contrived to facilitate the placing of them. The best preserved portion of this masonry is the Heit el




Fig 170.—The Jews' Wailing-place
(after M. de Vogüé).

Maghreby, "the western wall," where the Jews come every Friday to weep over the destruction of Jerusalem and to await the Messiah; it is the Wailing-place. Recent English excavations, carried 107 ft. below the present surface of the ground, have proved that this masonry is to be found all round the enclosure of the Haram.

The system of construction immediately above the drafted blocks is characterised by Roman masonry formed of smooth stones without grooves, their outer surface being carefully fluted by means of a chisel with

very fine teeth. The blocks, about a yard square, are laid with sharp-edged joints. This system is especially remarked on the western and southern sides. The following systems, in the order of their position one above the other, do not deserve to be described; they are relatively modern and belong to all epochs, but chiefly to the Saracenic period.

Not far from the Wailing-place, 39 ft. from the south-eastern corner, is the celebrated beginning of the bridge which united the temple to the city, crossing over the Tyropæon; it belongs to the first system of the substructure, and forms part of it. The English excavations have brought one of the piers to light; they have shown that the roadway of the bridge is 295 ft. long, and that the breadth of each arch amounts to 16 yards. While digging at the foot of the pier a pavement was discovered which no doubt represents the street which passed along there before Herod's epoch, or rather even before the destruction of the Temple by the Chaldæans. Some foundation is formed for this conjecture by the fact that when the English broke up this pavement and dug lower still they found the extrados of a vault: this was nothing less than the arch of another bridge of colossal masonry, which in the course of centuries had been buried under masses of rubbish: Herod, and perhaps Zerubbabel before him, built over the ruins without even trying to clear away the bridge. Who knows whether this arch, called *Robinson's arch*, from the excavator's name, is not the remains of a bridge erected by Solomon?

In the mass of substructure beneath the Haram, the existence of vaults and of a network of corridors

of drafted masonry has been proved, and these must, from the character of the work, be contemporary with Herod. On the platform, two cisterns are seen which probably date from Solomon's time, if they are not even earlier, though it must be admitted that they have been subjected to successive restorations. One is under the rock Sakhra, the other in front of the mosque of El Aksa: the latter, especially, which is the largest, is a superb artificial grotto, upheld by pilasters contrived in the side of the rock. The descent into that under the rock Sakhra is by a flight of fifteen steps; in the centre is a well which by means of a subterranean canal opens into the valley of Kedron, and was perhaps used by Araunah the Jebu-site.




Fig. 171.—The western door. Present state (after M. de Vogüé).

The outer enclosure built by Herod was pierced by several gates giving access to the terrace, which are still partly preserved. They are subterranean with regard to the platform; their threshold was of course on a level with the ground outside, and they opened on the staircases formed in the thickness of the terrace. At the present day, as the ground outside has been raised by rubbish of all kinds, Herod's doorways are filled up either entirely or partly. The *Western Gate* (fig. 171), near the Wailing-place, is at the present day buried to the extent of two-thirds. It is surmounted

by a great monolithic lintel 16 ft. long, and its structure belongs to the Herodian system of masonry, but it has undergone subsequent alterations within.

The two most important of the ancient gates are on the southern side; they are called the *Double Gate* and




Fig. 172.—Interior View of the Double Gate.

the *Triple Gate*, on account of the number of their arches.

The two arched apertures of the Double Gate give access to a large vestibule, the vaulting of which is supported by an enormous central column; here the

hottest hours of the day might be passed in comfort. From this vestibule there is an ascent to the upper platform by two parallel flights of steps separated by a row of pillars. There is nothing left of the time of Herod but the two outer jambs of the door, the middle pier, two monolithic lintels similar to those of the Western Gate, and, lastly, the central column of the vestibule. This column is squat, for it is only four of its own diameters in height; it has no base. Its capital, which broadens into the form of a basket, is decorated with acanthus leaves in very low relief all round.

The *Triple Gate*, also situated on the southern side of the Haram, 67 yards from the Double Gate, is similar to the latter, except that instead of two arches it has three; besides this, a triple sloping corridor led to the upper platform.

The *Golden Gate*,* opened in the eastern side of the enclosure, was in its original form similar to the Double Gate and the Triple Gate; and, like them, it is about $6\frac{1}{2}$ yds. below the level of the platform to which it gave access; nothing is left of the first structure except the two monolithic jambs 10 ft. and $13\frac{1}{2}$ ft. high, which seem to be even earlier than Herod's building. On the north, there was only one entrance, on a level with the platform, which communicated with the outside by a bridge thrown across the great moat.

Now that we have arrived at the terrace we are going to pass through the different parts of the

* This name is at present given to a building which has nothing in common with this door of the Temple.—M. de Vogüé, *Le Temple de Jérusalem*, p. 12, note.

buildings. They are commanded by the tower of Antonia, which was built by the Asmonæan kings, under the name of Baris, and enlarged and embellished by Herod; it occupied the north-eastern angle of the structure. Its base was a scarped rock, the flanks of




Fig. 173.—Plan of Herod's temple
(after M. de Vogüé).*

which had been cut away by human hands; its outer wall of enclosure was three cubits thick. An enormous trench cut in the rock isolated the fortress on the north, and four turrets flanked the outer curtains at the angles. Two flights of steps led straight down from the fortress into the outer court of the Temple.

The great outer court was on three of its sides surrounded by a double portico—

that is to say, by two rows of columns of the Doric order, 25 cubits high; the roof, upheld by this double portico, which was

* A, Ophel.—B, Bridge.—C, Tyropæon.—D, Causeway.—E, Tower of Baris or Antonia.—F, Portico.—G, Court of the Gentiles.—H, Court of the women.—K, Court of Israel.—L, Altar of burnt-offerings.—M, Court of the priests.—N, Solomon's porch.—O, Moat called *Birket Israil*. FF, Double gate and triple gate.—Q, Golden gate.—R, Kedron valley.

30 cubits broad, rested upon the outer wall. Or the south, instead of a portico there was a *basilica*, that is to say, "a building with three naves of unequal height, supported by columns." The aisles were 32 ft. broad and 50 ft. high; the central nave was 48 ft. broad and 100 ft. high. There were 41 columns in each row, which gave 754 ft. for the whole length of the basilica. The central nave was supported by three rows of Corinthian columns, and there were columns attached to the side walls which corresponded to each row. The




Fig. 174.—Bird's-eye view of Herod's Temple
(Restoration by M. de Vogt ).

building had a panelled ceiling of carved wood. The basilica opened on the bridge which cut the valley of the Tyropæon, and its axis was in a straight line with the axis of the bridge.

Such was the court of the Gentiles, accessible to all visitors. A barrier, only three cubits high, prevented profane intruders from penetrating into the enclosure reserved for the Israelites, which was contained within that of the Gentiles. M. de Vogt  thinks that this low wall of separation, on the southern side, must have corresponded to the boundary of the outer enclosure of the ancient temple of Solomon.

The enclosure reserved for the Israelites included the *women's court* and the *men's court*, or that of *Israel*. From the Gentiles' court access was obtained to the women's court by a flight of fourteen steps. This court had, at its four angles, square chambers which served for the stores of the Temple, for the ablutions and other pious exercises; there was also the Treasury chamber, in which the specie was kept which was coined for the exclusive use of the temple. Between these chambers rose porticoes. On the inner side, the women's court was separated from the court of Israel by a series of buildings which opened on the court of Israel, and the entrance into this court was by three gates, each provided with porches and five steps. The principal gate, celebrated under the name of the *Gate of Nicanor*, on account of its fine architectural proportions and the richness of its construction, was a folding gate of Corinthian bronze: twenty men were needed to open and shut it; before it was a semicircular flight of fifteen steps.

The court of Israel, reserved for the men who had accomplished certain acts of purification, was 11 cubits broad. The chambers which surrounded it on three sides were used as appendages to Divine worship; their façade was provided with porches. Each of them was consecrated to a special service: the skins of victims were salted and washed in them, musical instruments, salt, the perpetual fire, and wood were kept in them; the hall in which the Sanhedrim held its sessions was one of them.

A step one cubit broad, which the priests alone might cross, separated the court of Israel from the court of

the priests, and, in the middle of this court, the temple properly so called and the altar of burnt offerings stood. "The altar of burnt offerings was formed of three stages of rough-hewn stone, each stage a cubit less on all sides than that beneath it; the base formed a square of 32 cubits; the total height was 15 cubits high; the ascent was by an incline situated on the south, 30 cubits long; two smaller staircases led to the intermediate platform. On the upper surface the sacrificial fire burnt, and at the four corners were horns on which the blood was sprinkled and libations of wine and water were poured. A conduit situated at the southern corner of the altar received these liquids, and carried




Fig. 175.—The Altar of Burnt-offerings
(Restoration).

them off into the subterranean drains, and thence into the valley of Kedron."* At the north of the altar of burnt offerings six rows of iron rings were seen fixed to the ground in order to fasten the animals to them; there were also eight small columns to which the victims were suspended that they might be cut to pieces and flayed, and eight tables upon which the flesh was placed.

The temple properly so-called, which stood 22 cubits to

* M. de Vogüé, *Le Temple*, p. 56.

the west of the altar of burnt offerings, was built on a terrace six cubits high, mounted by a flight of twelve steps. There was thus a difference of $27\frac{1}{2}$ ft. between the level of the temple platform and the court of the Gentiles. As for the architectural arrangement of the building, it was similar to that of Solomon. The anterior pylon was 100 cubits high and 20 deep; at each extremity there were chambers in which the sacred knives were kept, which were used for slaying the victims. The Holy Place or *Hekal*, and the Holy of Holies or *Debir*, only separated by a veil, were both 60 cubits high, 30 broad, and together 65 cubits long measured from outside. "A series of thirty chambers and three stories was attached to the sanctuary, as in the ancient temple, for a length of 15 cubits, measured without, and this gave to the sanctuary outside the appearance of a basilica. The whole edifice was roofed with terraces, on which gilded points were fixed to drive away the birds."*

The Jewish Temple was one of the grandest architectural works that the genius of the ancients produced. The successive enclosures raised one above the other, and crowned by the gigantic pylons of the sanctuary, built of white marble, were the result of an inspiration of genius that has never been realised except in this instance, and all antiquity had but one voice to proclaim its imposing majesty. "When the rays of the rising sun struck upon the metal plates which covered the doors and roof of the sanctuary, when they illuminated the gilding on the façade, and the gigantic golden vine which spread its tendrils over the white marble of the

* M. de Vogüé, *Le Temple*, p. 37.

pronaos, the spectator's eyes were dazzled, and he was forced to turn them away, and the stranger who perceived the temple in the distance thought he saw a mountain covered with glittering snow."*

Such was the temple of the God of Abraham, Isaac and Jacob, restored by Herod, in which many of the scenes of the Gospels took place, and which was destined for so dramatic and mournful a fate. At once a public market, a house of prayer, and a fortress, it was condemned to be the tomb of Jewish nationality. Besieged and taken by the Romans, after a resistance unique in the annals of antiquity for its heroic desperation, it succumbed before the violence of Titus, and was profaned by Roman legionaries with torches and pickaxes in their hands. The echo of its fall, solemnly marked in the pages of human destiny, still resounds among us, for it was the overthrow of antiquity, and the irreparable destruction of the old civilisation of the East.

§ II. THE DECORATION AND FURNITURE OF THE TEMPLE.

The house of the Eternal was adorned with unheard-of splendour; precious woods, gold, silver, ivory and gems—nothing was spared by this people, jealous for the honour of their God; the accessories also of the worship of Jehovah, sacred vessels, knives, basins and utensils of every kind were works of art in which the chiseller and the metal-founder had each emulated the other's skill. But the artists who decorated the former

* M. de Vogüé, *Le Temple*, p. 58.

temple, let us not forget it, were Phœnicians. Now, the Phœnicians always confined themselves to the imitation of Egypt and Assyria; their technique has a hybrid character, which is, like Syria itself from a geographical point of view, a sort of compromise between Asia and Egypt. On these principles of criticism alone can we attempt to restore the decoration and furniture of Solomon's temple.

The veil hung between the Holy Place and the Holy of Holies, and concealing the latter from sight, was a large piece of silk, on which the skilful hand of Eastern embroideresses had represented the image of the world; the four colours which entered into its composition were the symbols of the elements: purple represented the sea, saffron fire, hyacinth air, byssus earth. The inner walls were panelled with carved planks of cedar. In the Holy Place these wood-carvings represented colocynths and open flowers; in the Holy of Holies, palm-trees and fantastic animals or cherubim were mixed with the flowers. This decoration was relieved by plates of gold fixed on the wood with nails of the same metal. The Ark of the Covenant, in the Holy of Holies, was sheltered under the wings of two immense cherubim of wood overlaid with plates of gold. The different parts of these monstrous figures were borrowed from the animal world, like those of the winged bulls in the Ninevite palaces. According to the Bible, the cherubim are winged and have bulls' feet; they draw Jehovah in his chariot or carry Him upon their back, like the Assyrian deities. Each cherub has at the same time a human face and a lion's face. They form a silent procession upon the cedar panels, the

leaves of the olive-wood doors, and the veil before the Holy of Holies, alternating with palms and colocynths, which, at Jerusalem, are substituted for the Egyptian lotus.

In the Holy of Holies there were two colossal statues of cherubs, 10 cubits high, overlaid with gold, which guarded the Ark of the Covenant. Each cherub had two gigantic wings, one outspread and drooped over the ark which it overshadowed, the other symmetrically outspread in the opposite direction and raised towards the ceiling. M. de Vogüé ingeniously compares with this description the Egyptian representations of two figures with long wings, kneeling on each side of the symbolic scarabæus or the solar disk supported by uræi, which they cover with their wings.




Fig. 176. — Egyptian naos and cherubim (M. de Vogüé, p. 33).



Fig. 177.—Egyptian ark and naos (from an Egyptian painting).

The Ark of the Covenant itself resembled those *naos* or *bari* which we see carried by Egyptian priests upon their shoulders. It was of acacia-wood (*shittim*), covered with plates of gold both inside and outside. It was about $1\frac{3}{4}$ yards long, 2 ft. 8 in. broad and high. The lid was called the Throne of Jehovah. The ark contained the two tables of stone upon which the law of Sinai was engraved.

In the Holy Place was the altar of incense, on which incense was burnt in honour of Jehovah; this was probably a sort of tripod, surmounted by a bowl with a lighted brazier. There was also the table of shew-bread and the seven-branched candlesticks. The table, on




Fig. 178.— Egyptian table of offerings (M.de Vogué, p.33).

which twelve loaves were placed every week, was undoubtedly analogous to the tables of offerings to the gods so often represented in Egyptian bas-reliefs, with loaves piled upon wine-pitchers; furniture of the same kind also seems to be spoken of in the cuneiform inscriptions of Nebuchadnezzar. The bas-relief on the Arch of Titus at Rome represents Jewish captives carrying on their shoulders the furniture of their ruined temple, and among this spoil figures the table of shew-bread such as it was in Herod's Temple, under the form of a square cippus.

The seven-branched candlesticks, ten in number, had a peculiar form, also revealed to us by the Arch of Titus and some other monuments. On the base with two steps a central stem is fixed, to which six branches are fitted, three on each side, arranged in the shape of



Fig. 179.— Seven-branched candlestick (M.de Vogué, p. 33.)

a fan. Each of the seven branches is adorned with three flowers and a socket. On the base, fantastic animals are seen in relief. Hiram-Abi, the famous worker in metals from Tyre, in Solomon's pay, also

“made lamps and tongs of gold, and bowls and snuffers and basons and spoons and censers of pure gold,”* shovels and goblets of bronze. The candlesticks and other treasures of the Temple, carried away to Rome by Titus, were seized by Genseric during the sack of the city by the Vandals (A.D. 455). They were removed to Carthage, but, on the conquest of the Vandals by Belisarius, were taken in triumph to Constantinople. The Jews petitioned the Emperor Justinian to restore these treasures to the Holy City, to which they rightfully belonged, and he is said to have ordered that they should be sent to one of the Christian Churches in Jerusalem, but we hear no more of their fate in the pages of history.†

In the court of the priests, before the vestibule of the Temple, there were two separate bronze columns, reminding us of Egyptian obelisks, named Jachin and Boaz. The restoration of these two columns, marvels of Phœnician art, and invested in the eyes of the Jews with a talismanic power, has often been attempted. They were hollow, and their metal walls were $3\frac{1}{2}$ in. thick. “Their capital, 5 cubits high, had the form of fleur-de-lis, the lower part of which, swelling outwards, was covered with a reticulated ornament enclosed within




Fig. 180.—Capital of the bronze columns. (Restoration by M. de Vogüé).

* I Kings vii. 49-50.

† Procopius, *De Bello Vandalico*, ii., chap. 9; Theophanes, *Chronographia*, p. 168, and Georg. Cedrenus, *Hist. Comp.*, p. 606 (Ed. Bonn, 1833).

two rows of pomegranates."* The total height of each column was 41 ft., the diameter of the shaft was 6 ft. 5½ in., the pomegranates, 200 in number, formed a double collar round each capital.

In the court of the priests, near the altar of burnt-offerings, which was itself covered with bronze, the famous *brazen sea* was placed, a great reservoir from which the priests drew water to purify themselves before the sacrifice. This bronze basin, which resembled the calyx of a tulip, was five cubits high



Fig. 181.—The brazen sea. (Restoration.)

(8 ft. 7 in.), and ten cubits (17 ft. 2 in.) in diameter; its exterior was decorated with two rows of colocynths in relief: the wall was 3½ ft. thick, as in the bronze columns; it contained at least 8,800 gallons. Instead of feet, the brazen sea was upheld by twelve bronze figures of oxen, in groups of three, which, in accordance with the proportion of the basin, must have been larger than life.

This gigantic basin was fixed and immovable; for

* M. de Vogüé, *Le Temple*, p. 34; Perrot and Chipiez, *op. cit.*, t. iv. p. 315 ff.

the purpose of drawing water, wheeled basins had been constructed, ten in number, also of bronze, into which the water intended for ceremonial purposes was poured. Each had four wheels, like a chariot; the wheels supported a square box, above which was placed the cylindrical basin, large enough to contain from 150 to 170 gallons. The walls of the receptacle and of the box which supported it were decorated with palms, colocyntns, oxen and winged lions in relief.



Fig. 182.—Movable basin. (Restoration.)

Such were the principal features of the temple furniture; smaller utensils, knives, pincers, tongs, dishes, are scarcely known to us. An exact idea of them can, however, be formed by an examination of the products of Egyptian and Assyrian industry, especially of the dishes, vases, and utensils found among the substructures of the Phœnician temples in the island of Cyprus.

Various passages in the Bible enumerate the orna-

ments of the priests, such as the *ephod*, which, in certain cases, signifies the liturgical vestment; in others a sort of sacred casket, containing two talismanic cubes, called *urim* and *thummim*. The priestly costume of Aaron is an embroidered garment in which gems are set, according to the Book of Exodus. As early as the period of Genesis, we see the children of Israel making use of seals of precious stone, precisely as their neighbours the Egyptians and Chaldæans did. A certain number of gems carved in intaglio have come down to us which bear names apparently Jewish: Shebaniah, Nathanyahu, Hananyahu, Obadyahu. These seals for the most part only bear the name of their possessor; they have neither ornament nor symbol.

§ III. CIVIL ARCHITECTURE.

The temple of Jerusalem, in which the national life of the Jews was concentrated, was also, as we have said, the summary of their art and industry. In vain have many archæologists, during the last sixty years, made efforts to discover in Palestine, or in the other regions of southern Syria, and even in the heart of Arabia, traces of an art which might have flourished in these regions before the arrival of the Greeks and Romans. Travellers have indeed observed at Ala-Safat, at Jebel-Musa, in the land of Moab, on the Bahrel-Huleh in Galilee, near Hesban, and in many other places, dolmens and upright stones, analogous to those in Africa, in Brittany, and on Salisbury Plain, and remains of walls of Cyclopean masonry, no doubt

built by those giants, the Rephaim and the Anakim, who, as the Bible tells us, were the first inhabitants of these regions. Certain circles of great blocks, like those of Minyeh and Deir Ghuzaleh in the land of Moab, may have marked the bounds of sacred enclosures, temples in the open air, that is to say, of those *bâmoth*, or "high places," of which the Scriptures so often speak. But these barbaric remains, like the borders of certain wells at which, perhaps, the flocks of the patriarchs slaked their thirst, have little interest for the history of art. No idea can be formed of civil architecture except by imaginary restorations. Solomon's palace, which communicated with the temple and was situated to the south, upon Ophel, was demolished and rebuilt twenty times with incessant modifications, until its final ruin. The principal building, standing in the middle of a spacious court, enclosed by supporting walls which bounded the hill like the temple-enclosure, was called the *House of Lebanon*, after the place whence the timber was brought of which it was partly constructed. It was 100 cubits long, 50 broad and 30 high; its walls were built of large blocks; forty-five cedar columns were counted in it, divided into three rows, and supporting architraves of the same sweet-smelling wood.* This edifice was used as an arsenal: like the monarchs of Nineveh, the kings of Judah had a magazine of weapons in their palace.

Behind were the royal apartments, consisting of a hall of columns, and another room panelled with cedar, called the *throne-room*; in front of the former stood a

* Perrot and Chipiez, *op. cit.*, t. iv., p. 463.

porch 50 cubits long by 30 broad. There were also the *selamlık* and the *hareem*, arranged as in all oriental palaces. The offices communicated with the city by means of the *Horse Gate*; the *Upper Gate* gave access to the temple-enclosure. This is the extent of our information upon the subject of Solomon's palace.

The palace of Hyrcanus, at Arak el-Emir, and the fortifications of Jerusalem and of the Tower of Antonia, are purely Græco-Roman, and do not come within the sphere of our work. However, the English explorers discovered by their soundings on the slope of Ophel, above Kedron, a fortified wall which presents several kinds of masonry one above the other; the lowest masonry is perhaps earlier than the rebuilding of the ramparts by Nehemiah after the Babylonian captivity: in this case it would date, if not from the reigns of David and Solomon, at least from the time of Jotham and Manasseh. The base of the quadrangular bastions is formed of very regular courses, sometimes rusticated; the blocks are 8 ft. long by 3 ft. 3 in. high; the marginal draft is even found in places. This tradition of bevelled masonry has been already noticed in the Herodian substructure of the Temple; it is also to be seen in the wall of Hebron (fig. 183).

In a country which generally lacks drinking water, the building of cisterns is a matter of importance, and this is the case in Judæa. One of the most remarkable works of this kind is that which carries the waters of the Fountain of the Virgin to the Pool of Siloam. In the tunnel an inscription has been found which enables us to fix the date of the work about the

reign of King Hezekiah, and teaches us by what methods this subterranean canal, 1,750 ft. long, was successfully hewn in the rock. Two bands of workmen attacked the mountain on both sides at once, and the miners, after numerous windings, which increased the labour and the length of the tunnel, at last struck "pick against pick," says the inscription, "and heard one another shout" on each side of the barrier. Thus the water was carried along a passage not more than 2 ft. broad and of a height which varies from 1 ft. 5½ in. to 14 ft. 7½ in. But bold as this work may appear in the hands of Jewish engineers, who possessed neither compass nor exact geometrical instruments, it teaches us nothing from the point of view of art, any more than the aqueducts hewn in the rock which are found in other parts of Palestine.



Fig. 183.—The tomb of Abraham at Hebron (after Vogüé, p. 119).

§ IV. TOMBS.

Palestine and the north-east of Arabia are covered with sepulchral monuments, but there are few which date from the pre-Hellenic epoch. Abraham bought a cave called Machpelah from the Hittites of Hebron for 400 shekels of silver, and was buried there, as well as

the other patriarchs of his race. The site of the cave is at the present day covered by a mosque, and in the crypt of this mosque the bodies of the patriarchs are supposed to lie. Now, the wall of the crypt, a superb



Fig. 184.—Absalom's tomb (after F. de Saulcy, *Voyage autour de la Mer Morte*).

piece of masonry of imposing appearance, is incontestably contemporary with Herod; there is the same marginal draft that we have studied in the enclosure of the temple built by that prince. The tomb called Absalom's is also a small building not earlier than the time of the Seleucids, and if it preserves, like the Palestinian structures of the same epoch, a few architectural reminiscences of Phœnician art, it has columns, capitals, and mouldings which are entirely Greek. We need not, therefore,

occupy ourselves with these monuments, or with the tomb of the Maccabees at Modin, or with the not less celebrated *hypogæa* known under the name of *Kebûr-el-Melûk*, or "Tombs of the Kings," *Tomb of Jehoshaphat*, of *Saint James*, with its Doric portico, or *Tomb of Zacharias*: sepulchral chambers which are

visited by pilgrims in the neighbourhood of Jerusalem, and the date of which Saulcy has in vain tried to place even farther back than the Babylonian captivity. The tomb of Joshua, among the ruins known under the name of Khirbet-Tibneh, north-west of Jifneh (Gophna), does not seem to be more ancient.

In Arabia, at Medaïn Salih, several tombs have been observed hewn in the rock, the façade and inner arrangement of which are identical with those of the Palestinian caves. There are Greek columns, pediments and mouldings mixed with a few traditional motives, the original birthplace of which is in Assyria or on the banks of the Nile; cavities for sarcophagi are arranged around the chambers as in the Jewish tombs. The inscriptions obtained at Medaïn Salih prove that these burying-places were formed during the first eighty years of our era.



Fig. 185.—Sepulchral chamber at Medaïn Salih. (Doughty, *Doc. Epigr. du nord de l'Arabie.*)

However, at the village of Siloam, near Jerusalem, there is a tomb, known under the name of the *Egyptian Monolith*, which seems to be far earlier than all those of which we have spoken; there are some who would even assign it to the epoch of Solomon. This trapezoidal monolith, Egyptian in style, is 13 ft. high, and the platform measures 19 ft. 10 in. by 17 ft. 10 in. The door which looks westward gives access to a square ante-chamber which leads into a room 8 ft. long on each side. The ceiling of the chamber is slightly convex, like many Egyptian hypogæa; two large niches

are contrived in the walls. Outside, the monument is provided with an Egyptian cornice. All tends to demonstrate that this tomb is earlier than the Babylonian captivity, in spite of the architectural alterations to which it has been subjected at a relatively modern period. Besides, to whatever date the sepulchral caves



Fig. 186.—The monolith of Siloam (after Saulcy, *Voyage autour de la Mer Morte*).

of Palestine belong, they are all conceived in accordance with the same traditional type, which is also that of Phœnicia, and which we shall find at Carthage; there is always a speos hewn in the rock, a façade with Egyptian, Assyrian, or Greek ornaments, according to the date, then a vestibule giving admission through a low, narrow doorway into a sepulchral chamber.

From this chamber the visitor penetrates through one of several apertures into other rooms ; and round these more or less numerous chambers the cavities for sarcophagi are cut. Thus the cave of Machpelah at Hebron




Fig. 187.—Tomb in the valley of Hinnom
(after Saulcy).

must have been arranged as early as the time of Abraham, and in the same fashion, without doubt, the sepulchral cavern was formed in which the ashes of the kings of Jerusalem were deposited. The discovery

of the hypogæum containing the sarcophagi of the princes of the house of David would doubtless be more important for epigraphy than for archæology properly so called. It would only confirm the verdict pronounced upon Jewish art : that it is entirely wanting in variety and originality in every instance except in the Temple of Jerusalem.

CHAPTER VIII.

PHœNICIAN AND CYPRIOTE ART.

THE Phœnicians, established on the coast of northern Syria, were not simply the agents of commerce ; they also carried the art of the great Asiatic civilisations to all the coasts upon which they set up their factories, and among all the races with whom they formed relations of business. Their manufactured products have no more marked originality than those of the Jews and Canaanites : a mixture of Egyptian and Assyrian art is observed in them. These two powerful foreign factors, if they had been brought into action by an ingenious and enquiring people, would no doubt have begotten a new art which would have summed them up and absorbed them, by combining them with the peculiar inventions of the national genius : this was the case in Greece, for example. But the Phœnicians, exclusively occupied with business, were content to seek sometimes from Assyria and sometimes from Egypt the elements of a bastard industry, in which the exotic forms are so little disguised and so imperfectly fused that it is as easy as possible to detect them.

If ancient authors and epigraphic texts attest the importance of the Phœnician factories in Greece, Italy, Sicily, Gaul, Spain, and Africa, none of the great

nations of antiquity has left fewer material traces than this of its industrial and artistic life. In Syria, Cyprus, Malta, and Carthage we have great trouble in finding vestiges of the structures raised by the Phœnician architects, or statues or ornaments which can be attributed to the craftsmen of this nation: the historian of art is obliged to glean in any direction that he can the poor waifs and strays which he considers, in spite of himself, as extremely precious, but which he would often disdain if they came from Assyria or Egypt. Cyprus, partly inhabited by a Hellenic population and thrown by nature like a bridge between Asia and Greece, scarcely forms an exception to this rule, although it offers by itself alone a larger material for oriental archæology than all the other Phœnician countries put together.

§ I. TEMPLES.

Before the introduction of Egyptian and Assyrian influence into Syria, the Semitic and Canaanitish races of this country held the high places (*bâmoth*) in veneration. On the highest summit of the mountains, in spots which recalled ancient memories, on peaks that had been struck by lightning, stone altars were raised and victims were immolated upon them; the surrounding forest became a sacred grove. In the same way our Celtic ancestors erected their dolmens.

Soon, under Egyptian influence, the Phœnicians began to construct temples. The *maabed* (temple) of Amrith* is still an Egyptian temple on a small scale;

* Renan, *Mission de Phénicie* pl. 10

as in the latter, there is a *cella* or tabernacle of stone, within which the divine image was contained. It is composed of slabs erected on three sides. One side remained open, and was only closed by a curtain. The monolithic slab of the roof is adorned on its four edges with a light border with mouldings, and projects like eaves above the door; in the interior it is cut in a semicircular form, so that it presents the appearance of a shallow vault. The rock which forms the base




Fig. 188.—Shrii e at Ain el-Hayât (Renan, *Mission de Phénicie*).

has been isolated from the mountain by sapping, and thus the chapel, including this natural pedestal, reaches 22 feet in height. At the edge of the surrounding court were certain structures, doubtless a colonnade bordering the sacred enclosure; but this has disappeared.

The *maabed* of Amrith is the most important remaining representative of the temples of Phœnicia. At Ain el-Hayât, however, two shrines have been discovered similar to that of Amrith; one (fig. 188) tolerably well preserved, consists of a monolithic *cella*, resting on a substructure of large blocks; the whole is $17\frac{1}{2}$ ft. high. Above the door a row of Egyptian uræi is seen; the ceiling within is perceptibly cut into the form of a vault on which two pairs of wings, surrounding the Egyptian solar disk, are sculptured in relief.

The famous temples of Melkarth at Tyre, and of Astarte at Sidon and at Gebal (Byblos), which excited the admiration of ancient travellers, are no longer known except in memory. The *maabed* of Amrith alone

gives us some idea of their architectural arrangement ; they consisted of courts, in the centre of which rose the shrine of the deity built upon a platform. The Phœnician and Canaanitish temple showed therefore a strong resemblance to the temple of Jerusalem and also to the great mosque of Mecca,—the only monument which perpetuates this architectural type among us.

Nothing but a few fragments is now left of the temples built by the Phœnicians in Cyprus. The great prosperity of this island under the Romans and in the middle ages is the direct cause of the destruction of the monuments of an earlier age. The superb cathedrals of Famagusta and Nicosia, the fine churches built under the Lusignan dynasty, the formidable ramparts constructed by the Venetians, rose at the expense of ancient buildings, the materials of which



Fig. 189.—Coin of Paphos.

were turned to profit as stone-quarries. The celebrated sanctuary of Astarte at Paphos, for instance, is only known to us by the conventional representation of it upon coins belonging to the Roman period. We are able to distinguish in this figure a court surrounded by a balustrade, and beyond the court a structure which reminds us of the pylons of Egyptian temples : it is a gigantic gate between two towers, provided with a large aperture through which we perceive the sacred stone, flanked by two candelabra ; above hover the star and crescent. The roof, on which doves are resting, was supported by columns forming a portico.

Tacitus, who relates the visit of Titus to the temple of Paphos, says that the goddess was represented in it under "the form of a circular block, rising in the form of a cone, gradually diminishing from the base to the summit." This description corresponds with the stone which the medals show us. According to the excavations carried on by P. di Cesnola on the site of the temple, the building was almost 220 ft. long by 164 ft. broad; the peribolus measured 688 ft. by 540 ft.; the principal gate, perhaps that which figures on the coin, had an aperture more than 16 ft. broad.

The temple of Golgoi (Athieno), the ruins of which were disinterred by Cesnola, was a rectangular building constructed of bricks dried in the sun; the substructure alone was of stone. On the north and on the east were doors with wooden frames. Within, wooden pillars, surmounted by stone capitals, supported the roof, formed of pieces of wood placed close together, on which mats and reeds were arranged with a thick layer of beaten earth. The exterior of the temple, coated with white rough-cast, must have been of a most modest appearance. The interior, on the contrary, was laden with the richest ornaments. In the middle of the enclosure a tall cone of grey stone was found, a yard high, which must have been the sacred stone of the goddess, and reminds us of the image at Paphos described by Tacitus. Round the mystic cone, a whole population of stone statues painted in brilliant colours, set in a line along the walls or ranged in files in the centre of the building, formed, as at Tello, the dumb train of worshippers of the goddess. Votive offerings were hung on the walls above a row of bas-reliefs,

analogous to those of the Assyrian palaces. Stone lamps in the form of shrines, fastened to the walls, lighted up this curious scene.

In the temple of Curium, Cesnola ascertained the existence of a crypt to which a staircase gave access; it was composed of four subterranean chambers cut in the form of apses in the rock and communicating with one another by doors and a passage. These chambers are about $22\frac{1}{2}$ ft. long on each side, and 13 ft. high; it was here that the famous treasure of Curium was found, consisting of the plate of the temple, and of votive offerings made to the deity.

The recent excavations which we have shortly described, though they have scarcely brought more than substructures to light, yet enable us to describe the Cypriote temples with some exactness. While those of Phœnicia are built on heights, reminding us of the primitive high-places, the sanctuaries of Cyprus are generally in the plain, in the midst of fertile fields, like the temples of Egypt. The shrine of the deity was under the open sky like the Greek temples; around, and at a greater or less distance, rose a gallery covered with a roof supported within by colonnades forming a portico, and without resting upon the wall of enclosure.

A Phœnician inscription of the fourth century before Christ relates the erection of several temples to various deities, notably to the god Sadambaal and to the goddess Astarte in the island of Gaulos (Gozo). The remains of these sanctuaries are still in existence: they are called the *Giganteja*, or "Giant's dwelling," and consist of two neighbouring enclosures not communicating

with one another. Constructed of irregular masonry, formed of enormous blocks, they are parallel, and their gates open on the same façade; though one is larger than the other they both follow the same interior arrangement. Each is composed of two oval or elliptical chambers next to one another, and communicating by a narrow passage; the farther chamber contains also a semicircular apse. The great temple is 119 feet long from the entrance to the




Fig. 190.—Plan of the Giganteja. (*Novv. Annales de l'Institut arch. de Rome*, 1832, pl. ii.)

bottom of the apse; its greatest breadth is 75 feet. The area is uncovered; in one of these enclosures a conical stone has been discovered analogous to those

in the temples of Phœnicia and Cyprus.

At Malta, ruins of temples have been discovered constructed on the same principles as the Giganteja of Gozo. The *Hagiar Kim*, "stones of adoration," near the village of Casat Crendi, presents identical architectural features, with the enormous blocks of its irregular masonry. The plan, however, is a little more complicated: it is a series of seven ellipsoid chambers built next to one another.

Not a single stone is left above ground of the temples raised by the Phœnicians in Sicily, Sardinia, Spain,

and even Carthage. The famous sanctuary of Astarte, which stood on the scarped peak which overlooks Eryx, in Sicily, has perished; so has the temple of Baal-Hammon at Marsala (Lilybæum) and the Sardo-Phœnician sanctuaries of Baal-Samaim, Astarte, Eshmun, and Baal-Hammon indicated by the Punic inscriptions discovered at Sulci. The temple of Melkarth, at Gades, so much resorted to in the time of Strabo has left no traces. It is in vain that the name of the powerful city of Carthage and of the illustrious men whom she brought forth excite our enthusiastic curiosity; to no purpose has the site upon which she was built become French soil: the Romans respected nothing in the city of their most formidable enemies. The destruction which followed Scipio's conquest, in the



Fig. 191.—Roman wall at Byrsa
(Boulé, *Fouilles à Carthage*).

year 146 before our era, was systematic, and extended to the very foundation of the walls. What did escape was altered and transformed for the profit of the Roman colony which rose upon the Punic ruins, and which was itself upon two occasions the object of a savage demolition. There is, therefore, nothing Phœnician to be expected from the archæological excavations at Carthage from the architectural point of view; except mutilated inscriptions, almost all that is discovered is Roman, Christian, or Byzantine. The

Chapel of Saint Louis, near which Boulé undertook his excavations, stands on the site of the famous temple of Eshmun in the middle of the acropolis of Byrsa; on the neighbouring hill was the temple of Tanit, whom the Romans called *Virgo cælestis*; between Byrsa and the harbour, beside the forum, in the neighbourhood of which I carried on some excavations with M. S. Reinach in 1884, rose the temple of Baal-Hammon. To these topographical indications the memorials of the sanctuaries of Hannibal's city are limited.

§ II. CIVIL ARCHITECTURE.

If hardly anything is left of the Phœnician temples on all the shores of the Mediterranean, it must be admitted that the state of the case is almost the same with regard to civil monuments. The position of the formidable ramparts of Tyre, which held conquerors of cities like Sargon, Nebuchadnezzar, and Alexander so long in check, can with difficulty be recognised at a single point: it is probably marked by a submarine wall of enormous blocks, bonded with a concrete in which lime is mixed with crushed bricks; these walls, according to Arrian, were 147 ft. high.

The enclosure of Banias (Balaneum), between Tortosa and Latakieh, is still partly standing; but is it of Phœnician or of Pelasgic origin? It extends to a length of about 1,970 ft.; the wall, pierced by three gates, from 26 ft. to 32½ ft. broad, is built of blocks of grey limestone of irregular form, which are neither trimmed nor cemented. It is from 16 ft. to 26 ft. thick, and, in places, is still as much as 32½ ft. high. Broken

lines, recesses and projections seem to announce the approaching appearance of bastions and towers in the art of fortification. The Pelasgic walls of Eubœa, Tiryns and Sipylus present analogous features.

What remains of the substructures of the walls of Aradus, Berytus, and Sidon, indicates the employment of large and fine blocks irregularly laid. In the Carthaginian ramparts of Eryx, in Sicily, the stones bear Phœnician letters which acted as position marks for the masons, but this fortified enclosure does not date from an earlier period than the fourth century, and the Punic architects must have imitated their neighbours the Greeks. The walls of Carthage, which roused the astonishment of the ancients, were from six to seven leagues in circumference; they consisted, at least at certain points, of three concentric walls, arranged in steps in consequence of the declivity of the ground. Nothing is left of them except a sort of talus at intervals, which serves as the boundary of cultivated fields. Constructed of hewn stone, they were, according to the statements of ancient writers, 77 ft. high and 34 ft. thick; the towers were still higher and stronger.

Since temples and ramparts have always been constructed in the most solid form, and that most capable of resisting the attacks of time and of men, if very little of these is left there is a much stronger reason why hardly anything should remain of civil monuments and private houses. In the soft limestone of the Phœnician coast the primitive inhabitants hewed out their dwellings like Troglodytes. In later times, by the aid of civilisation, the tombs alone were opened in the sides of the mountains, and the living cut out

enormous blocks of stone with their picks, in which they hewed doors and chambers. At Amrith there is a monolithic house cut in this fashion, which M. Renan considers as the type of the genus. It is 98 ft. square and 71 ft. high; the walls are 2 ft. 7 in. thick; in the interior three chambers are divided by thin partitions contrived during the hollowing of the rock. Sometimes only the lower part of the walls have been hewn in the rock, which thus only forms a monolithic plinth one or several yards high, and completed to the roof by light masonry.



Fig. 192.—Terra-cotta house.
(Louvre.)

At Cyprus traces of structures which could be attributed to the period of Phœnician dominion are sought in vain. The only monuments which give some idea of the civil architecture of this famous island are models of houses in terra-cotta, found at Dali and preserved at the Louvre ($7\frac{3}{4}$ in. high). The most remarkable of these little buildings has a door guarded by a sphinx. At the two windows appear the heads of women; on each side of the door, columns with capitals in the form of lotus-flowers support a projecting roof. But of what architectural value can such a toy, modelled in so coarse a manner, be?

The poverty of monuments is even more absolute in the case of Carthage and the western basin of the Mediterranean. What travellers who visit the site or the old city admire above everything are the unheard-of efforts made by the ancients to catch the water

from the sky and store it in vast covered basins, or else to bring water from springs at great distances. Nowhere throughout the East, where there has always been the greatest anxiety to provide water—not at Jerusalem, where the Siloam aqueduct was tunnelled, nor at Tyre, where the aqueduct was dug which brought the waters of Ras el-Ain into the city—are such grand traces left of the works undertaken with this useful object. Only the gigantic viaduct which goes for several leagues to bring the waters of Mount Zaghouan to Carthage, does not date, as it is at the present day, from an earlier period than the reign of Hadrian; and the same must be said of those immense vaulted cisterns, near Byrsa, in which a whole Arab village lodges at the present day, and in which tourists take drives: it has never been possible to say exactly how much is anterior to the period at which the Roman colony was founded. The Carthaginians, two hundred years before our era, certainly knew the vault and the dome, the natural and primordial elements of oriental architecture, as well as the Romans. The walls, vaults, and domes of the cisterns of Carthage are of a mediocre stone, furnished by the quarries of Zaghouan: small irregular blocks are buried in a very thick mortar of lime, so excellent that it unites with the stone and gives to the whole structure the homogeneous character of one single immense block. The Byzantine ruins which cover the plain of Carthage are built with equally bad materials and an equally good cement.

We must now enquire whether any trace remains of the constructions which the Phœnicians must have

undertaken in order to establish or maintain those ports on the Mediterranean coasts in which their vessels found a sure refuge. These works must have shown the most characteristic side of the art of building among this nation of merchants. However, they have perished almost entirely like the rest, or else they are still buried under the sand. Tyre and Sidon had two harbours, of which only the site is now to be




Fig. 193.—Plan of the harbours at Carthage (after Daux, *Emporia phœniciens*).

distinguished. The two harbours at Carthage, the commercial harbour and the cothon or military harbour, are still there, but three-quarters of them are covered with sand, and they no longer contain more than a pool of shallow water. Lengthy and costly excavations, of which those undertaken at Utica may give some idea, could alone tell us what they formerly were. At present we can only confirm the exactness of Appian's description when he says: "The harbours of Carthage were constructed in such a way that ships passed from one into the other; on the side of the sea they had only one entrance, 70 ft. broad, which was closed by iron chains. The first harbour, intended for merchant vessels, was furnished with numerous and various mooring-cables. In the middle of the second there was an island; round this island, as on all the edges of the basin, were large quays. The quays pre-

sented a series of docks which could contain a hundred and twenty vessels. Above the docks, storehouses had been constructed for the rigging. Before each dock rose two columns of the Ionic order, which gave to the circuit of the harbour and the island the appearance of a portico. In the island a pavilion had been built for the admiral, from which trumpet-signals sounded, and orders were transmitted by the herald, and in which the admiral kept his look-out. The island was situated near the mouth; its surface had a perceptible elevation above the plane of the water, so that the admiral might see all that passed on the sea without those who were coming from the open being able to distinguish what was being done within the harbour. Even the merchants who found shelter in the first basin could not see the arsenals in the second; a double wall separated them from it, and a special entrance gave them admission into the town without having to pass through the military harbour." Go at the present day to Carthage, and you will observe with astonishment the modest extent of these two reservoirs, which formed the harbour of the great African city. They are parallel to the sea, from which a narrow strip of land separates them; the admiral's island is still in the centre of the cothon, which is circular in form, and communicates by a narrow canal with the merchant harbour; the latter forms a large rectangle, and opens into the Mediterranean by a mouth a few yards wide. The Carthaginian vessels were scarcely larger than our fishing-smacks. The jetty which sheltered them on their entrance into the harbour of Carthage has left a trace marked by large blocks,

which at certain points reach the level of the sea. The two harbours of Utica were not more spacious: one was only 328 ft. by 108 ft., the other 780 ft. by 327 ft.

Of all the Phœnician towns, that which has preserved the most remarkable remains of its ancient jetty is Thapsus (Dimas), on the eastern coast of Tunis. The mole which, though dilapidated, still rises 8 ft.




Fig. 194.—Jetty of Thapsus. (Restoration by Daux, *Emporia phéniciens.*)

above the waves, is 850 ft. long, and its breadth is 35 ft. The peculiarity of its construction is that it is pierced by a series of small passages, arranged in three rows: their object was to deaden the violence of the shock of the waves, by allowing them to pass through the openings. Here again it is uncertain whether we are looking at a work exclusively Phœnician, Roman, or Byzantine.

§ III. TOMBS.

The most important of the monuments discovered in Phœnicia are the tombs. Nearly all are hewn in the rock, and are, as in Judæa and Arabia, great caves in which the sarcophagi of an entire family were deposited. The necropolis of Marath (Amrith), explored by M. Renan, furnished specimens of tombs which seem to be the most ancient, the most spacious, and hewn with the greatest skill. The descent into them is by a shaft, as in Egypt, and notches are cut in the wall of the rock into which the hands and




Fig. 195.—Tomb at Amrith.
Plan (after Renan).




Fig. 196.—Tomb at Amrith.
Section (after Renan).

feet must be inserted ; but in the more recent tombs a flight of steps is substituted for the shaft. At the bottom a low door is found on two sides, leading into a larger or smaller number of rectangular chambers. These rooms communicate with one another by means of passages in which a few steps are generally found, so that the most distant chambers are at a lower level than the others. Sometimes there are even two stories of chambers ; in the partition of rock which forms the intermediate ceiling a shaft is pierced by which they are entered from above. The sarcophagi are ranged round the walls, or placed in niches or cavities for coffins, hollowed out on the sides : once filled, these

niches were closed by a large slab, on which an inscription might be written in honour of the dead. The necropolises of Tyre and Adlun present the same types of sepulchral caves.



Fig. 197.—Sepulchral chamber at Amrith (after Renan).

Now, may we ask, what was the outer aspect of a Phœnician necropolis in which the tombs were thus hidden under the ground? Often, especially when the tombs were those of rich men, a stela or cippus of small size appeared above them,

and marked the position of the cave and the opening of the shaft. Tombstones of this kind, either monoliths or constructed of masonry, are scattered over the plain of Amrith; they are called on the spot *meghazil* (in the singular, *mighzal*); one of them (fig. 198) is described by M. Renan as "a master-piece of proportion, elegance, and majesty": it is 32½ ft. high, and consists of a base from which four lions project, two cylindrical drums placed one above the other and decorated with denticulated sculpture, and, finally, a small hemispherical dome carved in the block.



Fig. 198.—Mighzal at Amrith (Restoration by M. Renan).

A sepulchral monument at Amrith, the Burj el-Bezzäk, is entirely distinguished from caves and




Fig. 199.—The Burj el-Bezzäk. Section (after Renan).




Fig. 200.—Chamber of the Burj el-Bezzäk (after Renan).

structures of the form which we have just described ; it rises above the ground, like an ordinary house, and is built, without mortar, of regular masonry, with blocks 16 ft. long. It terminated formerly in a pyramidal roof, and its full height was 52½ ft. In the interior, there are only two chambers one above the other, each communicating with the outside by a narrow aperture. Round the walls of these chambers there were numerous niches for coffins, separated one from another by partitions.



Fig. 201.—The Burjel-Bezzäk. Restoration. (Renan, *Mission de Phénicie.*)

The necropolis of Sidon, which is more considerable than that of Amrith, presents the same peculiarities : the caves are constructed in the same manner ; only at

the present day no *meghazil* are any longer to be seen




Fig. 202.—Section of a tomb at Salda
(after Renan).

near the orifice of the shaft. In the poorest caves the corpses were laid upon the ground or deposited in graves; in other sepulchres cavities for coffins are hewn out all round the chambers; in the richest, finally, the bodies were placed in sarcophagi buried in the floor of the chamber. The hypogæa of Gebal differ from the type observed at Sidon, Tyre, and Amrith, by the peculiarity that the descent into them is neither by a shaft nor by a staircase; the aperture is formed in the vertical side of the mountain, and is sometimes surmounted by a pediment and a few decorative mouldings (fig. 203).

Of all the sarcophagi found in the Phœnician necropoles, perhaps not one can be attributed to an



Fig. 203.—Entrance of a tomb at
Gebal (after Renan).

earlier date than the reign of Cyrus. The simplest are

large monolithic troughs, provided with a convex or triangular lid. Some of them are decorated with garlands, foliage, and chaplets; the corners of the lid are sometimes provided with acroteria. The only ones which have a real artistic interest are the sarcophagi in the form of human figures, or rather of mummy-cases, the head of the dead person, and sometimes the arms also, being carved in relief on the lid. These sepulchral urns were coloured in imitation of the wooden sarcophagi of the Egyptians, which they copy




Fig. 204.—The sarcophagus of Eshmunazar. (Louvre.)

in their form; while the carved work of the faces shows us that Assyrian influence was dominant in Phœnicia long after the disappearance of Nineveh. The sarcophagi of Tabnit and Eshmunazar, which only date from the year B.C. 350, disclose to us a remarkable peculiarity in the means adopted by the Phœnicians, merchants and navigators before all things, in order to furnish the tombs of their dead with stone coffins. These peculiar monuments, of black amphibolite, issue from the Egyptian quarries of Hammamat near Cosseir, and they originally contained Egyptian mummies.

Phœnician sailors stole them or bought them for money; the ashes which they contained were thrown to the four winds, the hieroglyphic inscriptions and the Egyptian scenes, carved or painted upon the plaster which covered the stone, were entirely or partly removed and replaced by the epitaphs of Tabnit and Eshmunazar. A considerable number of Phœnician sarcophagi are thus borrowed coffins, and by no means the work of indigenous artists.

Sarcophagi in the form of the human figure have been discovered in nearly all the countries in which the Phœnicians established their factories, in Cyprus, Sicily, and Malta, and they everywhere present the same charac-




Fig. 205.—Sarcophagus in human form.
(Louvre.)

teristics: only the head of the dead man is in relief. At Saïda, a sarcophagus was found in which the arms are carved beside the body; the sleeve of the garment ends above the elbow, and the left hand holds an alabastron. In the museum at Palermo a sarcophagus is preserved which came from Solus, the lid of which has the form of a true reclining statue like a mediæval tomb: it is a woman clothed in a long peplos over a short tunic, the sleeves of which end at the shoulder; the left hand also holds a vase for perfume.* Besides

* See Perrot and Chipiez, *History of Art in Phœnicia and its Dependencies*, vol. i., p. 193 [Eng. Ed.]

stone sarcophagi, leaden and terra-cotta troughs have been found in the necropoles of the Syrian coast, and also coffins of cedar-wood, decorated with metal ornaments, generally bronze lions' heads.

The sepulchral chambers of Phœnicia contain mortuary furniture not without interest. It consists of *alabastra* of glass, terra-cotta and alabaster, standing against the wall; and of idols in terra-cotta, representing Baal-Hammon sitting between two rams, the god Bes, of Egyptian origin, the god Pygmæus, Astarte sitting or standing with a dove in her hand, and, lastly, terra-cotta chariots holding one or two figures, with two or four horses harnessed to them. Besides these objects of Phœnician manufacture, amulets and statuettes, imported from Egypt, are found. The body of the deceased was enveloped in bands; the mouth and eyes were often covered with gold leaf, and rich men often placed a complete mask, formed of gold leaf, in which all the features of the face are marked: it is thus seen to what an extent Egyptian habits were implanted in Phœnicia. Lamps, amphoræ, amulets and ornaments are also found in the tombs of the Syrian coast. Women were buried with their necklaces, their rings, their bracelets, their ear-rings, their metal mirror, their pyxes for cosmetics and perfumes, and their toilet articles. Rings, provided with engraved stones which served as seals, are also found; nowhere, except in Cyprus, have weapons been discovered in the tombs of this nation of merchants.

In the Cypriote necropolis at Dali (Idalion) there are often at the side of the corpses pieces of pottery with geometrical decorations, bronze weapons, gold

ornaments, metal dishes with figures engraved on the inner side, statuettes of Astarte, of warriors, of chariots and of riders similar to those on the Phœnician coast.




Fig. 206.—Tomb at Amathus (after Cesnola, *Cyprus*).

Among the tombs at Amathus which are Phœnician and date from the fourth century, there are some constructed of fine regular masonry, with a door framed in a fillet, and a flat roof, or one with a double slope like those

of our houses. These tombs sometimes contain several chambers, along the walls of which the sarcophagi were set in a row, sometimes in the human form, sometimes with a triangular lid.

The Phœnician tombs found in Malta, in Sicily and in Sardinia, present the same arrangement as those on the coasts of Syria and Cyprus: the descent into the cave is by a sunken shaft or by a flight of steps, and the chambers resemble those that we have described. At Caralis and at Tharras pyramidal cippi have been found *in situ*, above ground, which marked the position of the



Fig. 207.—Sepulchral chamber at Amathus (after Cesnola, *Cyprus*).

burial-places, as we have already seen in Phœnicia: in these tombs the furniture is imported from Egypt, Etruria and Asia.

The necropolis of Mehdiâ, on the eastern coast of

Tunis, contains tombs, the descent into which is by shafts as at Aradus. The tombs of Thina (Thenæ) near Sfax, those of Carthage on the hill near the town called Jebel Kawi, have all been violated in antiquity or by the Arabs. Constructed on an uniform plan, they consist of a rectangular chamber, the descent into which is by a flight of steps. All round this room, the orifices of the coffin-niches are seen like the mouths of ovens. The staircase may have as many as ten steps; the chamber is $6\frac{1}{2}$ ft. high, from $19\frac{1}{2}$ ft. to 21 ft. long, and $9\frac{1}{2}$ ft. broad. The walls are coated with a white stucco which sometimes was adorned with figures in relief; the fragmentary subjects which I was able to detect seemed to me to be Greek and perhaps Roman in style.

To sum up, the Phœnician tomb represented only two types: the erect tomb above




Fig. 208.—Plan of a tomb at Carthage (Boulé, *Fouilles à Carthage*).

ground, and the subterranean tomb. The first was monolithic, or built like a house; the second was either on a level with its entrance in the side of the rock, or else it was reached from above by means of a shaft or a staircase. Both contained a greater or smaller number of chambers according to the number of corpses to be buried in it. These bodies were, save in rare exceptions, placed in sarcophagi sometimes deposited in cavities contrived in the wall of the chamber, sometimes in ditches hewn out in the floor, sometimes simply deposited along the walls. The mortuary furniture varied according to the wealth of the families; it included, together with

amulets and figures of deities, all the toilet articles and ornaments used by the deceased during his earthly existence.

§ IV. PHŒNICIAN SCULPTURE.

Phœnicia, it must not be forgotten, was by turns subjected to the yoke of the Egyptians and Assyrians, who introduced into it, with their garrisons, their art, their customs, their industries and all that characterised the peculiar genius of their civilisation. The conquerors were the masters of the Phœnician artists, and the few objects which came from the hands of the latter were inspired by Egypt or Assyria ; it is only from the time of Alexander that a third element, Greek art, begins to reveal its action in Syria.

The field of study offered by Phœnician sculpture is remarkably limited: it consists of the bas-reliefs of certain sarcophagi, of votive stelæ and of meagre fragments of stone statues. The sarcophagi in human form, of which we have already spoken, though not of an earlier date than the Hellenic epoch, show us very clearly the Egyptian and Assyrian influences at work in Syria. If the form of the troughs is Egyptian, if the finest of them have actually been imported from Egypt, the sculptures with which they are decorated are altogether Assyrian. The symmetrically undulating curls of the beard are like those of the Ninevite colossi; only it is to be observed that the artist can handle his chisel like a Greek. From the time of the Seleucids, the physiognomy of these heads which stand out in high relief on the lid of the sepulchral trough, grows more

and more Hellenic, and is modified in accordance with Greek models; so that if a chronological classification of all these monuments is undertaken, the most ancient would be those in which Egyptian and Assyrian influence is most marked; the most recent are those in which the Greek style finally prevailed.

In the rare fragments of buildings anterior to the Macedonian epoch, observed in Phœnicia, the elements of decorative sculpture are borrowed from Egypt and Assyria: nowhere has an original motive of indigenous inspiration been found. The gate of a structure described by M. Renan at Umm el-Awamid has a lintel on which two small figures of Egyptian appearance are sculptured in adoration before the winged disk supported by uræi.* The Phœnicians



Fig. 209.—Phœnician slab at Amrith (after Renan).

imported this solar globe, even more ancient in Egypt than in Assyria, into every coast. It is found in Cyprus, Malta, Sardinia and Carthage, where it is carved on the votive stelæ of Tanit and Baal-Hammon. The sphinx is also one of the principal elements of Phœnician sculptures: not only its form, but even its posture, is copied from the sphinxes of the Egyptian temples; it reclines on a pedestal; and has upon its head the pshent and the uræus; but it has more than the Pharaonic sphinx—

* Renan, *Mission de Phénicie*, p. 411.

namely, wings borrowed from the Assyrian and Persian genii. Other fragments of architecture show us the motives of their decoration,—rosettes, palmettes, guilloches and denticulated designs of Assyria.

Astarte, on the stela of the king of Gebal, Jehawmelek, has the costume, attitude, and attributes of the Egyptian Isis, while the king, standing before her, resembles the Ninevite monarchs in adoration before their favourite deities, or Darius and Xerxes on the bas-reliefs of Persepolis. A stela at Amrith represents a deity standing on a lion, an Assyrian subject already reproduced in Hittite bas-reliefs; a still greater similarity is seen in the lion's cub held by the figure as by the hero Izdubar, and the energetic modelling of his limbs bears witness that the artist was educated at the school of Nineveh. And yet the god's head-dress, and the winged disk placed above his head, are Egyptian in form.*

The study of sculpture in the round leads to the same conclusions. The Phœnician *pataci*, images of the god *Pumai* (a word from which *Pygmy* and *Pygmalion* are derived), were only copies of the Egyptian gods Bes or the embryo Ptah: this type of ugliness united to strength was carved in wood at the bows of the ships, in order to terrify the enemy. While statues found in Phœnicia are clothed with the Egyptian shenti, lions forming the doorposts at Umm el-Awamid are only half sculptured in the round: the head, fore-quarters and front paws are the only parts carved. Nothing could more directly recall the lions of the Assyrian palaces.

* Perrot and Chipiez, *History of Art in Phœnicia*, vol. ii., p. 12.

If the Chaldæans, as early as the time of Gudea, were accustomed to erect in their temples statues of kings, of pontiffs, or even of private individuals, whose image thus remained always present before the eyes of the deity, the Phœnicians took care not to renounce this habit. M. Renan relates that in an underground chamber near the maabed of Amrith a considerable number of fragments of white limestone statues was discovered; they were also found at Cyprus (fig. 210). These statues are iconic in character; they are portraits of the "masters of the sacrifices," as the Phœnician texts call the devotees who had themselves represented in the very act of accomplishing their vows, in order that the deity might not forget them. The archaic statues lately found on the Acropolis at Athens seem also to have, if not the same iconic character, at any rate the same symbolic meaning.

Carthage, which was a city of warriors as well as of merchants, had despoiled all the towns that she had conquered of their artistic wealth, in order to adorn her temples and palaces. This systematic



Fig. 210.—Cypriote statue (New York Museum).

depredation was so great a scandal in antiquity that when Scipio took possession of Rome's haughty rival, he invited the inhabitants of the Sicilian towns to come and point out their artistic property, and resume their ownership of it; all that was not reclaimed was carried away to Rome, and a nation of statues was seen passing along in procession behind the triumphal car. Besides these Græco-Roman works, the fruit of pillage, which adorned the public places of Carthage, there were those which were the work of the Greek artists whom Carthage was pleased to summon to her bosom; there were also those of Carthaginian craftsmen educated at the school of the Greeks: these last alone interest us here, and the scanty specimens which exist of them confirm us in the opinion that the Carthaginians were not more artistic than the Phœnicians.



Fig. 211.—Votive stela from Carthage. (*Corpus inscript. Semitic.*)

These monuments consist almost exclusively of votive stelæ anterior to the taking of Carthage by the Romans in B.C. 146. These boundary stones, from $11\frac{3}{4}$ in. to $19\frac{1}{2}$ in. long by about $5\frac{3}{4}$ in. broad, were intended to be fixed in the ground, and therefore the lower part is still in the rough; the upper part, trimmed on its four sides, is particularly well smoothed on one of its larger faces; on this side alone is found a votive inscription addressed to the goddess Tanit, the Punic Astarte, and to Baal-Hammon. Above the inscription various

symbols are represented in engraved lines, rarely in relief. The stela terminates in an imitation of a gabled roof, often provided with two acroteria. The decoration of these Punic stelæ is, however, still Greek, as is proved by the design of the acroteria, ovals, triglyphs, volutes, pediments, and even Ionic columns which figure in it. The symbols, carved in the most barbarous fashion by workmen who could not claim the title of artists, are borrowed from the Punic religion and from the fauna and flora of Africa. The commonest is the open hand, raised towards the sky and generally set at the point of the gable; the Arab still paints it in black on the white lime with which he plasters his house: it averts the evil eye. We find also the Egyptian uræus; the solar disk with the crescent, a symbol of Tanit; the ram, the symbol of Baal-Hammon; the caduceus, the horse, the elephant, the bull, the rabbit, fish, the palm, the rudder, the anchor, the hatchet, the lotus-flower, vases of various shapes, ships and fruit. We also meet with the Divine Mother holding her child in her arms; a young child standing or crouching with an apple in its hand; or a funeral banquet, as on Greek stelæ.



Fig. 212.—Stela from Lilybæum. (*Corpus inscript. Semit.*)

The great female deity of the Carthaginian Pantheon, Tanit, is found not only under the form of a human figure, but very often under that of a symbol difficult to

describe. It is a sort of triangular mannikin (fig. 212), the traditional and degenerate representation of a sacred stone; this triangle is furnished with protuberances in its upper part, and resembles to some extent a man clothed in a long robe, who straddles his legs and raises his outstretched arms to heaven: this



Fig. 213.—Stela of Hadrumetum. (*Gazette arch.*, 1884, pl. vii.)

sacred cone with arms corresponds well enough to the description by Tacitus of the Paphian Aphrodite. The supreme Trinity, consisting of Baal-Hammon, Tanit and Eshmun, is also frequently symbolised by three cippi of unequal height, placed side by side, and joined on a common base. This symbol is also represented on the stelæ at Hadrumetum and Lilybæum; the cippi are broader at the base than at the summit, and the middle one is surmounted by the solar disk and the reversed crescent. Sometimes a fire-altar served by a pontiff burns at the feet of this symbolical figure (fig. 212).

One of the most interesting Punic stelæ that can be cited was found at Hadrumetum (fig. 213). An image of two columns is seen upon it, supporting a complicated entablature. The base of the columns is very elegant, and resembles a large vase from which acanthus leaves emerge; from the middle of this tuft of leaves a fluted stem rises, the upper part of which is fashioned like a woman's bust. This woman is seen in full face, and holds her hands clasped upon her

breast, which is also adorned with the round disk and the crescent; she has a similar disk upon her head. In the entablature a row of lotus-flowers, a winged disk supported by two uræi, and a row of uræi seen in full face and with heads erect are distinguished; everything in this monument is oriental, or, rather, Egyptian. Even in Sardinia and the Balearic Islands the votive stelæ of Tanit and Baal-Hammon enable us to follow the track of the preponderating influence of Egyptian art in Carthaginian symbolism.

§ V. CYPRIOTE SCULPTURE.

If the very vestiges of Cypriote architecture have disappeared, it is not so with the works of the sculptor. The quarter of a century which has just passed has seen disinterred as if by enchantment from the bowels of the great eastern island, and then transported into the chief museums of Constantinople, Paris, London, Berlin, and especially New York, hundreds of stone statues and thousands of terra-cotta figurines of strange appearance, with picturesque head-dresses and with foolishly-smiling visages, which form a group apart in the history of art, since they are neither purely Asiatic nor purely Greek. Save in rare exceptions, the monuments of Cypriote sculpture were not imported from abroad; they are the work of that mixed race of Greeks and Asiatics, which, by means of the Phœnician ships, was in constant relation with Syria, Egypt, and Asia Minor.

The productions of Cypriote sculpture which seem to be the most ancient remind us of the figures

in the Assyrian bas-reliefs; the costume is the same: a conical cap, a curled beard, a long tunic, and a short cloak passed over the shoulder. However, there are essential differences: the muscles are far from being expressed with the same vigour; no figure wears that long beard like a regular screw, which is so characteristic of Ninevite sculpture. We feel that the



Fig. 214.—Colossal head from Athieno. (New York Museum.)

Cypriote artist works at a distance from a model which he only sees with the eye of memory, or else that he imitates at second-hand, and is compelled to interpret a Phœnician work which is itself only an interpretation of an Assyrian prototype. The most ancient statues discovered in the temple of Golgoi may date back from the epoch at which the Assyrian conqueror Sargon erected at Citium (Larnaca) the triumphant stela on which he relates that his vessels have vanquished Cyprus. They are of all sizes. There is a colossal head 2 ft. 9½ in. high (fig. 214). It

wears a conical helmet; the eyes are prominent, the nose is straight and regular, the mouth small but full-lipped, the cheek-bones projecting; the beard is composed of long parallel tresses slightly curled at the end. This fine head, more than half oriental, may be considered as the type of its kind.

After the overthrow of the Sargonid dynasty, Cyprus was given up to Egyptian influence, which reigned

there during the period which extends from the fall of Nineveh, at the end of the seventh century B.C., to the Achæmenid dynasty. But here again the imitation is only partial, and not as servile as in Phœnicia. We find Egyptian fashion modified in Cyprus by the taste of a foreign race. The figures are half-nude instead of being entirely draped; they have no garment except the shenti, tied round the waist and adorned with uræi; the bust is bare; the arms are bare, but adorned with bracelets and held close to the body; the head-dress is the Egyptian *pshent* scarcely modified; the hair, cut straight and falling in compact masses behind the beardless head, reminds us of the *Klaft*.*

During the same period, but especially under the Persian dominion, we witness the interpenetration of the two influences—that of Egypt and that of Assyria—in Cypriote art: it is the marriage of the two styles, the union of the two streams. In the statues at Athieno, for instance, the head is Assyrian in the features of the face, the curled beard and the head-dress formed of a peaked cap, but all the rest is Egyptian: the nude torso, the necklace, the shenti round the waist quaintly loaded with ornaments, the symbolical meaning of which the artist no longer understands. A striking example of this hybrid style is the famous colossus of Amathus, which is 13 ft. 11½ in. high and 6½ ft. broad across the shoulders. He is a Hercules who offers a mixture of the athletic proportions of the Assyrian Izdubar, with the type of ugliness symbolized in the god Bes. He has short

* See Perrot and Chipiez, *History of Art in Phœnicia, etc.*, vol. ii., p. 123

horns, a low forehead, large ears; his hair and beard are treated in the Assyrian manner; he has a lion's skin round his waist; in his two powerful hands, pressed against his breast, he holds the hind paws of a lioness.



Fig. 215.—The colossus of Amathus. (*Gazette arch.*, 1879, pl. xxi.)

Is he not the giant Izdubar, whom Assyrian artists so often took pleasure in representing? On the other hand, his tattooed arms, his hairy skin, his lion's skin fastened round his body, his bestial and Silenus-like face, his legs like the paws of a wild beast, are all copied from those figures of the god Bes, which the excavations in the Nile valley bring to light by hundreds. At the same time the artist handles his chisel as a Greek might. The limbs are plump and rounded: no more of those exaggerated muscles which characterise Assyrian art; nothing Eastern in the insignificant features of the

face. We have already, in certain points, the Hellenic Heracles, with whom the Cypriote god is soon to be confounded.

In fact, the third element which comes into Cypriote sculpture is the Greek element, with all its

methods, as the colonies on the coast of Asia Minor understood them as early as the sixth century. In the year B.C. 500 Cyprus made an alliance with the cities of Ionia; and Cimon's expedition in B.C. 450 determined the definite preponderance of Hellenic civilisation in that island. The statues in which Greek inspiration is recognised have something original which distinguished them at first sight (fig. 210). The physiognomy recalls that forced smile which has been called the *Æginetan smile*; the heads are freed from those conical head-dresses so dear to oriental art, which Greek art repudiated in order to replace them by a diadem or a high crown; the hair is no longer in ringlets and scarcely forms a row of flat curls to frame the forehead; the play of the drapery is quite different from that which comes from Nineveh, and reveals a good taste which is quite charming. In short, the Cypriote monuments, which correspond to this description, only form a branch of Greek archaic art, and we must no longer treat of them in a book devoted to the East. Let us only cite, as an example, the famous statue of the priest with the dove, which seems to date from the Græco-Persian period. It is a colossal statue 8 ft. high, representing a man holding in his hands a cup and a pigeon. His head-dress consists of a hemispherical cap which ter-



Fig. 216.—The priest with the dove. (New York Museum.)

minates in the head of an animal; three tresses of hair, a characteristic sign of Greek archaism, fall symmetrically from the back of his head on the front of each shoulder. The rows of curls in the beard which covers his mouth and chin are visibly imitated from the Assyrian fashion of dressing the hair. The fringes and draperies of the garment still remind us, indeed, as well as the square form of the shoulders and breast, of the statues of Tello; but how much more ample and harmoniously arranged they are!




Fig. 217.—Bas-relief of Heracles and Eurytion. (*Colonna-Ceccaldi, Monum. antiques de Cypre, pl. v.*)

here Greek taste still imprisoned in the hieratic formula bequeathed to it by the East.

To the same Græcizing art belong all those iconic statues from the temples of Golgoi and Amathus, which, instead of the

peaked cap or of the pschent, wear on their heads garlands of foliage or of narcissus, more or less high and more or less rich, but infinite in their variety. Like the statues found in Phœnicia to which we alluded above, they are portraits of priests, priestesses, or other personages who offer to the god for perpetuity the object which they hold in their hand: a flower, a fruit, a branch, a patera, a pyx, an alabastron, a bull's head or a pigeon.

Few bas-reliefs have been noticed in Cyprus. However, a colossal statue of Heracles in the Græcizing

style, found at Golgoi, had a pedestal decorated with a most remarkable bas-relief, reminding us of those in the Ninevite palaces. The ground is painted red to make the figures stand out; the relief is low and flat, the anatomical details of the figures are carefully studied and exaggerated in the Assyrian manner. The scene represents Heracles driving away the herds of Geryon, a subject which seems to be of Tyrian origin. Heracles, nude, with the lion's skin on his back, was probably holding his bow, which has disappeared as well as his head; like the giant Izdubar, he is of colossal stature;



Fig. 218.—Sarcophagus from Amathus. (New York Museum.)

before him is the dog Orthros, with three heads, already pierced by an arrow shot at him by Heracles; Eurytion flees with his herds; his beard and hair are treated in the Assyrian manner. He carries a whole tree, with which he was no doubt lashing his oxen; this tree is treated like those that figure on the walls of Nineveh.

Certain Cypriote sarcophagi are also decorated with Greek subjects, treated in the oriental manner: the birth of Chrysaor, who issues from the neck of Medusa, for instance, is seen; banqueting scenes and bull or boar hunts are found. A picture represented on the principal side of a sarcophagus from Amathus (fig. 218)

is copied in servile fashion from the sculptures of Assyria and Egypt; there are rows of pearls, lotus-flowers and daisies; a climbing plant is even to be remarked here like the sacred tree on the Ninevite bas-reliefs. One of the figures holds the Asiatic umbrella, and the tassels of the horses are Assyrian. However, the figures of the cortège are Greek in style, attitude and costume. On the smaller sides are two oriental subjects: at one end four figures of Astarte in full face, of the type reproduced in profusion in Chaldæa and Phœnicia; at the other four figures of the god Pygmæus, who is made up, as we have seen, of Bes and Izdubar together.

In two words, Cypriote sculpture, fruitful as it is, lacks variety, like Egyptian sculpture and Assyrian sculpture, its two mistresses. It lives only by borrowing, and has invented nothing. What characterises the stone statues which it produced is immobility and hieratic stiffness, together with finish in the details and decoration. They have no features which proceed from a realistic study of nature. It has been remarked that these statues, intended to be set in rows along the inner walls of the temples, are scarcely at all modelled behind, and are flattened as if they had been carved out of slabs of insufficient thickness; moreover, though broad in the chest, they are narrow in the hips and feet; the legs are pressed closely together, so that they have to some degree the appearance of reversed cones. Cypriote art has no originality except in the Hellenic element, which it assimilates; the Cypriote artist is a Greek who has served his apprenticeship among the Orientals.

§ VI. PHŒNICIAN AND CYPRIOTE CERAMICS.

The triple influence that we have remarked in Phœnician and Cypriote sculpture is observed no less clearly in pottery. In the seventh century Assyria carried on the artistic education of Phœnicia; then it was Egypt till the end of the sixth; finally Greece enters into the lists in her turn, bringing her peculiar genius which, especially in Cyprus, joins hands with its two elder brothers.

The Phœnicians, then, learnt first of all from the Assyrians and Egyptians how to model clay, and to fashion of it figures and vases of every form.

In the list of terracottas from Phœnicia which depend upon Ninevite art, and which were found at Amrith

(Marathus), chariots holding four warriors and drawn by two or four horses hold the first rank. The figures, generally bearded, and wearing the conical cap, present in their features the purest Semitic type, like certain Babylonian terra-cottas; the harness of the horses shows the minute detail of the Ninevite equipments. Besides these chariots, figurines have been obtained from the Phœnician necropoles, which represent Astarte, nude, standing upright, carrying her hand to her breast, or else sitting and clothed in a long robe



Fig. 219.—Phœnician chariot in terra-cotta. (Louvre.)

down to her feet without folds ; she often wears a high calathos of Asiatic origin, which has been observed on the head of captives in the Assyrian bas-reliefs.



Fig. 220.—Pygmy in terra-cotta. (Louvre.)

We know that ceramics was never highly developed in Assyria and Chaldæa; accordingly, as soon as Egyptian influence could show itself in the political sphere in Phœnicia, the pseudo-Egyptian style was not slow to replace the pseudo-Assyrian style in ceramics. The figurines of the new school, fashioned like the preceding ones in orange-red clay, represent women standing or sitting,

sometimes suckling a child, holding a fan, a pigeon, or the lunar disk. The Phœnicians even learned from the

Egyptians to coat their statuettes with green or blue enamel, analogous to that which is called Egyptian fatence, so that it is sometimes difficult to say whether the enamelled statuettes found in the tombs of Phœnicia are imported from Egypt or are works of native industry. In their course of servile imitation Phœnician craftsmen have reproduced even the hieroglyphic characters, which they distorted because they did not understand the sense of them.



Fig. 221.—Pygmy in terra-cotta. (Louvre.)

The type most frequently copied by the Phœnicians

is the grotesque god Bes or the embryo god Ptah, whom they turned into the god Pygmæus, called Patæcus by Herodotus. This large-headed and bandy-legged dwarf, of repulsive obesity, the type of deformity and ugliness, is met with everywhere in Phœnician pottery.



The pseudo-Hellenic or Græcizing style has furnished

Fig. 222.—Terra-cotta head from sarcophagus. (Louvre.)



Fig. 223.—Astarte. Phœnician terra-cotta. (Louvre.)

numerous terra-cotta monuments in Phœnicia, as is attested by the large head found in the necropolis of Amrith, which is nothing less than part of the lid of a sarcophagus in human form. The head is vulgar, and has neither an Egyptian nor an Assyrian appearance; it was inspired by Greek art, but to some extent followed oriental tradition. Among the Phœnician statuettes which may be referred to Greek archaic art there are figurines of Aphrodite standing upright, clothed in a long tunic, the folds of which the goddess grasps in one hand, while she holds a pigeon in the other. Tresses of hair fall over the breast on each side of the head. On other occasions the costume of these women is composed of a long robe and a mantle fastened by a brooch on the shoulder; they hold their arms close to the sides of the body.

The clay of Cyprus lends itself better than that of Phœnicia to moulding and to baking, therefore in very early times it could be utilised for this purpose ; and a considerable number of its productions take us back to a very primitive stage of art. The most ancient of the Cypriote figurines follow oriental and Asiatic traditions. They represent Astarte, the goddess of fecundity ; they are modelled with the thumb, with lines traced with a point, and bands of black or red for all their ornament. "The head is almost



Fig. 224.—
Terra-cotta
from Cyprus.
(Louvre.)

formless," says M. Perrot;* "a curved, beak-like nose, a pair of large round eyes, and monstrous ears may be distinguished, each of the latter pierced with two holes at the place of attachment of the heavy elaborate earrings worn by Phœnician and Babylonian women. The arms are bent round horizontally, so that the hands lie either on the chest or the stomach. . . . The extreme width of the hips seems to give a promise of maternity. The scratches on the clay may be meant to represent a loin-cloth. The legs are held tightly closed ; they taper rapidly downwards, and end in feet scarcely large enough to give stability." To the same period belong those vases in the form of animals or human heads, those strange statuettes of foot-soldiers, of riders covered with speckled armour, and of war-chariots, which one might suppose to be



Fig. 225.—Cypriote terra-cotta.
(Louvre.)

* Perrot and Chipiez, *History of Art in Phœnicia, etc.*, vol. ii., p. 148 f.

modelled by children. Cypriote figurines are so numerous, however, that they can be arranged in a scale so as to mark without gaps the gradual stages in the progress of the art.

In Cyprus the grotesque god Pygmæus, whom we noticed in Phœnicia, is often met with, and he offers the same characteristics here as on the coast. We have always the mixture of the pseudo-Egyptian and pseudo-Assyrian styles combined in different degrees with the archaic Greek style. We will cite, following M. Heuzey, some statuettes of women with their hair dressed in Egyptian fashion, and marked by



Fig. 227.—
Cypriote
terra-cotta.
(Louvre.)

the gesture of the divine mother, holding her hand to her breast, and by the gesture of the goddess of generation (fig. 227); this last, which reminds us of the Aphrodite of Cnidos, is not found in purely oriental art. Here we catch in the very act the fusion of Asiatic traditions with Hellenic ideas. Such was the skill of Cypriote artists in pottery that they manufactured terra-cotta statues of life-size; in this case they have all the characteristics that we noticed in statuary.

Phœnician vessels carried far away into the whole basin of the Mediterranean the products of Phœnician, Rhodian, and Cypriote pottery. At Corinth, for instance, a small aryballus in the form of a helmeted head, of pseudo-Egyptian style and of



Fig. 226.—Cypriote
terra-cotta.
(Louvre.)

Phœnician workmanship, was found. The helmet covers the whole head, except the eyes, nose, and mouth. There is an Egyptian cartouche containing the name of the king Uahabra (Apries), B.C. 599—569.



Fig. 228.—Mask from Carthage. (Louvre.)

On the site of Carthage, a large mask in terra-cotta coloured reddish-brown was disinterred, which recalls at once the mask of Amrith and the lids of the Egyptian sarcophagi in human form (fig. 228). The hair is dressed in Egyptian fashion, the ears pierced to receive rings, and the cheeks marked with a groove at the natural limit of the beard. The modelling alone is rather Assyrian, and shows signs of Asiatic softness. In the excavations near the harbours I obtained one of the most remarkable examples of Punic pottery that can be cited (fig. 229). The cheerful smile of this head of Astarte gives it a strong family likeness to the head of Tanit on Carthaginian coins, and even to the archaic heads of Athena on the most ancient tetradrachms of Athens.



Fig. 229.—Terra-cotta mask from Carthage. (*Cabinet des Médailles.*)

The terra-cottas found at Tharras and at Sulci in Sardinia, present the same types and the same hybrid character as those of all Phœnician countries. Even the Chaldæan goddess has been observed among them,

nude, in full face, holding her hands to her breast, and sometimes disguised in an Egyptian head-dress; figures of Pygmies, and of Astarte sitting on a throne, holding a pigeon or a lunar disk, have also been found.

Thus, from one end of the Mediterranean to the other, wherever the Phœnicians established their factories, they carried with them their hybrid art, in which the fusion of the elements is not sufficiently marked to prevent those that are borrowed from being recognised. The dissection and analysis of each of the products of Phœnician art, both in the terra-cottas and in sculpture, enable us to restore to Assyria, Egypt, and Greece what belongs to each of them; this work done, nothing is left which is the property of the Phœnicians except the execution.

§ VII. PHŒNICIAN GLASS.

According to Pliny's testimony the invention of glass has long been attributed to the Phœnicians. The following is a translation of his account: "In that part of Syria which is called Phœnicia, and which lies next to Judæa, a marsh named Cendevia exists at the foot of Mount Carmel. It is regarded as the source of the river Belus (Nahr-Halu), which, after a course of five miles, falls into the Mediterranean not far from the colony of Ptolemais. The waters of this river flow slowly; they are deep, muddy and unhealthy, but religious rites have made them sacred. The Belus only deposits sand at its mouth; and this sand, formerly unfit for any use, becomes white and pure as soon as the waves of the sea have rolled and washed it. The bank measures

at the most five hundred paces, and yet for many centuries this small space has sufficed for the manufacture of glass. It is related that nitre-merchants, alighting on this shore, were about to prepare their meal, when they perceived that there were no stones to support the pots. They ran in all directions without finding any, and then in despair they took the blocks of nitre with which the vessels were laden and made an impromptu furnace. But scarcely was the fire lighted, when the salt melting mixed with the sand, and streams of a transparent liquid, unknown till then, were seen to flow. Such was the origin of glass."*

It is easy enough to recognise the kernel of historical truth contained in the fable echoed by Pliny. The Phœnician merchants having lighted their fire by chance in the cavity of a rock which concentrated the heat, obtained a commencement of vitrification of nitric salt: in this no doubt the invention of the Phœnicians consisted. They had discovered white transparent glass, while before them the Egyptians and the Assyrians only knew an opaque glass produced by the combustion of certain plants.

Opaque glass, or rather glass paste, seems to be of Egyptian origin. The vitreous substance serves as a varnish to terra-cotta from the time of the first dynasty, and it is found thus employed on the posts of the sepulchral door of the step-pyramid at Sakkara. In later times it is applied as a glaze to scarabæi, sepulchral figurines, and paintings. Soon it was perceived that this material had consistency enough to be used by itself: "From that time," says M. Frœhner, "the

* Pliny, *Hist. Nat.*, xxxvi. 67.

manufacture of what we call glass-ware, that is to say, of small ornaments, beads, armlets, and figurines of opaque glass, isochrome, or of several colours, was invented; it did not stop here, and commerce spread its products everywhere."* The invention of glass-blowing soon followed: the oldest coloured glass vase known bears the name of Thothmes III. (Eighteenth Dynasty). White glass appears in Egypt much later; bottles of transparent glass, preserved at the British Museum, are of the Twenty-sixth Dynasty.

In Chaldæa and Assyria, the progress must have been the same as in Egypt; the vitreous substance was employed at first as varnish on bricks, statuettes and vases; then opaque glass and finally transparent glass were arrived at gradually, perhaps under the influence of Egypt. Assyrian objects of vitreous paste, such as rings, necklace-beads, small vases, are not rare in our museums; but transparent white glass seems to have been imported from Phœnicia, and never used to more than a limited extent in Mesopotamia. The celebrated transparent glass vase of Sargon (B.C. 722—705) at the British Museum is well known: in spite of its cuneiform inscription, it is Phœnician in style and matter, so that we are obliged to suppose that it was executed in the workshops of Sidon at the time when Sargon was master of the country. "This



Fig. 230.—Transparent glass vase bearing name of Sargon. (British Museum.)

* W. Frœhner, *La Verrerie Antique*, Coll. Charvet, p. 10.

vase," says M. Frœhner, "is the prototype of the unguent-flasks of which we have so many specimens in alabaster (*alabastra*) of Egyptian and Phœnician manufacture. Very heavy in form, and consequently of a very archaic style, it resembles a purse; its walls are thick, and two square appendages form the handles. The technical process followed in its manufacture is no less primitive, for it was not blown; the workman took a piece of cooled glass; then with a lathe he rounded the body and hollowed out the interior, exactly as if he were working in alabaster. To put it in its true place, we must remember that the Phœnicians were the first to produce white glass of this purity of tone."

But before chance taught them to utilise the fine sand on the banks of the Belus and to manufacture from it that fine transparent glass so much vaunted by ancient authors, the Phœnicians had borrowed from their neighbours the Egyptians and Assyrians the art of employing vitrifiable matter as enamel. At Rhodes, Salzmann discovered enamelled vases of Phœnician origin; the geographer Scylax informs us, on the other hand, that Phœnician merchants exported objects of vitreous paste, that is to say, amulets and necklace beads, even beyond the pillars of Hercules. The necropoles of Cyprus have furnished some glasses with thick walls, slightly transparent, which were certainly manufactured in the workshops of Tyre or Sidon. M. G. Rey brought from Phœnicia to the Louvre an idol of vitreous paste in the form of a cone placed between two quadrupeds; but the most interesting Phœnician monument in vitreous paste that we can cite is the necklace from Tharras in Sardinia. It is

formed of forty beads, two cylinders, four bulls' heads, and a large grotesque mask of Pygmæus (Louvre).

From the foregoing facts, it results that though the Phœnicians had for many ages a monopoly of the glass-manufacture, they cannot be considered as its inventors.

They only made admirable use of the material placed by nature in their hands. The wonderful properties of the sand of the Belus are vaunted not only by Pliny but by Josephus and Tacitus. The glass manufactured by the Phœnicians was purer and clearer than that of Egypt, and consequently more sought after; not only alabastra and amphoriskoi, worthy of mediæval Venetian artists, issued from their workshops, but also false gems of coloured vitreous paste, imitating precious stones so as to be mistaken for them; hence the prosperity and reputation of



Fig. 231.—Phœnician glass. (Louvre.)

the manufactures of Tyre and Sidon. Lucian says of the complexion of a beautiful young girl that it is more diaphanous than the glass of Sidon.*

This last city was the centre of the Phœnician glass manufacture from the remotest antiquity to the Roman period; but remains of ancient furnaces, glass fragments of various colours, and scoriæ, have been found at Tyre, which attest the existence there also of important glass-works.

* *Amores*, ch. xxvi.

A fine glass flask, moulded and decorated with fruit, found at Jerusalem, has been attributed to the age of the independence of Judæa; but it may well be not earlier than the Græco-Roman period, like the ornaments of vitreous paste found in the tombs of the kings by Saulcy. These objects, as well as flakes of greenish glass, found in Palestine, probably came from the workshops of Hebron or Aleppo, which are in activity to the present day, and produce before our eyes vases which imitate the ancient specimens to perfection.



Fig. 232.—Glass vase
from Jerusalem.
(Louvre.)

The glass-workers of Tyre and Sidon signed their works at the Græco-Roman period, like their colleagues the potters. Those of Sidon added the name of the workshop to their own; the Greek or Latin stamp placed in relief on the thumb-rest or handles had the double advantage of giving the name of the manufacturer and of presenting a rough surface, which made it easier to hold the vase. The best known of the Sidonian glass-workers, Artas, lived in the first century of our era; the productions of his workshops are found with his mark in all the countries bordering upon the Mediterranean.

§ VIII. BRONZES AND ORNAMENTS.

One of the most original sides of Phœnician art consists of the manufacture of bronze, silver or gold dishes, on which various subjects in Assyro-Egyptian style are

chiselled, engraved, or even hammered in *repoussé*. The skill of the Tyrian and Sidonian artists in this branch of art was celebrated from the highest antiquity. Solomon appeals to them for the furniture of Jehovah's Temple; in Homer, Achilles offers as a prize for the races, in the games organised for the funeral of Patroclus, "a crater of chiselled silver, holding six measures, and without rival on earth for beauty: skilful Sidonian craftsmen made it;" elsewhere the poet speaks of a silver crater, the work of Hephaistos, which a king of Sidon gives to Menelaus. The Phœnician dishes found at Nimroud (fig. 92), in Cyprus, and at some points of the Mediterranean coasts, are specimens of those goldsmiths' works which astonished



Fig. 233.—Patera from Palestrina. (Kircher Museum, Rome.)

Homer's Greeks. They are pateræ without feet, shallow and hemispherical, such as those seen in the hands of the Assyrians in the bas-reliefs of Nineveh. The figures which decorate them are on the inner surface, and arranged in concentric zones. Engraved or hammered in *repoussé*, these subjects seem sometimes to represent, not trivial figures nor images of deities, but, on the contrary, genre pictures, and scenes like those in the Egyptian paintings. Thus the subject which decorates the silver-gilt patera (fig. 233) dis-

covered in 1876 at Palestrina, the ancient Præneste, in Latium, has been ingeniously explained by M. Clermont-Ganneau.* In the concentric zone bordered by a long serpent a small drama is developed in relief in a series of successive phases; it might be called "A Hunting Day, or Piety Rewarded. An oriental play in two acts and nine tableaux." We see: (1)



Fig. 234.—Dish from Dali. (Louvre.)

(2) the hero leaving his house in his war-chariot; (3) he alights to shoot a deer; (4) capture of the deer; (5) halt in a wood after the hunt; the horses are unharnessed; (6) preparations for the meal, in which the deer is to be eaten; (7) an ape attacks the hero, who, fortunately, is protected by a winged deity; (8) the ape is pursued and thrown down by the horses; (9) the hunter kills the savage beast; (9) triumphal entry into the house. The interpretation would be complete if a mythical name could be given to the hero of the drama.

Hunting scenes of the same kind, but not so easy to explain, decorate a silver dish from Cære in Etruria, of the same manufacture as the pateræ of Phœnicia, or Cyprus. On one of the silver dishes from Dali

* *L'imagerie phénicienne et la mythologie iconologique chez les Grecs*, part i., 1880.

(Idalion) possessed by the Louvre,‡ there is a lion hunt; on the patera from Amathus there is the siege of a fortress.

The treasury of Curium furnished Cesnola with a large number of these pateræ in silver or electrum, on which appeared engraved subjects of the same inspiration and the same style: figures with four wings, struggling with a lion; Astarte with her hand upon her breast, beside hideous patæci, Isis-Hathor, Egyptian sphinxes and sparrow-hawks; hunts, battles, religious sacrifices. Everywhere on these monuments, which, as the Homeric poems show us, were so greatly sought for by the Greeks of the heroic age, and imported by Sidonian merchants, we find copies of the usual designs on the Egyptian and Assyrian monuments, an unconscious mixture of hybrid scenes, which have nothing original except this quaint amalgam itself, even more striking here than in



Fig. 235.—Handle of a bronze crater. (New York Museum.)

the other manifestations of Phœnician and Cypriote art. If we had a larger number of these curious dishes, we should find, no doubt, that the motives are little varied, often repeated, even in subjects as interesting as the Hunting Day, and that the effort of imagination here made by the Phœnician artist has been little inventive. Fortunately for the reputation

of Phœnician and Cypriote goldsmiths, other monuments show that their metallurgy was not limited to these interesting pateræ. Thus, for instance, Cesnola brought from his excavations in Cyprus a fragment of



Fig. 236.—Phœnician gold ornament.

a large bronze crater, the handles of which are decorated in the most original fashion. We here find lions standing on their hind legs holding œnochoæ, and clothed in fishes' scales, like the god Anu in Assyro-Chaldæan symbolism.

In Cypriote furniture and ornaments we observe the same characteristics of a hybrid art. There are little silver vases chiselled in the Assyrian style with rare elegance, handles of sceptres, and other precious utensils like those of Nineveh. Certain

ornaments, intended for women's head-dresses, are of exquisite workmanship; so are the ear-rings, the necklaces of gold, gems and glass; with figures of lions, rams, deer, masks with curled beards in the Assyrian fashion, heads of Isis-Hathor and lotus-flowers. Some of these necklaces and bracelets end in lions' or serpents' heads,

and form models which Greek artists needed only to copy, for they are masterpieces in their kind. We have seen that the Ninevite excavations brought to light ivory tablets carved by Phœnician artists, and imported into Mesopotamia by commerce: plaques of the same style have been obtained from Phœnicia itself: they were ornaments of precious caskets. These products of Phœnician industry were imported into all the coasts of the Mediterranean; and, at Palæstrina, in Latium, an ivory tablet was found, on which a vessel manned by rowers is engraved, similar to those in the Egyptian paintings. Ostrich-eggs, found




Fig. 237.—Phœnician ear-rings.

in Etruria, arranged to serve as vases, are adorned with engraved figures, the Phœnician character of which could scarcely be disputed: there are zones of warriors on foot, on horseback, and in their war-chariots; files of animals, fights of lions with bulls in semi-Egyptian style; the frame of these scenes is borrowed from Assyria; the whole is relieved by iridescent colours.*

If we had in Phœnicia bas-reliefs like those of Assyria, and paintings like those of Egypt, we should be able to give some account of those brilliant stuffs of dyed purple, described by classical antiquity with so much enthusiasm. It was to the Tyrian god, Mel-

* See Perrot and Chipiez, *History of Art in Phœnicia, etc.* vol. ii. p. 404 f.

karth, that tradition assigned the invention of this dye, obtained, as it is well known, from the juice of a marine shell, the *murex*, which is found especially on the coast of Phœnicia. We can only affirm, according to literary testimony, that the workshops of Tyre and Sidon produced stuffs in abundance, the colour of which, as the ancients remarked, instead of being altered and deteriorated by a bright light, was only rendered more vivid and brilliant by it.

§ IX. ENGRAVED GEMS.

The glyptic art, through the multiplicity of its productions, is one of the principal elements of Phœnician archæology, and teaches us more than the miserable fragments which remain of pottery or sculpture. Here, more clearly than in the other branches of art, we find imitation of Egypt and Assyria taken for granted, as a witness of the poverty of invention of the Phœnician intellect.



Fig. 238.—Cylinder in the De Clercq collection (after Menant).

Two cylinders exist in the De Clercq collection which bear a cuneiform inscription by the side of Egyptian figures. That which we give as an example (fig. 238), after M. Menant,* is the seal of "Annipi, son of Addume the Sidonian." Thus the owner of the cylinder is a Phœnician; he has inscribed his name in Assyrian beside the god Set,† Reseph, the

* Menant, *La Glyptique orientale*, t. ii.

† The figure representing the god Set has not a hawk's head, as M. Babelon states, following M. Menant. Here, as always, Set has the head of a nondescript animal, somewhat resembling an ass!

warrior god, and Horus with the hawk's head. The style of the inscription, like that of the figures, betrays, however, the unskilful hand of the Sidonian imitator.

We possess, on the other hand, cylinders on which the figures are purely Assyrian, while the inscription is in Phœnician or Aramaic characters. This one at the British Museum is the "seal of Akadban, son of Gebrod the eunuch, worshipper of Hadad" (fig. 239). The style of the figures and the details of the costume are so clearly Assyrian that this monument discloses to us the plagiaristic

method to which the idle imagination of the Phœnicians had recourse. These merchants found it simpler and speedier to appropriate Assyrian or Persian cylinders, satisfied with having



Fig. 239.—Cylinder at the British Museum (after Menant).

their names engraved upon them. They did not blush to wear during their life the ornaments of other nations, until their ashes should rest in sarcophagi stolen from the Egyptians.

However, in Cyprus, they tried to engrave cylinders for themselves. The recent excavations have disinterred a large quantity of them, and, by the side of cylinders brought from the continent by commerce, some have been found which were certainly manufactured in the island. But what astonishes us in these monuments is their extreme barbarism; the design is most summary, the figures are scarcely sketched, and

the chisel has only made rough scratches on the jasper, the hæmatite, or the chalcedony. And even the figures of men or animals, the trees and the geometrical ornaments with which the Cypriote cylinders are covered, are copied by unskilful workmen from the productions of the Assyro-Persian or Egyptian glyptic art.

After all, Phœnician cylinders are rare enough. Practical before everything, the merchants of Tyre and Carthage preferred flat seals of multiple form to cylinders, the use of which was difficult; they manufactured scarabæi, scarabœoids, ellipsoïds, cones, octagonal conoids, these last especially in the Aramæo-Persian period, and lastly bezels for rings. Among the numerous gems which have come down to us, and which must be attributed either to the Phœnicians themselves or to the Aramæan populations of Syria, some have still preserved their mounting: a ring in the form of a horse-shoe enabled the owner to turn the stone on its axis and to hang it from a necklace. The inscription of one or two lines, when it exists, gives the name of the owner, his father's name, and sometimes his quality. • The subjects, naturally more limited than those of the cylinders, are always of Egyptian, Persian, or Assyro-Chaldæan inspiration. There are, for instance, the winged and radiated disk, deer, lions, bulls, sphinxes, gryphons, the divine bust in a winged disk, a pontiff sacrificing at an altar, or in adoration before the pyreum. The Louvre possesses a scarabœoid of red agate acquired in Mesopotamia by M. de Sarzec; a god is seen upon it, holding a serpent in each hand, like the Egyptian Horus; he has four wings, and bears on his head the solar disk supported by two horns.

The name, Baalnathan, indicates that its owner was probably an Ammonite or a Moabite. It may be admitted, with M. de Vogüé,* that among the Phœnician, Aramæan and Jewish intagli, those in which Egyptian influence appears exclusive are the most ancient, that is to say, anterior to the Assyrian rule in Syria.



Fig. 240.—
Scarabæoid
seal.

From the seventh century B.C. the action of Assyria appears in the Aramæo-Phœnician glyptic art, sometimes allied to the Egyptian influence, sometimes exclusive as on a scarabæus in the museum at Vienna, bearing the name of Akhotmelek, wife of Josuah, on which a deity is seen sitting on a throne and receiving a libation from a standing pontiff (fig. 240). A fine scarabæus in green jasper at the British Museum (fig. 241), with the name, in Phœnician characters, of *Hodo, the scribe*, shows a principal scene inspired by an Assyrian cylinder, while on the field the Egyptian *crux ansata* figures, and the scarabæoidal form of the gem is certainly of Pharaonic origin.



Fig. 241.—Sca-
rabæoid seal
(after Menant).

In this hybrid coupling of Egyptian to Assyrian art the least trained observer can discern what belongs to each of the two constituent elements. The position of the outstretched wings, one raised, the other lowered, before and not behind the figures, the uræi, the pshent, the shenti, the hawk-headed gods, the lotus-flower, the sphinx, and the *crux ansata*, properly belong to Egypt. The long-fringed robe of

* *Revue archéol.* t. xxvii. 1868, p. 432 ff.

the priests, the curled hair and beard, the cylindrical tiara, the fire-altar, the sacred tree, and the lions are, besides other features, the property of Assyria and Chaldæa. The writing alone is Aramaic or Phœnician. At the Achæmenid epoch, seals are found in Phœnicia, the workmanship of which shows signs of Persian influence; sometimes even the legend, although Aramæan, gives us a Persian name.

From the fourth century B.C., lastly, the glyptic art, following the same laws as the other branches of art, is rapidly invaded by the Greek genius. Engraved stones with Cypriote or Phœnician legends show subjects incontestably interpreted by Greek artists, even when the incidents are oriental; at last we find Greek subjects, so that the oriental influence is only shown by the legend, which still remains Phœnician. We are then arrived at the age of Alexander, and the ancient civilisations of the East have ceased to live.

CHAPTER IX.

ARCHÆOLOGICAL DISCOVERIES AT SUSÁ.

§ I. M. DE MORGAN'S MISSION IN SUSIANA.

THE progress of oriental archæology leads us from one surprise to another. Year after year discoveries are made in rapid succession, which we watch with breathless interest as they transform and elucidate some chapter in the history of those primitive civilizations from which our own is in part derived. Following the discoveries made in Chaldæa, Assyria, and Phœnicia, another region of the East now takes its turn in throwing light on the past—the country of Elam, or Susiana, a region hitherto almost unknown to us, although in the earliest ages of the world it played an important part.

The ruins of Susa, situated at the north of Ahwaz, form a number of immense tells which cover an extent of four and a half to six square miles on both banks of the river Kerkha. The plain, which is dominated by these majestic mounds as far as the banks of the Karún, stretches far to the north, where it is bounded by the Bakhtiyari mountains. Southward it extends to the *Shatt al Arab* and Lower Chaldæa.

What new material may we draw from this ancient soil of Elam, to provide food for our chimæra-like appetite for universal knowledge ; a soil where countless generations

of human beings lie buried, piled on each other like so many geological stratifications, and surrounded by all the appurtenances of their earthly existence? The Greeks have merely transmitted to us baseless fables concerning the history of Elam. Ignoring all local traditions, the writers of the Macedonian period related that the mythical founder of this region was Memnon, son of Tithonus, and of Aurora; that he led a body of black warriors to the aid of Troy when besieged by the Greeks, and was slain in a duel by Achilles. Eos, or Aurora, wept for her son, and according to a pretty fiction it is the tears of this inconsolable mother which form the morning dew. Classical antiquity was cradled in such poetic stories of the mysterious regions of the rising sun, without any attempt to discover the actual facts. It is the Bible alone that has preserved the name of one of the kings of Susa, Chedorlaomer, a contemporary of Abraham.

In the present day, however, the power of deciphering the Chaldæan cuneiform texts has rendered us acquainted with isolated episodes of the political relations between the Elamites and the Babylonians and Ninevites.

In 1810 Macdonald Kinnear and Monteith accompanied General Malcolm on his mission to the Shah of Persia; in 1826 Sir Henry Rawlinson, and later again Sir A. H. Layard, visited the tells of Susa, and copied several inscriptions which had been laid bare by the heavy rains. As the monuments emerged from the rubbish, it became evident that only excavation could compel the mounds of Susa to yield the secrets they contained.

These excavations were commenced in 1851 by Sir Kenneth Loftus and Colonel Williams, who cleared the wells of the palace of Darius I., son of Hystaspes. The researches were then abandoned, and it was only in 1885 that the French Government commissioned M. Dieulafoy to carry on the work begun by Loftus. He laid bare the *Apadana* of Artaxerxes, and deposited in the Louvre Museum the magnificent Achæmenid fragments described in Chapter V. of this volume (p. 146 *et seq.*). But various remains and fragments of inscriptions of an age far more remote showed that merely the surface of the ruins had been touched, and that it would be necessary to undertake systematic excavations of greater depth. A diplomatic treaty signed May 12th, 1895, renewed and confirmed in Paris in 1900 by the Shah of Persia, accorded to France the exclusive right to carry out archæological excavations over the whole extent of the Persian Empire. M. Jacques de Morgan was appointed Delegate-General of Antiquities in Persia, with a special mission to carry on the researches at Susiana.

After encountering difficulties of every kind, M. de Morgan, accompanied by a number of colleagues, among whom we must mention one of the most eminent of contemporary Assyriologists, Père V. Scheil, arrived at the site of the ruins of Susa on the 16th of December, 1897, and commenced work there. The first results sent to Paris formed a special exhibition at the Grand Palais des Champs Elysées, in the spring of 1901, and occasioned great surprise and admiration. These remains consist of immense numbers of inscribed bricks, of bas-reliefs, of stelæ covered with

cuneiform writing of most archaic appearance, and of works of art of a style hitherto unknown. Thus, in beginning the publication of these monuments, and the translation of the texts, M. Scheil could write without exaggeration or hyperbole: "It is here that the history of the country of Elam begins"; and he then proceeds to deal with those great problems of history, of which the solution had become the question of the moment.

What were the earliest civilizations of the East, and to what period do they carry us back? To what ethnic groups do the Elamites belong? What connection is there between Elam, Anzan, and Susa, the three names given in the original texts to Susiana? Did there actually exist in that country a combination of institutions, political or religious, of a distinctive and independent character? What languages and what races of mankind met in that region which adjoins the land of the Semites, the Arians, and perhaps the Turanians?

These are questions of deep moment, and they have obtained from the early excavating campaigns a hesitating and partial reply, which does not satisfy our thirst for the whole truth regarding the origins of the earliest civilizations. "The proto-archaic texts," says M. Scheil regretfully, "will show how limited is our knowledge both of the origins, which are continually becoming more remote, and of the primary factors of civilization, the number of which is steadily increasing."

We can only give a general sketch of the archæological results obtained up to July 1905, the date of

the inauguration at the Louvre of the gallery devoted to the objects discovered up to that time. The work is still proceeding, and we may hope that it will be brought to a conclusion without interruption. Between January 1, 1897 and April 15, 1905 M. de Morgan has dug more than 280,000 cubic metres of earth and débris of all kinds, and he estimates further that it will be necessary to remove 1,280,000 cubic metres in order to bring the excavations to a final conclusion. Working at the rate of 35,000 cubic metres yearly, the archæological excavations at Susa will occupy not less than 35 years.*

§ II. CHRONOLOGY OF THE RUINS ACCORDING TO RECENT DISCOVERIES.

The researches we have just described, so far as they have been carried at present, show that many of the mounds of Susa, formed of an accumulation of débris and covered with a thin layer of sand deposited by the desert winds, were inhabited from prehistoric times to the Arab period. The prehistoric remains are found at a depth of over 80 feet, below the evidences of more advanced civilizations.

After digging through the accumulated remains of forty centuries, the virgin soil is reached, and here are found worked flints, primitive pottery, and other objects similar to those found on all prehistoric sites. Above

* In proportion to the amount of the discoveries, the results are published, and the monuments reproduced and commented on, in the vast publication entitled *Délégation en Perse, Mémoires publiés sous la direction de M. J. de Morgan, délégué-général* (quarto, Leroux, editeur, Paris). Eight volumes have already appeared, the ninth is in the press (November 1905).

the level of the worked flints, and the rough, hand-made pottery, shaped without the aid of the wheel, another civilization is found, more advanced, although still prehistoric, which produced vases in sandstone and calcite of various sizes, and—far more important and fundamental—seals or stamps, proofs of a culture widely removed from barbarism. These seals are hemispherical in form, and pierced with a hole for suspension. The base or flat face is decorated with figures of animals engraved in rudimentary fashion by means of the drill and point. The most usual subject is a lion, or lion's head. But nowhere at this level of the remains has the slightest trace of writing been found. The dwellings were huts, made either of beaten earth or of crude bricks.

A thick layer of cinders and other unequivocal indications, enable us to assert that this primitive civilization disappeared owing to the massacre of the inhabitants and the burning of their dwellings. At this early period, to which it is impossible to assign even an approximate date, Susa suffered from some foreign invasion, and the pillagers installed themselves in place of the indigenous inhabitants, whom they destroyed. It is, therefore, a new civilization we find above the remains of the prehistoric people, and which introduces us to the domain of actual history, the commencement of the Elam-Anzanite period.

It is to this invading race that Susa owes her first written documents. These inscriptions, although they are in a language almost unknown to us, are undoubtedly the most important that this period has hitherto yielded.

The earliest text known is engraved on a bone cylinder (fig. 242). The mere appearance of the signs strikes us with the remote antiquity to which they must be assigned; they are actually hieroglyphs. Among them apparently there can be distinguished an insect, a double comb, a quadruped, a bird, some grains of wheat, and a man carrying a double load on his shoulders. On the lower part of the cylinder two bulls are depicted, each with his head over a manger.

This object, which so far seems to be the sole




Fig. 242.—Bone cylinder, showing the earliest stage of cuneiform writing (Louvre).

representative of the earliest stage of cuneiform writing, and which leads us to question whether this mode of writing was not invented at Susa, is followed by a series of clay tablets ranging in size from $2\frac{1}{2}$ to 9 inches at the sides, and with the principal face covered with writing, of which the signs are almost cuneiform. Dr. Scheil, however, says of these that apparently "we have here a system of cuneiform writing other than that of primitive Chaldæan, or at least the result of an extremely independent evolution, very different to that which has given us the signs known as the Babylonian: evidently

these signs, instead of being extremely archaic are linear in character, and geometric rather than hieroglyphic."

Dr. Scheil recognises that these texts are arithmetical, and he has already been able to distinguish the elements of Elamite numeration (fig. 243). Any one studying them from the point of view of workmanship, will notice, as Dr. Scheil again observes, that the signs are inscribed with a neatness and certainty that indicate previous



Fig. 243.—Fragment of an Elamite tablet inscribed with arithmetical calculations (Louvre).

long practice on the part of the scribe. Nowhere can we discern errors or rough work, such as would be the results of early attempts and experiments. Thus we arrive at the conclusion that those texts were written by the invaders, who were already in possession of

this system of writing when they arrived at Susa.

It is at this period that we first find cylinders covered with representations of animals, engraved on the surface before the tablets were baked or dried in the sun. These cylinders are of greenish enamelled paste and very hard; only a small number has been discovered at present, but impressions made with some of the objects of this class agree for the greater part with the clay tablets. We give a reproduction of one of the most

curious of these impressions (fig. 244). Here we can distinguish giants, leonocephalic and taurocephalic, taming lions and bulls apparently for amusement. In this instance the style is very remarkable, and recalls that of certain animals on the finest of the Chaldæan cylinders.

Of this same civilization there is also a large number of alabaster vases; these are frequently decorated with incised lines, forming geometric designs; in some instances these vases have animal forms, such as ducks, pigs, fish, or seated monkeys, types generally figured in a summary and rudimentary fashion.

Above the proto-Elamite zone the ruins become confused and belong to different periods.




Fig. 244.—Cylinder showing giants, lions, and bulls, glazed pottery (Louvre).

It is obvious that the soil of Susa was constantly overturned and pillaged. Happily the beacon light of history now begins to guide our footsteps, and enables us to classify chronologically those remains, which are discovered in disorder. The written texts, which are increasingly numerous, from this time are divided into two main classes; the first written in a Semitic dialect, the second in the Anzanite language. This shows that in the country of Elam at that remote period an ethnic dualism existed, which corresponds with the double name for the capital of Anzan and Susa—a dualism

which certain sculptured representations of the human figure also exhibit from the anthropological and ethnological point of view. The Anzanite inscriptions are still only partly decipherable, notwithstanding the insight shown by Dr. Scheil in commencing a study of them.

As to the inscriptions in the Elamite language, over a thousand have been brought to the Louvre. They are on slabs of stone, on blocks which have served as sockets for doors, and yet more are inscribed with a stylus on bricks.

These have been deciphered by Dr. Scheil; they give the names of the kings by whose commands the buildings were erected, in which they were employed. With the help of these clues, and guided by some more explicit texts and by the information about Susa already afforded us in the inscriptions of Chaldæa and Assyria, it has been possible to establish the first landmarks of the history of that powerful Elamite empire, whose complete annals will shortly provide a new chapter of the history of the Ancient World.

After the mythical period, in which such kings as Humbaba and Kudur appear, whose names so far only occur in legendary poems and stories, the earliest historical texts introduce us to the princes of Elam as vassals of the Mesopotamian suzerains. Of these the first is called Ur-iti-Adad, vassal successively of the two kings of Agade, Sargani-sar-ali, and Naram-Sin, about B.C. 3750. One of his successors, Karibu-Sa-Susinak, *patesi* of Susa, *sakkanak* of Elam, boasts of having built the temple of the god Sugu "the ancient," and of having constructed the canal of Sidur; he is a

vassal of Dungi, king of Ur, and of Gudea, *patesi* of Sirpurla.

To the rule of the *patesis* at Elam succeeded that of the *Sukkal-mah*. This was occasioned by a change in the suzerainty, which from being Chaldæan now became Elamite.

About B.C. 2280 the king of Susa, Kudur-Nakhunta, effected the conquest of Mesopotamia and decorated his capital with the spoils of the towns of Chaldæa; notable among these was the statue of the goddess Nana, which he caused to be transported from Uruk (Erech) to Susa.

Long after, Hammurabi, king of Babylon, delivered Chaldæa from the domination of Elam, and one of his successors, Kuri-galsu, even succeeded in entering Susa as a conqueror. But later again the Susians gained their revenge; they took Babylon by assault, and carried away the statue of Bel.

A king of Susa, Shutruk-Nakhunta, boasts of having devastated Chaldæa, and of having seized the stelæ of Melishikhu; he records that he took some hundreds of towns, brought back several kings as captives, and built a large number of temples at Susa. His grandson, Shilkhak-in-Shushinak, restored these buildings, where the stelæ, the *kudurru*, and the statues of Chaldæan divinities were placed, with all the precious objects taken from the towns of the Tigris valley.

The names of about twenty other Susian kings are known; they belong to two or three different dynasties, and we can trace the existence of conflicting races in Susa itself. This fact is further shown by the

variety of languages which are found written in cuneiform character.

By turns conquerors and conquered, the Susians passed from the rôle of oppressors to that of oppressed ; raid succeeded to raid, with results as contradictory as the gusts of wind in a gale. The kings of Nineveh, who during the twelfth century B.C. became the most powerful rulers of this part of the world, were the dominating power in Chaldæa and constituted themselves protectors of the country against the incursions of the Susians. Under Sargon, king of Assyria (B.C. 722-705) and his successors there began a mighty struggle, which ended with the ruin of Susa by Assurbanipal in B.C. 647. We must here recall that strange and tragic episode of the annals of the Assyrian monarchy.

The king of Nineveh, relating his conquests in the land of Elam, records that sixteen centuries earlier Kudur-Nakhunta, king of Susa, had invaded Mesopotamia, and carried away the statues of the Chaldæan gods, more especially the image of the great goddess Nana, which thus remained prisoner until he, Assurbanipal, went to her rescue : "The King of Elam, Kudur-Nakhunta placed his hands on the temples of the country of Accad, and he carried away the statue of the goddess Nana : His days had been multiplied and his power was very great. The great gods permitted these things, and for the space of 1635 years this image remained in the power of the Elamites. That is wherefore I, Assurbanipal, the prince who adores the great gods, I conquered the land of Elam. . . . The statue of the goddess Nana had been in adversity for 1635 years ; she had been carried into captivity in Elam

a country which was not consecrated to her. The goddess with the gods, her fathers, proclaimed my name as sovereign of the nations, from this time forth, and she entrusted to me the task of rescuing her statue. She said : *Assibanipal will cause me to come forth from Elam, a land of the enemy and will establish me again in the Temple E-anna.* This divine command was pronounced in bygone days, but it was only those of my own time who explained it. Then I seized the hands of the statue of the great goddess, and, in order to rejoice her heart, I caused her to take a direct road to the Temple E-anna. The first day of the month of Kislev, I caused her to enter into the city of Uruk, and I reinstated her in the eternal tabernacle of E-anna, the temple of her choice."

The Ninevite bas-reliefs, which accompany these curious inscriptions, effectively represent a procession of Assyrian priests and soldiers, carrying the reconquered ancient idols on their shoulders with great pomp.

At the time of the destruction by Assurbanipal, Elamite Susa contained, not only the objects of art, the statues and valuable monuments relating to the history of Elam and the cult of her gods, but also, under the title of *spolia opima*, all the valuables which had been brought by the kings of Elam from their expeditions into Chaldæa as trophies of victory. Assurbanipal recovered the greater part of these objects, and replaced them in the towns from which they had been taken ; the booty was immense, as he himself records. But much would naturally have been effectually concealed, and this he would be forced to leave behind at the time of the sack

of the town; he also left a number of objects of secondary importance, such as certain statues, stelæ, and *kudurru*, which had originally come from Chaldæa.

Undermining and incendiarism destroyed all that could not be laden on the backs of the soldiery and animals of the Assyrian army, and thus Assurbanipal effected the complete ruin of Susa.

This explains the circumstance that a number of monuments and objects of Chaldæan origin are found in the ruins of Susa among others indigenous to Elam.

The capital of Elam appears to have been built once more after the departure of the Assyrians, for a cylinder of Nebuchadnezzar informs us that this prince built many temples there, as well as at Babylon.

Susa never again really recovered her ancient splendour until the time of the second dynasty of the Achæmenid kings of Persia. Darius, son of Hystaspes, made it the capital of his realms, and until the rise of Alexandria, Susa remained the most important centre of art, and of Persian civilization (see Chapter V.).

At this period, Susa was once more the theatre of events similar to those which so many centuries before had agitated her existence. When the entire East, Susa, as well as Babylon, and even Sardis, had fallen into the power of the Persian Achæmenids, and when Darius and, later, Xerxes, invaded Greece in B.C. 492 and 480, the Hellenic sanctuaries were pillaged in their turn. The Persians carried away their treasures, statues, and ex-votos across Asia as far as Susa, and there placed them in their own temples as trophies of their victories. When, in his turn, Alexander in B.C. 331 invaded the East, as avenger of the Hellenic

race, he laid a heavy hand on the treasures of Susa ; in that capital he discovered the great works of art of Greece, more especially the bronze statues of the Tyrannicides, Harmodius and Aristogiton, which Xerxes had carried away from Athens: these the conquering Macedonians were delighted to restore to the Athenians. The temple of Didyma near Miletus, like all others, had been pillaged by Darius, and its treasures carried off. What must have been the astonishment of M. de Morgan when he discovered in the course of his excavations a huge bronze knuckle-bone, weighing more than 152 lb. and bearing a Greek inscription of the seventh century B.C., recording that this singular object was dedicated by a dweller in Miletus to Apollo Didymæus.

Thus we find an ex-voto from the Temple of Didyma carried to Susa by the Persians under Darius, and which has now found its way to the banks of the Seine, an object of astonishment to visitors to the Louvre. This enormous knuckle-bone is provided with two handles to facilitate transport. The upper one, worn through by long-continued friction, shows traces of the iron bar or hook passed through it for its long journey from Miletus to Susa. Thus history—Proteus with his thousand forms—repeats itself unceasingly under its many transformations ; even modern times furnish us with numerous episodes similar to those just related.

§ III. THE PRINCIPLES OF BUILDING.

Speaking generally, there can be no study of the architecture in elevation, as the ruins afford no examples

of building in stone. We are forced to confine ourselves to examining the ground plans of the buildings, the pavements, and the foundations. Everything else has fallen to pieces, or been reduced to powder. In some of the tells of Chaldea, however, remains of temples and palaces have been found with the lower courses still in position.

It is in consequence of this that we have been able to give M. de Sarzec's reconstruction of the plan of the palace of Gudea at Tello (fig. 2, p. 9). The American Archæological Mission has also discovered at Niffer (Nippur) the lower courses of a *sikkurat*, or staged tower, in excellent preservation. In this region the building materials were frequently kiln-baked bricks, and mortar made of bitumen of such exquisite quality as to render the walls of such consistency that at the present day it is necessary to use powder to demolish them.

At Susa, so far as investigations have been carried at present, it appears that crude bricks were usually employed in building, and without the bitumen mortar, with the result that the walls were easily demolished, both by the pick-axe of the intentional devastator and by the corrosive action of the weather. "Thus on all sides," says M. de Morgan, "reigns the greatest of confusion of piled-up materials."

One exception has thus far been found, a small temple of the god Shushinak, where the plan can be traced, owing to the basement having been constructed of baked bricks, with revetments of glazed sandstone. Large numbers of tiles have also been found, enamelled with yellow or pale green and bearing the name of king Shutruk-Nakhunta. This is the class

of decoration which developed during the Achæmenid period, of which we have previously given some specimens.*

The hiding-places found under the pavement of the



Fig. 245.—Brick Column, Susa.

temple yielded a number of votive objects, which are exceedingly interesting and valuable. Of these we shall speak later ; we must now only mention the brick columns, the principle of which has been studied, and of which we give a representation (fig. 245).

* See pp. 168, 169, 171 (figs. 135, 136, 137).

This column is composed of a number of bricks, all of which bear the name and protocol formula of the royal builder, Shutruk-Nakhunta. Some of these bricks are square, others round, and others are segments of circles. The figure here given sufficiently indicates how they are arranged, and it will be seen that the principle is precisely the same as in the similar constructions at Tello (see p. 10, fig. 3).

Observations made on the spot show that the column was worked over from the foundation after its construction, for many bricks with the name of Shutruk-Nakhunta are reversed, and there are others with names of other kings. To obtain more precise information on Elamite architecture and building, we must wait for further discoveries, which will surely not be long deferred.

§ IV. STONE SCULPTURE.

The earliest example of the sculptor's art found by the de Morgan Mission up to the present time is a Chaldæan stela, transported from Babylonia to Susa as the result of some victory. It is an obelisk of black diorite, similar to the statues discovered by M. de Sarzec at Tello, of pyramidal form with a rectangular base. It measures 4 ft. 3 in. in height. The four faces are covered with cuneiform inscriptions in a language which is a mixture of Sumerian and Semitic. The writing is very fine, inscribed with care and delicacy, and the text comprises not less than 7,600 signs. It refers to a king named Manishtu-Irba, as purchaser of lands in the neighbourhood of Kis, to the

north of Babylon. This monument is purely epigraphic, and bears no sculptures, at any rate in its present condition.*

Another example dates back to the same period, and is also Chaldæan in origin. It is a fragment of sandstone pavement ($37 \times 17\frac{1}{2}$ inches) on which is sculptured in relief one of those fantastic genii peculiar to Chaldæan mythology. He has a human head, and is standing, holding with both hands the boughs of a sacred tree similar to that represented on the Chaldæan cylinders. The eye is enormous and disproportioned, the nose prominent and arched, the chin retreating: above the mouth there is a small drooping moustache, while the beard, formed at first of small regular curls, divides into a series of straight locks and falls square over the breast. A striped band, finished with an ornament shaped like the ear of an animal, forms the head-dress, and from it a heavy coil or twist of hair falls to the shoulder. There is a pair of immense horns on the top of the head. The body ends at the loins with animal's feet and a lion's tail. The style and type of this genius recalls in a striking manner the most archaic of the bas-reliefs of Tello.†

On other stone reliefs are unfolded before our eyes a convoy of prisoners in chains, or again, the episodes of a siege, the immolation of prisoners, vultures devouring the corpses on a field of battle; on another there is a figure of a god with long twisted beard, and massive shoulders, placidly seated on his throne and receiving the homage of the prince who is under his

* *Memoires de la Mission*, vol i., pl. ix.

† *Memoires de la Mission*, vol.vii., pl. i., fig. A.

protection. These scenes, at once expressive and severely simple, are excellent specimens of primitive Chaldæan art as revealed to us at Tello. Imported into

Susa by conquest, there is nothing Susian about them.

The most interesting of these Chaldæan monuments discovered in the rubbish of the Elamite capital is undoubtedly the triumphal stela of the king Naram-Sin (fig. 246), which attracted much attention immediately after the notification of its discovery by M. de Morgan and Dr. Scheil in 1898. This stela is sculptured on a



Fig. 246.—Triumphal stela of Naram-Sin.

block of sandstone, covered with bas-reliefs and inscriptions. It is 6 ft. 4 in. high and 3 ft. 2 in. wide; the outline is irregular and the sculptor has utilized the

whole for his composition, without attempting to get rid of the irregularities, as though the block itself possessed somewhat of a sacred character and was held inviolate, even before the addition of the sculptures with which it is decorated.

A primary inscription relates that Naram-Sin, king of Agade in lower Chaldæa, 4000 B.C. caused this stela to be erected, in order that there should be engraved on it the account of his warlike deeds against the people of Lulubi.

But the stela bears a second inscription, added long after the time of Naram-Sin. This new cuneiform text is not Chaldæan ; it is in the Anzanite language and bears the name of Chutruk-Nakhunta, king of the Elamites.

Notwithstanding the uncertainty which still attends the interpretation of Anzanite texts, Dr. Scheil has been able to ascertain that in this inscription, Chutruk-Nakhunta boasts that he has carried off the stela of Naram-Sin from the town of Sippara in Chaldæa, after a victory, and has had it removed to Susa, and caused this inscription to be cut on it, mentioning his victory and the removal of the stela. Thus this monument, discovered by M. de Morgan, was originally a trophy of victory of the Chaldæan king, Naram-Sin, which later became a similar trophy of Chutruk-Nakhunta, when the Elamites took vengeance on the Chaldæans and succeeded in invading Chaldæa.

The curious bas-relief which decorated the greater part of the stela, dates back to primitive times, and represents, not the conquest of the Elamite kings, but those far earlier victories of the Chaldæan, Naram-Sin.

M. de Morgan thus describes it: "The king, victorious over the Lulubis and their allies, is pursuing his enemies in the mountains. At the head of his army he climbs the heights; corpses cover the ground and roll over the precipices; the vanquished, who have taken refuge in the forest, are imploring mercy from their conquerors, to escape falling under their weapons. The stars of heaven, favourable to the armies of Agade, are illuminating with their glow the glories of Naram-Sin. Such is the *motif* that guided the sculptor, and such no doubt was the leading idea given him by the king. As to the interpretation, the arrangement of the figures, and grouping of the whole scene, that is the work of the artist.

"The composition of the bas-relief of Susa is clever in its simplicity. Only eight armed men are figured, to represent the army of Agade, which is led by Naram-Sin in person. Two act as scouts in the forest, while six represent the body of the troops. Three men are falling dead and one wounded under the blows of the king, to express the carnage wrought on the foe by the conqueror, and four fugitives are holding up their hands to figure the submission of the conquered. Two trees remind us by their shape, of the sparsely wooded forests which cover the mountains of Kurdistan."

Such is the summary synthesis of the victories of Naram-Sin, the sight of which must have struck the imagination of the Chaldæans, reminding them of the mountainous and wooded country which had been the theatre of so terrible a slaughter.

The country which forms a setting for this scene is depicted with the same simplicity we find later in the

Chaldæan and Ninevite sculptures, and may be compared more especially with the Chaldæan work on the *Vulture Stela* found by M. de Sarzec at Tello (see pp. 25, 26, figs. 11, 12, 13). An enormous cone, with various undulations surrounding it, represents the mountainous country that is pervaded by the army of Naram-Sin. A few trees suggest the forest, superposed registers take the place of perspective. The figure of the king is colossal, to assert his superiority—a convention possessed by Chaldæan art, in common with the art of Egypt and Assyria. His calm attitude indicates that he has gained the victory without the slightest difficulty. On him, thus figured after the manner of a Greek hero as a demi-god, the artist has concentrated his principal efforts; it is he on whom attention must be centred. His body is well proportioned and well drawn, although stiffened into a conventional attitude, the eye is large, the nose short, the beard silky and flowing long over the breast, and the working of the muscles is powerful and remarkably realistic.

It may be objected that the figure is too narrow, and we should consider it altogether too slender, were it not that the same defect appears in the other figures.

“The only defensive armour worn by Naram-Sin,” remarks M. de Morgan, is a casque. This is a pointed cap, ogive in form, which rests on a band surrounding the forehead. This band has two pointed pads reaching to the top of the cap—one in front, the other behind—and is adorned with two horns, whose curves harmonise with the outline of the head-dress. A metal screen falls over the nape of the neck, protecting the neck and

shoulders. With his left arm the king is clasping to his breast his bow and battle-axe, in the right hand he holds an arrow, hesitating as the suppliants kneel before him, whether to deal one more blow with his weapons. . . .

“Naram-Sin fought half naked, wearing only one tight narrow garment, which affords full value to all the parts of his body.

“The tunic, crossed on the chest, is embroidered at the collar ; it is drawn tightly round the body and knotted at the side. Two long folds fall below the knee ; on the neck is an amulet ; heavy bracelets are on the wrists, and a long girdle round the waist. The legs are bare, and on the feet are sandals with flat soles, similar to those worn at the present day by many Orientals, fixed on by straps passed between the toes, and fastened together above the ankle.”

On close examination it will be seen that the two groups of warriors depicted, the victors and the vanquished, clearly indicate their distinguishing characteristics, from the ethnical and anthropological point of view. The first—the conquerors—have the Semitic profile, while the second—the conquered—have a profile approaching the Negritic type. Thus, in this carefully sculptured piece of so remote a date, we find realism, which is most minute in detail, associated with most fantastic conventions as regards the general arrangement of the composition—a double characteristic which, as we have repeatedly maintained, has always remained the original stamp of oriental art.

The ethnic peculiarities of the Negrito race are even more strikingly indicated on a fragment of bas-relief

which represents the bust of some person, nude, bearded, with a small cord tied round the head (fig. 247). What living realism there is in this lean body, bony and loose jointed! What close study of nature in the knitting of the muscles, the crisp thick beard, the enormous projecting lips, the nose with its distended cartilages, and the disproportionate eye presented full face! In all this is there not an amount of character which bespeaks a sincere art, observant of nature, and capable of rendering it with brutal frankness?

The celebrated code of laws of Hammurabi, the most important monument which up to the present time has been exhumed from the ruins of Susa, is, also, not of Susian origin (fig. 248). Hammurabi was king of Babylon, and the



Fig. 247.—Fragment of bas-relief representing figure of Negrito type.

stela on which his law is engraved was taken from Chaldæa. The text itself tells us its origin. It was originally at Sippara, in the temple of the sun, the god who inspired the precepts engraved on the monument. Shutrük-Nakhunta caused it to be transported to Susa after his victorious campaign into Chaldæa. It is a block of diorite, with a circumference of about 6 feet at the base, and is 7 ft. 3 in. in height. It resembles an enormous ovoid pebble, carefully polished but not shaped, a characteristic which we have observed in the stela of Naram-Sin and a large number

of Chaldæan monuments. The whole surface is covered with fine close writing, engraved with most careful precision. The space at the top of the stela is reserved



Fig. 248.—Stela of Hammurabi, on which his code of laws is engraved.

for representations in high relief of the god Samas, holding out his hand to the king, who is standing before him, giving him the stylus, with which to write his laws. The costume both of god and king is purely Chaldæan.

Again Chaldæan in origin, although of far later date, is a small diorite fragment of bas-relief called the *bas-relief of the Spinner*.* It represents a woman sitting on a stool, her legs crossed and feet behind in the tailor's attitude. She is holding her spindle with both hands; in front of her is a fish lying on a table, and behind her a slave is waving the fly-flap.

The round chubby faces of the figures recall the bas-reliefs of Khorsabad, which represent the eunuchs of the Ninevite palace.

Among other stone monuments with which the excavations at Susa have enriched the Louvre Museum, there is a considerable series of large ovoid diorite blocks,

* *Mémoires de la Mission*, vol. i., pl. xi.

similar to the famous *Caillou Michaux*, which is figured earlier in the book (page 34, fig. 21). The original name of these objects is *Kudurru*, which corresponds with the idea of "limit, boundary." These are titles of rural properties given to important personages, or to temples, by the kings of Babylon. In addition to the inscriptions, which fix our attention, these *kudurru* are covered with bas-reliefs of monstrous figures of gods and demons, under whose supervision the contract is placed, or who would punish those who should dare to change the object and its inscriptions. Those bas-reliefs, where the Babylonian divinities are seen accompanied by their totems, are only of mediocre workmanship, but the figures carved on them are exceedingly interesting and curious. At the top of these objects there is generally the figure of the celestial serpent rolled up or outstretched. The *kudurru* found at Susa do not differ from those of Chaldæa, and are undoubtedly imported from that country.



Fig. 249.—Kudurru (unfinished), Kassite period.

One of the most remarkable is that of Melisihu, king of Babylon.* Another, which deserves special notice, is that of "Nazi-maruttas, king of Kis, son of Kurig-alzu, descendant of Burna-buryas, king of Babylon."† By way of a specimen we give here an illustration of one which offers a special peculiarity—it is unfinished (fig. 249). It will be seen that the figures are winged.

* *Mémoires de la Mission*, vol ii., pl. xxiv.

† *Memoires de la Mission*, vol. ii., pl. xviii., xix.

Huntsmen, gods, serpents, lions, and birds, the usual decorations of the *kudurru*, are well engraved, but the cuneiform text is absent. The space reserved for it is framed by two columns, the body of a serpent and a crenellated frieze. It appears, therefore, that this object must have been seized in Chaldæa by the Susians, before it had been utilised and consecrated.

From this general sketch of the stone sculptures which so far have been recovered from the ruins of Susa, one essential fact stands out prominently ; stone-carving was not practised in Susa : all the monuments hitherto discovered were brought from Chaldæa. They are Chaldæan sculptures imported into Susa by the victorious Elamites.

§ V. BRONZE METAL-WORK.

Owing to the fact that they lived in a country where stone could not be obtained without great difficulty, the Susians built their houses, palaces, and temples with brick : and it was doubtless due to the same cause that they showed themselves so eager to carry off the stone statues and bas-reliefs that adorned the Chaldæan cities, and which they seized by right of conquest, to embellish their own capital. The same reason will also explain the extraordinary development we find in the metal-working of the Elamites from the earliest times. With them, bronze took the place of stone. They made bronze statues, bronze bas-reliefs, bronze beams, and such was their knowledge and technical dexterity, that we might almost assert without fear of exaggeration, that bronze metal-working was as advanced three

thousand years before our era, as it has ever been in modern times.

M. de Morgan brings this to the proof by exhibiting at the Louvre, among his Susian discoveries, a bronze cylinder 14 ft. 3 in. in length, cast in one piece, like a cannon of average calibre, and covered over the whole surface with archaic cuneiform inscriptions, in the name of the Elamite king, Shilhak-in-Shushinak. Another cylinder of the same class, but not quite so long, is larger in diameter.

What can have been the purpose of these colossal tubes, which are cylindrical, except at the ends where they are squared? One of them is inlaid with small gold studs. It is improbable that they were columns; it appears more likely that they were placed horizontally as beams, or railings, intended for the protection of a nation of giants.

Another bronze object not less strange, is a species of altar, or rather a sacrificial table. This also is made in one single casting, 5 ft. 3 in. long, 27½ in. broad, and 12 in. deep. It is pierced like a stone sink, to allow liquids to escape, and round the sides it is decorated with two enormous serpents. There are also five human busts, Atlas-like figures, who support the altar on their powerful shoulders. Unfortunately, this colossal object has been mutilated with unusual fury; it bears many traces of blows from a mallet, and all the protruding parts have suffered. The five Atlas heads have been broken off and have disappeared. The victorious pillagers, it appears, only stopped their vengeance when their strength was exhausted, and when the enormous metal slab, reduced to a shapeless

block without projections, resisted all their efforts. A large number of other objects found by M. de Morgan, both in stone and bronze, bear alas! similar traces of the merciless and brutal hatred displayed by the various races which disputed the domination of Elam.

In consequence of this treatment, it is impossible to judge the sacrificial table from the artistic side. For this point of view we must turn to a bronze bas-relief,



Fig. 250.—Bronze bas-relief fragment (Louvre).

dated in the reign of Shutruk-Nakhunta, which may be considered the earliest artistic monument, well-preserved in the essential portions, which is also actually Elamite (fig. 250). This bas-relief is damaged at the sides, and pieces have been violently broken off, but a fragment still remains, 3 ft. 3 in. in length, and about 2 ft. in height. The most deeply

cut reliefs project about half an inch. "It consists," says M. de Morgan, "of three superposed registers; the upper one is almost completely destroyed, and only enough remains to enable us to discover the subject depicted on it: these are figures of human beings and of animals. The middle register is rather more than 16 in. in height, and on it are seven figures 14 in. high, walking towards the right. The lower register was greatly neglected and merely contains drawings of birds and trees, worked with the burin. . . ."

“The seven personages in the middle register are all alike. The left hand is lowered and holds a bow with a double curve, while the right brandishes a large curved dagger over the head. Behind the right shoulder the quiver can be seen full of arrows, and the strap worn across the breast. They wear large head-dresses, below which hangs their long hair. The beard is worn long, and from their general appearance they appear to belong to the Semitic races. The tunic which covers the body is confined at the waist by a belt, and falls below the knees, open in front. Although they are carefully studied and rendered with tolerably correct proportions, these figures are far from presenting the artistic qualities of the sculptures on the stela of Naram-Sin. They are stiff, too slender, their limbs are lanky, and their feet disproportionately long.

Notwithstanding these defects, they are superior to Assyrian work, and show that the Elamites possessed artistic instincts to which we are not accustomed among Semitic people of this period.” *

The inscriptions accompanying these figures are in the Elamite language; they are votive, and refer to the building of temples in honour of various divinities.

Thus, possessing no stone for carving bas-reliefs comparable to those of Nineveh, the Susians supplied the deficiency by casting gigantic bas-reliefs in bronze. Their knowledge of metallurgy, which was so marvellously developed, extended yet further: having no means of obtaining great blocks of diorite such as were employed by the Chaldæans for the statue of Gudea at

* *Mémoires*, vol. i. (1900), pp. 163-164.

Tello, they demanded of their bronze-founders, statues of that metal, similar to those of their neighbours. They succeeded in producing statues more than life-size at one single casting, in solid bronze.

On entering the *Salle Susienne* at the Louvre, one's attention is immediately drawn to the bronze statue of queen Napir-Asu, wife of king Untash-Gal, who reigned B.C. 1500. This statue, of which the head unfortunately is lost, is life-size. With outstretched fingers the queen crosses her hands over the breast, on her wrists there are quadruple bracelets, and on the fourth finger of the left hand she is wearing a ring; the anatomical details of the finger-joints are particularly well rendered. The costume consists of a long fringed robe that falls to the feet. The general outline of the skirt is bell-shaped, and is striped and sprinkled with stars, no doubt intended for spangles worked into the tissue. The bodice is tight-fitting, and shows the outlines of the figure; on the shoulder there is a jewelled fibula, and down the length of the sleeves there are elegant clasps. Finally, a large embroidered shawl is thrown over the shoulders; one end hangs in a point in front, like the enormous wing of some bird. It is, indeed, marvellous that such details could be accurately rendered in a statue of solid bronze, weighing I know not how many tons.

In addition to these gigantic specimens of Elamite bronze-casting, we possess a large number of votive statuettes in bronze as well as utensils of every kind and form. In the foundations of the temple of the god Shushinak, more especially, a number of bronze statuettes were discovered. These represent generally

figures of men standing, the hands raised to the body, either holding a bird as though making an offering to the god, or in other instances in the Chaldæan attitude of prayer (fig. 251).

In the example we give here, the figure is holding a bird with both hands, the head is completely shaved as in the diorite statues from the palace of Gudea (see p. 27, fig. 14). In all these instances, the metal-work of Susa is a copy or imitation of Chaldæan sculpture.

§ VI. JEWELLERY AND THE INDUSTRIAL ARTS.

One of the most sensational discoveries effected by the French Mission in Susa was that of January 22, 1904, when a gold and a silver statuette were found in perfect preservation and original in style (fig. 252). That they were votive offerings is shown by their having been found under the pavement of the Temple of Shushinak with other offerings of less surpassing interest, among which was a small diorite staff with the head of a lion in gold filigree, executed with marvellous delicacy. As it is necessary to make a selection in order to keep within limits, I must content myself with describing the gold statuette. It is $2\frac{1}{2}$ in.



Fig. 251.—Bronze statuette. Temple of Shushinak (Louvre).

in height, not including the bronze pedestal on which it is placed. It was worked over with the burin and punch after being cast, and, as in the case of the bronze statuettes, the figure recalls the products of Chaldaean art (compare, for example, fig. 27, p. 40). It represents a man standing dressed in a garment delicately fringed round the lower edge, below which the feet are partly visible. His right arm is raised, the hand outstretched in the attitude of prayer; with the left he



Fig. 252.—Gold and silver statuettes (Louvre).

is holding a young bird to his breast, an offering to the god whose protection he is imploring; again the usual subject of the bronze statuettes. He has a long beard, his nose is straight and prominent, his eyes disproportionately large, and the chin is retreating. His abundant hair is expressed by fine reticulated lines, and on his immense head there is a tiara, which resembles in form a twisted piece of material. The dress on the front of the body is sprinkled with small stars; round his waist is a girdle, and the skirt of his robe is dotted with small holes made with a punch, which no doubt represent embroideries or gems worked into the material.

The silver statuette found with the gold figure is

almost exactly like it, and is also in perfect preservation. Both are probably figures of the king who was founder of the temple, and supreme pontiff; he is bringing to the god the victim to be sacrificed on the occasion of laying the first stone. We might dwell at length on the want of proportion in the different parts of these statuettes; the head is too large, the ears badly placed, the chin too low on the chest. They are nevertheless exquisite examples of goldsmith's work, of unusual size, and essential as illustrating the history of Elamite art.

There is another piece, that would be even more important than these statuettes had it reached us in a better state of preservation (fig. 253). This is a silver mask in repoussé work, and one hand of the same metal, which formed part of a statue probably of wood, the nude parts, the face and hands, being of silver. Numerous



Fig. 253.—Silver mask, Elamite period (Louvre).

Numerous silver studs which remain riveted in position must have been intended to fix the metal to the wood. The wood has decomposed, and only the oxidised metal remains. The statue must have been one-third of life-size.

Judging from the features, the head represents a woman of Semitic type; it may perhaps have been an image of the goddess Nana. The two hands were closed, holding some objects which have now disappeared, the large eyes were made of carved ivory,

and the pupil, which has also disappeared, was probably made of some glittering gem. At the same time that the silver mask was recovered, two head-dresses of glazed sandstone were found (fig. 254). One of these is in the form of a wig divided into two parts, one covering the head, the other falling over the neck. The front of the headpiece is decorated with a projecting gold button in the centre, and there are also thirty-five gold studs arranged in front; the back and sides are decorated with silver and brass studs.



Fig. 254.—Head-dress. Elamite period (Louvre).

The second of these head-dresses is also in glazed sandstone, and is a kind of cap or turban, shaped like the knob of a stick, and decorated over the whole surface with nine rows of bronze disks held in place by nails of the same metal arranged quincunx fashion.*

This kind of cap was usual among the Chaldæans, and we find examples both on bas-reliefs and cylinders.

There are numerous objects in ivory which date back to the primitive period of the history of Elam. These consist of engraved plaques, figures of animals, statuettes, and small implements. Of this series we must call attention to a delightful ivory figure $4\frac{1}{4}$ in. high, of which unfortunately the head is missing (fig. 255). It represents a woman standing, her hands

* *Mémoires de la Mission*, vol. vii., pl. x.

crossed on her breast, as in the Tello statues. Her costume consists of a long dress reaching to the ankles made in one piece with only a trimming of braid round the bottom, and a different pattern of braid on the bosom. It covers the shoulders like a cape, leaving the fore-arms bare. The modelling of the arm has been studied with elaborate care. A fringed shawl in narrow pleats is thrown over the right shoulder above the dress, and falls over the back and the front as low as the knee. A hole pierced in the neck shows that the head must have been separate and fixed on; possibly it was of gold, and a deep groove on the border of the cape at the neck and over the elbow indicates that it also was of gold.

The lists of objects of all kinds found up to the present time, with the fine works of art we have been considering, have already filled several volumes: This means that these industrial objects almost enable us to evoke the daily life of the ancient inhabitants of Elam. There are cylinders, some in glazed pottery, others in ivory, hæmatite, chalcedony, and jasper, which were employed to seal their contracts; alabaster vases of various shapes; an immense number of small gold, silver, and bronze rings, and also flat disks in these metals, which may have been used for money; a dove in lapis-lazuli, studded with gold; magnificent gold bracelets and others of silver and bronze, often worked



Fig. 255.—Figure of a woman, ivory (Louvre).

with great delicacy, pins, fibulæ, pendants, beads in glass, alabaster, lapis-lazuli, and pottery, sometimes incised with geometric designs : domestic utensils, heads of staves or sceptres, axes, knives, and various weapons : there is nothing missing of the ordinary outfit of the subjects of Shutruk-Nakhunta, king of Elam, the great conqueror and builder.

Two horns made of alabaster, bearing inscriptions in the name of this prince, must have belonged to an enormous bull's head.* There are numbers of objects of a votive character, which appear to have been thrown in quantities into the foundations of the temple of Shushinak. Griffins' heads in gold, animals' heads in pottery, lions carved in agate in the round, bulls' heads in lapis, pendants in carnelian mounted in gold, sheets of gold with Anzanite inscriptions. There is ample space in this new field of archæology for studying these objects, for classifying and comparing them, and drawing from them all the information that can be afforded by their examination.

Want of space forbids our dwelling longer on this subject, and for the same reason we will say nothing about the numerous monuments of the period of the Persian Achæmenids, nor with yet stronger reason, of the time of the Parthians, Arsacids, and Sassanians, which does not enter into the scheme of our present volume. And yet, in bringing this rapid sketch to a conclusion, we will remark that, of all the discoveries made by M. de Morgan, that which is perhaps most admired by the public is the gold jewellery, set with precious stones, which came from the tomb of a woman

* *Memoires de la Mission*, vol. xix, p. 90 and pl. iii.

of the period of the Persian Achæmenids. It is advisable to compare it from a technical point of view with the more ancient jewellery of the Elamite period.

These bracelets, pendants, and gold beads, these multiple rows of the richest necklaces, bear witness to the extraordinary luxury of the courts of Darius and Xerxes, and may well dazzle us. Noticeable among these treasures are pendants formed of minute gold curls, in imitation of the curled and wavy manes of lions. Here I believe we find an artistic innovation of striking originality in a form of art bound by conventions and traditions.

The setting of the gems in gold mounts of marvellous delicacy has not in any civilisation attained a higher level than in Achæmenian Susa. It is necessary to use a magnifying glass to examine this minute and delicate work. Here is the perfection of the goldsmith's art, and these Persian jewels of the fifth century B.C. now form a preponderant and essential factor in the question round which so much controversy rages, of the origin of cloisonné jewellery.

INDEX.

- Absalom, Tomb of, 234.**
Abu Habbah, 2, 12, 42.
Abu Shahrein, 2, 3, 10, 18, 73, 76.
Achæmenid dynasty, Palaces of, 56, 118, 147 ff.
jewellery, 337.
Addume, 294.
"Æginetan smile," 273.
Afaj, 36.
Agade, 47, 308, 319, 320.
Ahasuerus, 139.
Ahura-mazda, 165, 166, 172, 179.
Ain el-Hayât, 240.
Alabaster,—
 thresholds of, 17.
 statuette of, 42.
 uses of, in Assyrian architecture, 85.
 Phœnician mortuary vases of, 259.
 vases, 307, 335.
 beads, 336.
 horns, 336.
Ala-Safat, 230.
Alexander the Great, 312.
Altar of burnt-offerings, the, 221.
 bronze, 327.
Amanus, 60.
Amathus,—
 vase of, 31, 77.
 tombs at, 260.
 colossus of, 271, 272.
 iconic statues from, 274.
 sarcophagus from, 291.
 patera from, 291.
Amethyst, 142.
Ampulla, sacred, on cylinder, 47.
Amrith, 239, 248, 253, 264, 277.
Amulets, 17, 21, 44, 51, 259.
Animals,—
 figures of, on Chaldæan tiles, 19.
 representation of, in Assyrian sculpture, 107, 108, 109.
Annipi, 294.
Antiphellus, 177.
Antonia, Tower of, 210, 211, 212, 218, 232.
Anunit, the goddess, 2.
Anzan, 302.
Anzanite inscription, 304, 307, 319.
 on gold sheets, 336.
"Apadâna" of Persian palaces, 154, 157, 168, 301.
Aperlæ, 177.
Apes, in Assyrian sculpture, 109.
Appian, on harbours of Carthage, 250.
Aradus, 247.
Arak et Emir, 232.
Araunah, 205, 208, 215.
Arbela (see ARVIL).
Arch, use of, by Assyrians, 55.
 of Titus, 226.
Archers, frieze of, at Susa, 169, 170.
Architraves, 77, 152.
Archivolt, at Khorsabad, 116.
Aristophanes, 41.

Aristotle, on Babylon, 79
 Ark, Jewish, 224, 225.
 Armenia, 76.
 Arrangement of rooms in Chal-
 dæan palaces, 16.
 Arrian, on tomb of Cyrus, 177.
 Artaxerxes Mnemon, 168, 183.
 Artaxerxes Ochus, 152.
 Arvil, 51.
 Asmonæan kings of Judæa, 218.
 Asrinilu, 46.
 Assurbanipal, 60, 72, 92, 310.
 campaign of, against his
 brother, 80.
 as canephoros, 89.
 with his wife, 101, 102.
 progress of sculpture in time
 of, 113.
 furniture of, 135.
 Assur-nasir-pal, 60, 61, 72, 91,
 92, 138, 139.
 statue of, 86.
 progress of art under, 112.
 Astarte, 241, 243, 245, 260, 264,
 279.
 "Atesh-gahs," 173, 174.
 Athieno, 242, 270, 271.
 Attitude of prayer (see GES-
 TURES).

Baal-Hammon, 245, 246, 263,
 267, 268, 269.
 Baal-Samaim, 245.
 Babel, Tower of, 4.
 Babil, mound of, 16, 52, 73.
 Babylon, 1, 60, 118.
 walls of, 5, 79, 80, 81.
 modelling in clay at, 39, 123.
 buildings at, 52.
 temple of Bel at, 73.
 extent of, 79.
 Bagdad, 15.
 Bahr-el-Huleh, 230.
 Balaneum (see BANIAS).
 Balawat, 51.
 gates of, 126, 127.

Banias, 246.
 "Baphomet," 202.
 Baris, Tower of (see ANTONIA).
 Basalt stela, 34.
 Base of columns, 11, 12, 43,
 64, 65.
 Basement (see PLATFORM).
 Basilica of Herod, 219.
 Basin, movable, in Jewish
 Temple, 229.
 Basins before temples, 31, 77.
 Basket, mystical, 36, 37, 89.
 Bas-reliefs,—
 Chaldæan, 23-6, 324.
 Assyrian, 54, 91-3, 311.
 Persian, 159-66.
 Hittite, 187-91, 193-202.
 Phœnician, 262-4.
 Carthaginian, 266-9.
 Cypriote, 274-6.
 Elamite, bronze, 327.
 Battlements,—
 of platform at Khorsabad, 53.
 of walls of Assyrian towns,
 81, 82, 110.
 of platform at Persépolis, 152
 Bavian, 187.
 Beads, 336.
 Bel, the god—
 temple of, at Babylon, 7, 73,
 74, 76, 77, 78, 119, 125.
 Bel and the Dragon, Book of,
 77.
 Belisarius, 227.
 Belshazzar, 114.
 Belus, the river, 283, 287.
 Berosus, 2, 119.
 Berytus, 247.
 Bes, the god, 259, 264, 271, 272.
 Birds, treatment of, in Chaldæan
 art, 25.
 in Assyrian art, 109.
 offered to the gods, 331, 332.
 Birejik, stela from, 187.
 Birket-Israil, 208.
 Birsnimroud, Mound of, 6, 16,
 52, 73.

- Bit-kutalli, 70.
 Bitumen, use of, as mortar, 5,
 6, 8, 17, 20, 314.
 Boar on Babylonian tablet, 128.
 Boaz, the column so-called, 227.
 Boghaz-Keui, 191.
 Borsippa, 78.
 Botta, E., 66, 142.
 Boulé, M., 246.
 Bracelets, Assyrian, 142, 143.
 Elamite, 335.
 Achæmenian, 337.
 "Brazen Sea" in Jewish Tem-
 ple, 77, 228.
 Branchidæ, 28.
 Brick column at Susa, 315.
 Bricks,—
 use of, by Chaldæans, 3-8,
 10, 17, 19.
 by Assyrians, 53, 65, 74,
 116-20.
 by Persians, 167-72.
 by Hittites, 191.
 by Elamites, 314.
 Bronze, 12, 18, 35-7, 63, 70,
 125-34, 227-9, 288-92.
 use of, in Susa, 326.
 altar, 327.
 cylinders, 327.
 bas-relief, 327.
 statues, 330.
 knuckle-bone, Temple of
 Didyma, 313.
 Bulls,—
 winged and human-headed,
 92-6, 154, 167, 224.
 in Assyrian decorative de-
 signs, 114, 115.
 in Persian sculpture, 162,
 163.
 on Elamite cylinders, 305,
 307.
 Bulls' horns on tiara, 23, 26.
 Burin, 45, 308.
 Burj el-Bezzâk, 255.
 Byrsa, 246.
 Byzantine architecture, 159.
 "Caillou Michaux," 33, 34, 325.
 Calah, 91.
 Cambyses I., 176.
 Cambyses II., 150.
 Candlesticks, Jewish, 226, 227.
 Canephoros, 36, 37, 89.
 Canopy of Persian throne, 165.
 Capitals, 12, 43, 63, 64, 155,
 156, 227, 242, 248.
 Cap of Chaldæan statue, 28,
 334.
 Caralis, 260.
 Carchemish, 185.
 Carthage, 247, 248, 249.
 Caryatids, 86, 87, 327.
 Casat Crendi, 244.
 Cedar-wood, use of, in Assyria
 and Babylon, 60, 61, 78.
 Cemetery, Assyrian, 50.
 Ceramics,—
 Chaldæan, 38-40.
 Assyrian, 121-5.
 Phœnician, 277-9.
 Cypriote, 280-1.
 Carthaginian, 282.
 Cesnola, P. di, 242, 243.
 Chair, Assyrian, 135.
 Chalcedony, 44, 142, 182, 335.
 Characene, 12.
 Chariots, Assyrian, 136, 137.
 Chedorlaomer, 300.
 Cherubim, 93, 224.
 Cidaris, 179.
 Cippi, 111, 260, 268.
 Cisterns,—
 Jewish, 215, 232, 233.
 Carthaginian, 249.
 Citium, 270.
 Clamps, use of, in building,
 149, 150, 191.
 Clay, in building, 4, 6, 39, 40,
 54, 56.
 tablets, Elamite, 305.
 Clercq, M. de, 45, 46, 47.
 Clermont-Ganneau, on Phœni-
 cian patera, 290.
 Cloisonné, 337.

- Coffins, at Mugheir, 20.
 Phœnician, 256-9.
- Colocyths, 224, 225, 228, 229.
- Columns,—
 Chaldæan, 9-12.
 Assyrian, 61-6.
 Persian, 153-6.
 Jewish, 217, 227, 231.
 Cypriote, 241, 242, 248.
 Elamite, 315.
- Concrete, 17.
- Cone, mystical, 242.
- Cones, 18, 21, 36, 38.
- Contracts under protection of gods, 326.
- Corbelled vault, 14.
- Courts,—
 of Chaldæan palaces, 16, 17.
 of Assyrian palaces, 69, 70.
 of Jewish Temple, 218-21.
- Crater, 292.
- Cross, as Assyrian ornament, 143.
- Ctesias, 70, 81, 119.
- Cuneiform writing, origin of, 305, 306.
- Curium, 243.
- Cylinder,—
 foundation, 21, 22.
 inscribed, 305, 306, 307.
 huge bronze, 327.
 Elamite, 335.
 seals, 335.
- Cylindrical seals, 17, 21, 44-9, 142-5, 146, 180-4, 203, 294-8.
- Cyrus, 146.
 his portrait, 160.
- Dakhmas, 174, 175.
- Dali, 259.
- Daniel, Book of, 114.
- Darius, 150, 152, 301, 312.
 bas-relief of, 166.
 tomb of, 178-80.
 cylindrical seal of, 181.
- David, 205, 232.
- Decoration,—
 of Chaldæan vases, 39, 40.
 of Chaldæan walls, 9, 12.
 of Assyrian vases, 122, 123.
 of Hittite cylinder, 203.
 of Holy Place in Jewish Temple, 224.
 of Phœnician sculpture, 263, 264, 267, 268, 269.
- Deir Ghuzaleh, 231.
- Demons, 116, 130, 132-4.
- Didyma, Temple of, 313.
- Dieulafof, M., 118, 149, 165, 174.
- Dimas, 252.
- Diodorus Siculus, 76, 80, 119.
- Diorite, 17, 26, 316, 323.
- Disk, winged, 166, 172, 187, 201, 240, 263, 269, 296.
- Disks, metal, used as money (?) 335.
- Divan, Assyrian, 135.
- Divine Mother, The, 48, 124, 267, 281.
- Dolmens, 230, 231.
- Domes, 15, 56, 158, 159.
- Doors, 17, 152.
- "Double Gate" of Jewish Temple, 216, 217.
- Dowry, record of, 33.
- Drainage, 20, 21, 51, 57-9.
- Drapery,—
 treatment of, in Chaldæan sculpture, 34, 35.
 treatment of, in Assyrian sculpture, 105.
 treatment of, in Persian sculpture, 161, 165, 166.
 in Cypriote art, 273, 274.
- Drill, use of, by Assyrian seal-engravers, 144.
- Dungi, 309.
- Dur-Sarrukin, 66, 69.
- Eagle and Lion Tablet, 24.
- E-anna, Temple of, 6, 310, 311.
- Ecbatana, 74, 75, 146.
- Eflatoun, 200.

- Egyptian style,—**
 in pateræ from Assyria, 128.
 in ivories from Assyria, 137, 138.
 in Persian architecture, 156.
 sarcophagi in Phœnicia, 257, 258.
E-kua, Temple of, 60, 78.
Elam, 299.
Elam-Anzanite period, 304.
Elephant in Assyrian sculpture, 109.
Embroidery,—
 Chaldæan, 34, 41.
 Assyrian, 105, 106, 138-41.
 Persian, 172, 180
 Jewish, 224.
Enamelled bricks, 19, 70, 74, 83, 116-20, 153, 167-72, 336.
Enamelled statuettes in Phœnicia, 278.
Enio, the goddess, 196.
E-parra, Temple of, 6.
Ephod, 230.
Erech, 2, 48, 125, 309.
Eridu, 2.
Eryx, 247.
E-saggil, Temple of, 6, 73, 78.
Esarhaddon, 22, 72, 92.
Eshmun, the god, 245, 246, 268.
Eshmunazar, 257.
Esther, Book of, 140.
E-ulbar, Temple of, 7, 22.
Eunuchs, 100, 324.
Euphrates, 32.
Euyuk, 192.
Ex votos, 312, 336.
"Exaltation of the Flower," bas-relief of, 160.
Ezekiel, 119.
E-zida, Temple of, 6, 73, 78.
- Façade at Abu Shahrein, 18.**
 at Warka, 18.
 on bas-relief from Assurbanipal's palace, 62.
- Façade of temple of god Haldia, 76, 77.**
 of Assyrian palaces, 92, 93.
 at Persepolis and Susa, 156, 157.
- Ferashbad, 158**
Figurines in terra-cotta,—
 from Chaldæa, 40, 41.
 in Assyrian tombs, 51
 from Khorsabad, 121, 122
 from Babylon, 124, 125.
 from Phœnicia and Cyprus, 277-81.
- Fire-altars, 173.**
Firuzabad, 158, 159.
Flints, worked, 303.
Floral designs—
 on Babylonian tiles, 19, 118.
- Flowers, treatment of, in Assyrian sculpture, 110.**
Fly-flaps, 135, 164, 324.
Fortress,—
 Assyrian representation of, 110.
- Foundation-cylinder, 21, 22.**
Friezes,—
 from Susa, 168-71.
- Fringes,—**
 in Chaldæan drapery, 28, 36, 37, 41, 202.
 in Assyrian drapery, 105, 106.
 in Elamite drapery, 332.
- Frœhner, M., on the glass vase of Sargon, 286.**
Furniture,—
 Chaldæan, 43.
 Assyrian, 134-6.
 of Jewish temple, 223-7.
- Gabr-i-Madar-i-Soleiman, 175.**
Gates,—
 of Assyrian fortresses, 82-4.
 of Balawat, 126, 127.
 of Jewish Temple, 215-17.
- Gaulois, 243.**
Gaumates, 179.

- Genesis,—
 on bricks at Babel, 4.
 on the "Great City," 81.
- Genii,—
 on the "Caillou Michaux," 33.
 wear tiara with horns, 36.
 on Chaldæan cylindrical
 seals, 45.
 before temple of Haldia, 77.
 on façades of Assyrian pa-
 laces, 92-96.
 identified with cherubim, 93,
 224.
 in Persia, 161.
 animal's feet and tail, 317.
- Genseric, 227.
- Gestures,—
 in Assyrian bas-reliefs, 102,
 103.
 Chaldæan attitude of prayer,
 331, 332.
- Ghiaur-Kalesi, 199.
- Giants, 307.
- Giganteja, 243.
- Glass, 283-8.
 vase of Sargon, 285.
 transparent, invention of, by
 Phœnicians, 283.
 opaque, origin of, in Egypt,
 284.
 manufacture of, at Tyre and
 Sidon, 287.
- Glazed statuettes in Phœnicia,
 278.
 sandstone, 314, head-dress,
 334.
- Glazed tiles,—
 in Chaldæa, 19.
 in Assyria, 116-20.
 in Persia, 167-72.
 in Susa, 314.
- Gold—
 disks as money, 335.
 rings, 335.
 studs, 328, 334.
 statuette, 331.
 filigree, 331.
- Gold (*contd.*),—
 settings for gems, 337.
 pendants, 337.
 "Golden Gate" of Jewish
 Temple, 217.
- Golgoi, 242.
- Gophna, 235.
- Gozo, 243.
- Græco-Parthian kings, 12.
 "Great City," The, 81.
- Greek—
 artists in Persia, 148, 160.
 influence in Cypriote art, 272,
 273, 276, 281.
 influence in Jewish art, 234,
 236.
- Griffin's head, 336.
- Gudea, 309.
 palace of, at Tello, 3, 8-20.
 cones bearing name of, 38.
 statues of, 26-9.
 plan of fortress upon statue
 of, 81.
 inscriptions upon statues of,
 112.
- Gypsum, 53.
- Hadrian, 249.
- Hadrumetum, 268.
- Hæmatite, 44, 334.
- Hagiar Kim, 224.
- Hair,—
 shaved in Chaldæan statu-
 ettes, 36.
 treatment of, in Assyrian
 sculpture, 100.
 in Persian art, 160, 170.
 in Hittite art, 188, 190, 193,
 194, 196, 200.
 in Phœnician art, 262.
 in Cypriote art, 270, 273, 274.
 treatment of, in Elamite art,
 329.
 shaved in Elamite statuettes,
 331.
- Haldia, the god, 76, 77.
- Hamath, 185.

- Hammurabi, 44, 309, 323.
 Hanbury, Col., Chaldæan sword
 belonging to, 37.
 Haram esh-Sherif, 211.
 Harbours of Carthage, 250.
 of Tyre and Sidon, 250.
 of Thapsus, 252.
 of Utica, 252.
 Hareem of Chaldæan palace, 16.
 of Assyrian palace, 69, 70.
 of Solomon's palace, 232.
 Harness, Assyrian, 141.
 Phœnician, 277.
 Head-dress,—
 Chaldæan, 23, 26, 28, 40, 41,
 321.
 of gods and genii, 36, 200, 317.
 Assyrian, 101, 143.
 Median, 146.
 Persian, 170, 179, 181.
 Hittite, 188, 191, 195, 198, 200.
 Cypriote, 270, 271, 273.
 Hebron, 232, 233, 234.
 "Heit-el-Maghreby," 213.
 Helmets, Assyrian, 128.
 Heracles, 274.
 Herod, 208, 209, 210, 211, 212,
 214, 223.
 Herodian masonry, 212, 213,
 215, 216, 232, 234.
 Herodotus,—
 on use of bricks at Babylon, 5.
 on temple of Bel at Babylon,
 73, 74, 77, 78.
 on fortress of Ecbatana, 74, 75.
 on the royal city of Babylon,
 80.
 on figures of "Sesostris" in
 Ionia, 112, 201.
 on absence of temples and
 statues in Persia, 172.
 on treatment of dead by
 Persians, 175.
 on "*persis*," 179.
 Heuzey, M.,—
 on sculpture at Tello, 23.
 on eagle and lion tablet, 24.
 Heuzey, M. (*contd.*),—
 on "*kaunakes*," 32, 41.
 on Assyrian statuettes, 121.
 on statuette of the "Divine
 Mother," 124.
 on archaic school of art in
 Thessaly, 160.
 Hezekiah, 233.
 Hieroglyphs, Elamite, 305.
 "High places," 231, 239.
 Hinnom, valley of, 205.
 Hiram, 206.
 Hiram-Abi, 226.
 Hit, 5. *Aut. 2: 18-203*
 Holy of Holies, 222, 224, 225.
 Holy Place, 222, 224, 226.
 Horn, bronze, discovered at
 Tello, 37.
 Horns,—
 as ornaments of head-dress,
 23, 26, 36, 200, 317, 321.
 of bronze statuette, 35.
 bull's, alabaster, 336.
 Horses in Assyrian sculpture,
 108, 141.
 Houses, Phœnician and Cy-
 priote, 247, 248.
 Humann, M., 201.
 Humbaba, 308.
 Hyrcanus, palace of, 232.
 Iasili-Kaia, 191, 193-8.
 Ibn Tûlûn, mosque of, 174.
 Ibriz, 200.
 Iconic statues, 265, 274.
 Idalion, 259.
 Ilu, the god, 172 (note).
 "Immortals," the, 165, 170.
 Inscriptions on figures on bas-
 reliefs, 112.
 Ionia, 112.
 Ionic capital, 12, 43, 64.
 Iron, 43, 125.
 Istar, the goddess, 49, 124, 125,
 188, 202.
 Ivory, 137, 138, 335.

- Izdubar,—
 on Chaldæan cylindrical seals, 46, 47.
 on Assyrian bas-reliefs, 93.
 statuettes of, 121, 122.
 in Persian art, 162.
 compared with colossus of Amathus, 271.
- Jachin, columns so called, 227.
- James, Saint, tomb of, 234.
- Jasper, 335.
- Jebel-Musa, 230.
- Jehoshaphat, tomb of, 234.
- Jerablus, 185.
- Jerusalem,—
 extent of, 205.
 glass vase found at, 288.
- Jetty of Thapsus, 252.
- Jewellery, Achæmenian, 336.
- Jews in Assyrian sculpture, 103.
- Jifneh, 235.
- Joints, treatment of, in Chaldæan seal-engraving, 45.
- Jonah, Book of, on size of Nineveh, 81.
- Joshua, tomb of, 235.
- Jotham, 232.
- Jur, 173, 174.
- Justinian, 227.
- Kadesh, 185.
- Kalaba, 199.
- Kalah Shergat, 5, 31, 111.
- Karamles, 51.
- Karibu-sa-Susinak, 308.
- Kasr, mound of the, 52.
- "Kaunakes," 32, 41, 42.
- Kebûr-el-Melûk, 234.
- Kedron, valley of, 205, 212, 221, 232.
- Kerbela, 50.
- Khan,—
 of palace at Tello, 17.
 of palace at Khorsabad, 69.
- Khorsabad, 51, 52, 54, 55, 63, 66-72, 73, 74, 75, 79, 83, 86, 93, 106, 111, 114, 131, 142, 149, 324.
- "Kirubi" identified with cherubim, 93.
- combination of various elements in, 95.
- modification of, in Persian art, 183.
- Kis, 317, 326.
- "Klaft," 271.
- Kouyunjik, 51, 52, 56, 72, 73, 111.
- Kubbet es-Sakhra, 208.
- Kudur, 308.
- Kudurmapuk, 36.
- Kudur-Nakhunta, 309, 310.
- Kudurru, 309, 311, 325.
- Kurigalzu, 21, 309.
- Lachish, 103, 136.
- Lagas, 3 (note).
- Lapis-lazuli, 142.
- Larnaca, 270.
- Larsa, 2, 21.
- Layard, Sir A. H., 62, 68, 72, 123, 300.
- Leather, working in, among Assyrians, 141.
- Lebanon, 60, 78.
- Limestone, 23, 52, 153.
- Lion, 304, 307.
 head in gold filigree, 331.
- Lioness in Assyrian bas-relief, 107.
- Lions, winged, 92, 94.
 in Hittite art, 186, 187, 189.
 in Assyrian art, 107, 108.
- Loftus, Mr., 3, 10, 18, 21, 40, 114.
- Lotus,—
 in bas-reliefs, 110.
 on ivory plaque from Assyria, 137.
 columns imitating stalks of, 11.
 on sculptured threshold, 110.

- Louvre, 26, 303, 313.
 Lozenge ornament in Chaldæa, 19, 45.
 Lulubi, people of, 319.
 Lycian tombs, compared with Persian, 177.
 Lydian method of building, 149.
- "Maabed," 239-41.
 Maccabees, tomb of the, 234.
 Temple, in time of the, 210.
 Machicolations, 82.
 Machpelah, 233.
 Malta, 244.
 Malthaiyah, 187.
 Manasseh, 209, 232.
 Mandane, tomb of, 175.
 Manistu-Irba, 316.
 Marash,—
 lion at, 186.
 basalt stela at, 190.
 Marble, 44.
 Marduk-nadin-akhi, 33, 34, 41.
 Marginal drafting,—
 in Persian masonry, 149.
 in Jewish masonry, 213, 232, 234.
 Matting used in brickwork, 5.
 to cover the roofs, 15, 242.
 M. de Morgan, 301, *et seq.*
 on Naram-Sin, 320, 321.
 Mecca, mosque of, 241.
 Medain Salih, 235.
 Median art, 146.
 Mehdiā, 260.
 Melisihu, 325.
 Memnon, 300.
 Menant,—
 on cylindrical seal of Sargon I., 47.
 on seals from Uruk, 48.
 on representation of human sacrifices, 49.
 Meshed-Murgab, 147.
 Mesopotamia,—
 want of stone and timber in, 3, 4.
- Mesopotamia (*contd.*),—
 quality of clay in, 4, 39.
 quantity of rain in, 6.
 Metals in Assyria, 125-34.
 Metellus Scipio, 141.
 Michaux, the Caillou Michaux, 33, 34, 325.
 "Mighzal," 254.
 Miletus, 28.
 Minyeh, 231.
 Moab, 230, 231.
 Models of houses from Cyprus, 248.
 Money, probable use of metal disks, 336.
 Monolith of Siloam, 235.
 Moriah, Mount, 205, 206, 207, 208.
 Mortar used in Assyria, 54.
 used in Elam, 314.
 Moulds, Hittite, 202.
 Mugheir, 2, 3, 6, 8, 14, 20, 21, 38, 51, 73, 75.
 Müntz, M., on Babylonian embroidery, 140.
 Musasir, 76.
 Muscles, treatment of, in Assyrian art, 100.
 Myra, 177.
 Mythological figures in Chaldæan art, 33.
- Nabonidus,—
 restoration of buildings by, 7, 22.
 foundation-cylinder of, 21, 22.
 architecture of time of, 52.
 Nabopolassar, 80.
 Nabu-ablu-iddin,—
 stela of, 12, 42.
 "Naharaim," 32.
 Nahum, on brick-making, 4.
 Nakhsh-i-Rustam, 147, 173, 176, 179.
 Name, stamped upon bricks, 5, 316.

- Nana, the goddess, 7, 309, 310, 333.
- Napir-Asu, Queen, 330.
- Naram-Sin, 308, 318.
stela, 319 *et seq.*
- Nazi-Maruttas, 325.
- Nebi Yunus, 51.
- Nebo, the god, 7, 86.
- Nebuchadnezzar, 41, 79, 119, 209, 226.
bricks bearing name of, 5.
architecture of time of, 52.
brings cedars from Lebanon, 60, 78.
builds Tower of the Seven Lights, 73.
restores E-saggil, 78.
restores E-zida, 78.
builds walls of Babylon, 80.
- Nebuzar-adan, 209.
- Necropolis,—
at Mugheir, 14, 20, 21, 38.
at Warka, 38.
at Marath, 253-5.
at Sidon, 255, 256.
at Dali, 259.
at Amathus, 260.
at Mehdiā, 260.
at Thina, 261.
at Tyre, 254.
at Adlun, 254.
at Gebal, 256.
at Caralis, 260.
at Tharras, 260.
at Jebel Kawi, 261
- Negritic type, 322
- Nehemiah, 232
- Nejef, 50
- Nero, 141, 211.
- Nicanor, Gate of, 220.
- Nimroud, 51, 52, 61, 62, 72, 111.
- Nineveh,—
walls of, 6.
vaulting at, 13.
extent of, 81.
- Nin Girsu, 10.
- Ninus, 119.
- Numeration, Elamite, 306.
- Nymphio, 201.
- Oannes, 2.
- Onyx, 44.
- Ophel, hill of, 205, 210, 231, 232.
- Oppert, 46, 79, 81.
- Orientation of Chaldæa buildings, 8.
of Assyrian buildings, 67
- Ornaments, 142, 143.
- Ourdeys, 82.
- Ovoid gems, 45.
- Painted bricks,—
Chaldæan, 19.
Assyrian, 74, 116-20.
Persian, 167-72.
- Painting,—
on façades of Chaldæan palace, 18, 19.
on stucco in Assyrian palaces, 56, 114, 115.
on Assyrian bas-reliefs, 115, 116.
on Assyrian vases, 122.
on walls of Persian buildings, 159, 172.
in Cypriote pottery, 280.
- Palace,—
of Gudea at Tello, 8-22.
of Sargon at Khorsabad, 66-72.
of Cyrus at Madar-i-Soleiman, 148-50.
of Darius at Nakhsh-i-Rustam, 150.
of Xerxes, 150-8.
of Artaxerxes, 157.
of Solomon, 231.
- Palestrina, 290, 293.
- Palm-wood, use of, in roofing houses, 15, 60, 158.
pillars of, 63.
- Paphos, 241, 242.
- Parthians, 12, 56.

- Partitions of rooms, 13, 54, 55.
 Pasargadæ, 147, 148, 150, 151, 160.
 Passages, vaulted, at Tello, 14.
 Pataëci, 264.
 Pateræ, 127, 128, 289, 290.
 Patesi, 8, 46, 81, 308.
 Pausanias, on size of Babylon, 79.
 Pediments, 76, 77, 175, 235, 256, 267.
 Pendants, 336, 337.
 Pendentives, 159 (note).
 Perrot,—
 on Assyrian voussairs, 58, 59.
 on gates of Balawat, 126, 127.
 on Hittite sphinx, 193.
 on Hittite bas-reliefs, 199.
 on Cypriote terra-cottas, 280.
 Persepolis, 8, 147, 150, 162.
 Persepolitan capital, 153-6.
 Persis, 179.
 Perspective, ignorance of laws of, among Assyrians, 98, 110.
 Philostratus, 140.
 Phœnician bronzes in Assyria, 129.
 ivories in Assyria, 138.
 artists employed in Jewish Temple, 224.
 Pilasters, 9, 61, 77.
 Pillars, 10, 11, 63.
 (see COLUMNS).
 Pine-cone in Assyrian art, 111, 139.
 Pipes for drainage, 20.
 Pivot of door, 17, 18.
 Place, M. V., 54, 55, 61, 66, 117.
 Plan of Chaldæan fortress, 29, 81.
 Plaque,—
 of bronze, 131-4.
 of ivory, 137, 138.
 Plaster, use of, in Chaldæa, 11, 18.
 in Assyria, 56, 114, 115.
 in Persia, 172
- Platforms of buildings,—
 in Chaldæa, 8.
 in Assyria, 52, 53, 67, 68.
 in Persia, 149-52.
 in Judæa, 207, 208.
 in Susa, 314.
 Pliny,—
 on Babylonian embroidery, 140.
 on Telephanes, 148.
 on invention of glass, 283.
 Porphyry, 44, 153.
 Position-marks on masonry, 149.
 on bricks, 117, 118.
 Pottery, inferiority of, in Chaldæa, 38, 39.
 prehistoric, Elam, 304.
 Præneste, patera from, 289-93.
 Prehistoric remains, Susa, 303.
 Progress of art in Assyria, 111-13.
 in Cyprus, 270-3.
 Pshent, 263-71.
 Pteria, 191.
 Pudil, 38.
 Pygmæus, the god, 259, 276, 279.
- Rammanu, the god, 22, 144.
 Rammanu-nirari, 38, 92.
 Ras el-Ain, 249.
 Rassam, Mr. H., 72.
 Rawlinson, Sir H., 72, 300.
 Renan, M. E., 263, 265.
 Reseph, the god, 294.
 Rings, 335.
 Robinson's Arch, 214.
 Rule, graduated, 29.
- Sacrifice, human, 49.
 Sadambaal, the god, 243.
 Sagasaltias, 22.
 Sakhra, 208.
 Sakkanak, 308.
 Samas, the god, 2, 22, 323, 324.
 shrine of, 12, 42, 43, 64.

- Samas-sum-ukin, 80.
 Samsi-Rammanu III., 88, 92.
 Sandals, 322.
 Sandstone, 304, 317.
 Sarcophagi, Phœnician, 256-9.
 Sargani (see SARGON I.).
 Sargani-sar ali, 308.
 Sargon I., 47, 48.
 Sargon II., 53, 57, 90, 61, 66,
 76, 92, 93, 96, 106, 113, 116,
 117, 270, 285.
 Sarvistan, 158, 159.
 Sarzec, M. de, 2, 10.
 Sassanian buildings, 56, 63,
 158, 159.
 Saulcy, F. de, 235.
 Scheil, Père V., 301.
 on inscriptions, 305, 306, 319.
 Schrader, E., 81.
 Scipio Africanus, 266.
 Seals,—
 Chaldæan, 44-9.
 Assyrian, 143-5.
 Median, 146.
 Persian, 180-3.
 Hittite, 203.
 Jewish, 230.
 Phœnician, 294-8.
 Elamite, 304, 335.
 Selamlik, 16.
 Seleucids, 210, 234.
 Semiramis, 76, 80, 119.
 Senkereh, 2, 21.
 Sennacherib, 60, 66, 67, 72, 92,
 93, 103, 113, 139 (note).
 Sepharvaim, 2, 42.
 Sepulchral architecture in
 Assyria, 50.
 towers in Persia, 14
 Seraglio, 16, 69.
 Sesostris, 112, 201.
 Set, the god, 294.
 Sewage, disposal of, 20.
 Shalmaneser III., 72, 89, 126,
 "Sharur," 6.
 Shat el-Hai, 3.
 "Shenti," 264.
 Shew-bread, 226.
 Shilkhak in Shushinak, 309.
 Shushinak, Temple of, 314,
 330, 331, 336.
 Shutruk-Nakhunta, 309, 314,
 315, 319, 323, 336.
 Sidon, 247, 250, 255, 289.
 Sidur canal, 308.
 Siloam, 232, 235.
 Silver, use of,—
 in Chaldæa and Assyria, 21.
 in Elam, statuette, 332.
 mask, repoussé, 333.
 studs, 334.
 rings, 335.
 disks, 336.
 Sin, the god, 16.
 Sinjerli, 188.
 Sippara, 2, 323.
 Sirens, bronze, 129-30.
 Sirpurla, 3.
 Sivan, 4.
 Smith, G., 72.
 Sockets for pivot of door, 17,
 18, 308.
 Solomon, 205, 206, 208, 209,
 210, 211, 215, 219, 221, 224,
 232, 235.
 palace of, 231-2.
 porch of, 209, 211.
 Solus, 258.
 Sophia, church of Saint, 56,
 159 (note).
 Sphinxes,—
 Persian, 183.
 Hittite, 192, 193.
 Phœnician, 263.
 Stables, 17, 69, 70, 136.
 Staged towers, 15, 16, 72-6,
 174, 314.
 Staircases, 8, 67, 151, 152.
 Standard, Assyrian, 133, 134.
 State saloon in Chaldæan
 palace, 17.
 Statues,—
 from Tello, 26-30.
 of Assur-nasir-pal, 86.

- Statues** (*contd.*),—
 caryatid, 86, 87.
 iconic, in Cyprus, 265.
 captured by Scipio at Carthage, 266.
 colossal, in Cyprus, 270-72.
 of priest with dove, 273.
 bronze from Elam, 330.
- Statuettes**,—
 bronze, from Chaldæa, 35-8.
 of canephoros, 36, 37.
 kneeling, with cone, 36.
 of figure standing upon lion, 37, 38.
 terra-cotta, from Warka, 40.
 alabaster, from Chaldæa, 42.
 terra-cotta form Khorsabad, 121, 122.
 of Izdubar, 122.
 of Istar, 123-25.
 terra-cotta from Phœnicia and Cyprus, 277-82.
 of Divine Mother, 124, 281.
 from Elam, bronze, 330.
 gold, 332.
 silver, 332.
 ivory, 335.
- Steatite**, 43, 123.
- Stela**,—
 the "Vulture Stela," 24-6, 321.
 of Samsi-Rammanu, 88.
 of Assurbanipal, as canephoros, 89.
 Hittite, from Birejik, 187.
 votive, from Carthage, 266.
 Chaldæan from Elam, 317.
 of Manishtu Irba, 316.
 of Naram-Sin, 319 *et seq.*
- Stone**,—
 want of, in Mesopotamia, 4.
 staircase of, at Abu Shahrein, 8.
 scanty use of, in Assyria, 50, 65.
 facing of, at Khorsabad, 52, 53.
 use of, in Persia, 149.
 want of, in Persia, 326.
- Stool**, 135.
- Strabo**,—
 on use of vault in Babylonia, 15, 56.
 on use of palmwood pillars at Babylon, 63.
 on height of temple of Bel, 73.
 on tomb of Cyrus, 177.
 on rites of Cappadocian Asartate, 197.
- Stucco**, 18, 114, 172.
- Stuffs manufactured in Chaldæa**, 41.
 in Assyria, 105, 138, 139.
- Stylus**, 308, 324.
- Sukkal-mah**, 309.
- Sulci**, 282.
- Sumerian language**, 316.
- Susa**, 147, 168.
 Mission in, 299 *et seq.*
- Susiana**, 158.
- Sword**, Chaldæan, 27.
- Tablet, Eagle and Lion**, 24.
- Tablets**,—
 votive, 21.
 clay, Elam, 305.
- Tabnit**, 257.
- Tacitus**, on temple of Paphos, 242.
- Takht-i-Jemshid**, 152, 179.
- Takht-i-madar-i-Soleiman**, 149.
- Talisman**, 17, 230.
- Tanit**, the goddess, 246, 263, 267, 268, 269.
- Tapestry**, 138-40.
- Tarkudimme**, 203.
- Taylor, J. E.**, 3, 8, 9, 18, 76.
- Telephanes of Phocæa**, 148.
- Tell Amran**, 52.
- Tello**, 2, 3, 5, 8, 9, 14, 18, 20, 23, 32, 73, 81, 85, 315, 317, 318.
- Tells**, 2, 10, 300.
- Telmessus**, 177.
- Temple of the Great Light**, 6.
 of E-anna, 310.

- Temple of Didyma, 313.
 of Shushinak, 314, 330, 331,
 336.
 Tent, 136.
 Terrace (see PLATFORM).
 Terra-cotta, 38, 39-41, 51, 121-5,
 248, 277.
 Thapsus, 252.
 Tharras, 260.
 Thenæ (see THINA).
 Thessaly, archaic school of art
 in 160.
 Thina, 261.
 Thresholds, 110, 111.
 Throne,—
 of Sennacherib, 136.
 of Darius, 165.
 Thyatira, 202.
 Tiara,—
 on Tello bas-relief, 23.
 on Vulture Stela, 26.
 on Marduk-nadin-akhi, 41.
 of Sargon, 106.
 on Median cylinder, 146.
 of Persian human-headed
 bulls, 167.
 of Darius, 181.
 on stela from Birejik, 188.
 of Hittite deity, 195.
 on Elamite statuette, 332.
 Tiglath-Pileser, 92.
 Tigris, the, 32.
 Timber, use of, in Assyria, 60,
 61.
 "Timmennu," 21, 22.
 Titus, arch of, 226.
 Tomb,—
 of Mandane, 175.
 of Cambyses, I., 176, 177.
 of Cyrus, 177.
 of Darius, 179.
 Tombs,—
 at Mugheir, 20, 21.
 at Warka, 38.
 in Assyria, 50.
 of Achæmenids, 175-80.
 at Marath, 253-55.
- Tombs (*contd.*),—
 at Sidon, 255, 256.
 at Dali, 259.
 at Amathus, 260.
 at Mehdiâ, 260.
 at Thina, 261.
 at Tyre, 254.
 at Adlun, 254.
 at Gebal, 256.
 at Caralis, 260.
 at Tharras, 260.
 at Jebel Kawi, 261.
 Totems, with Babylonian
 deities, 325.
 Tower,—
 of Seven Lights, 73.
 staged (see ZIKKURAT).
 of Jur, 173, 174.
 Trees, Treatment of, in As-
 syrian art, 110.
 Trinity, Phœnician, 268.
 Triple gate of Jewish Temple,
 217.
 Tulip in Assyrian decorative
 design, 110.
 Tunnel of Siloam, 232, 233.
 Turanians, 302.
 Types of human figure in As-
 syrian art, 100-2.
 in Chaldæan art, 321, 322.
 in Elamite art, 329, 333.
 Tyre, 249, 287.
 Tyropœon, valley of, 205, 212,
 214, 219.
- Umalnaru, 46.
 Umbrella,—
 Assyrian, 135.
 Persian, 164.
 Umm el-Awamid, 263.
 Ur, 2, 48, 75.
 Uræus,—
 on ivory plaque from As-
 syria, 137.
 in head-dress of Cyrus, 161.
 in Phœnician sculpture, 240,
 263.

- Uraeus (*contd.*),—
 on stela of Hadrumetum,
 369.
- Ur-Bau, 38.
- Urim and Thummim, 230.
- Ur-iti-Adad, 308.
- Ur-Nina, 24.
- Uruk, 2, 48, 309.
- Utica, 252.
- Vandals, seizure of treasures
 of Jewish temple by, 227.
- Vases,—
 Assyrian, 122, 123.
 Chaldæan, 39.
 Elamite, 304, 307, 335.
- Vault,—
 at Tello, 14.
 at Mugheir, 14.
 at Babylon in time of Strabo,
 15.
 at Khorsabad, 55, 57, 58, 59.
 in drain at Nimroud, 57.
 in Persia, 158, 159.
- Veil in Jewish Temple, 224.
- Vermilion, use of, in Assyrian
 art, 116, 119.
- Vogüé, M. de, 205.
 on platform of Jewish Tem-
 ple, 208.
 on Herod's restoration, 211.
 on Golden Gate, 217 (note).
 on altar of burnt offerings,
 221.
 on chambers attached to
 Temple, 222.
 on appearance of Temple,
 222, 223.
 on cherubim, 225.
 on columns before Temple,
 227.
- Vousoirs, 55, 58, 59.
 "Vulture Stela," 24-6, 321.
- Walls,—
 of Chaldæan palace, 12, 13.
 of Assyrian palace, 54-6.
 of Babylon, 79, 80.
 of Nineveh, 81.
 of Khorsabad, 79.
 of Jewish Temple, 212-14.
 of Jerusalem, 232.
 of Banias, 246.
 of Carthage, 247.
 of Eryx, 247.
 of Elam, 314.
- Warka, 2, 9, 18, 40, 63, 114.
- Weapons,—
 Chaldæan, 37, 38.
 Assyrian, 129, 137.
- Windows of Persian palaces,
 152.
- Women, treatment of, in As-
 syrian art, 101.
- Wood,—
 want of, in Chaldæa, 4.
 use of, in Assyria, 60, 134-7.
- Woodwork, carved, 134-7.
- Wuswas, 9, 10, 114.
- Xanthus, 177.
- Xerxes, 148, 150, 152, 154, 164.
- Zacharias, tomb of 234.
- Zaghouan, 249.
- Zarpanit, the goddess, 78.
- Zerubbabel, 210, 214.
- Zikkurat,—
 in Chaldæa, 15, 16.
 in Assyria, 72-6.
 in Persia, 174.
 in Elam, 314.

H. GREVEL & CO.'S

Publications.

ART WORKS.

Art.

An Illustrated Quarterly Magazine of Ancient and Modern Art. Edited by J. E. BUSCHMANN. New Series. Vol. I., Part I., containing about 120 pages, including a great number of full-page and other illustrations. Each Part 3s. net. Annual Subscription, post free 14s.

The Art Decorator.

Designs in Colours for Art Workers. Seventeenth year of Publication. In Monthly Parts of 1s. each, containing 5 Coloured Plates. Folio. Annual Subscription, 15s. post free.

"Of inestimable use to every student of art and professional decorator."—*Standard*.

"To the amateur artist in search of ideas and suggestions it is simply indispensable."—*Queen*.

Prof. Ernst Brücke. The Human Figure, its Beauties and Defects.

With 29 Illustrations by HERMAN PARR. Edited, with a Preface, by W. ANDERSON, late Professor of Anatomy to the Royal Academy of Arts, London. New and Cheaper Edition. Crown 8vo. Cloth. 5s.

"It is long since we have been called upon to review a more thorough, learned, or interesting book upon an attractive and important subject."—*Athenaeum*.

Costumes of All Nations.

119 Coloured Plates, containing over 1,000 Costume Pictures, designed by the first Munich Artists. New Edition. Small Folio. Cloth. £1 5s. net.

Engraving and Etching.

A Handbook for the Student and the Print Collector. By F. LIPPMANN, Keeper of the Print Room, Berlin Museum. Translated by MARTIN HARDIE, South Kensington Museum. With 134 Illustrations. Demy 8vo. Cloth. 7s. 6d. net.

ART WORKS — *continued.***Famous Art Cities.**

A series of Illustrated Monographs on the History of the Great Art Centres of the World.

Vol. I.

Pompeii, by Prof. R. ENGELMANN. Translated by TALFOURD ELY. With 145 Illustrations. Royal 8vo. Cloth. 4s. net.

Vol. II.

Venice, by G. PAULI. Translated by P. G. KONODY. With 142 Illustrations. Royal 8vo. Cloth. 4s. net.

Vol. III.

Nuremberg; Development of its Art to end of the 18th Century, by P. J. RÉE. Translated by G. H. PALMER. With 163 Illustrations. Royal 8vo. Cloth, gilt top. 4s. net.

Vol. IV.

Florence, by ADOLF PHILIPPI. Translated by P. G. KONODY. With 170 Illustrations. Royal 8vo. Cloth. 4s. net.

These charming Volumes, as regards excellence of taste and wealth of illustration, will compare favourably with the most expensive works which have been published on the same subjects. Taken together they will form a complete history of the great Art Centres, but each volume may be purchased separately. Art students and amateurs will be sure to welcome these beautiful monographs, as they will serve a double purpose. They will not only be a trustworthy guide to the history and works of art of the cities to which they refer, but also a permanent reminder and a perpetual souvenir of the objects seen and admired.

ART WORKS—*continued.*

Ernest Lefébure. Embroidery and Lace.

Their Manufacture and History from the remotest Antiquity to the present day. Translated and enlarged by ALAN S. COLE, C.B. With over 150 Woodcuts. New and cheaper edition, revised. Crown 8vo. Cloth. 7s. 6d.

"A book which is not only a comprehensive, well-arranged, and trustworthy history of a delightful art, but a book which is pleasant to see and pleasant to read, well written and well edited. Its manner of production does much credit to the publishers."—*Academy.*

Monographs on Artists.

Edited and written jointly with other authors by H. KNACKFUSS, Professor at the Royal Academy of Arts, Cassel. Price per Volume, richly illustrated and tastefully bound, large 8vo, with gilt top, 4s. net; 4s. 6d. post free.

These charming Volumes, unique in appearance and illustration, will form, when complete, a history of the great periods of Art, but each volume is complete in itself, and may be obtained separately.

I.

Raphael. With 128 Illustrations. 4s. net.

II.

Holbein. With 151 Illustrations. 4s. net.

III.

Rembrandt. With 159 Illustrations. 4s. net.

IV.

Van Dyck. With 55 Illustrations. 4s. net.

V.

Dürer. With 134 Illustrations. 4s. net.

VI.

Botticelli. With 90 Illustrations. 4s. net.

VII.

Leonardo da Vinci. With 128 Illustrations. 4s. net.

VIII.

Donatello. With 141 Illustrations. 4s. net.

IX.

Rubens. With 122 Illustrations. 4s. net.

"The series, without question, is one of the best now being published."—*Daily Chronicle.*

ART WORKS—*continued.*

The Practical Art Gallery.

A Monthly Magazine of Examples of Fine and Applied Art for Art Workers and Collectors. Edited by Dr. GEORGE HIRTH. With 144 Plates per annum. 4to. Each Part 1s. net. Annual Subscription. In 12 Monthly Parts. 15s. post free.

Velazquez.

An Album of 48 Plates. With a Biographical Introduction and a Description of the Pictures after Prof. C. JUSTI. 4to. Cloth. 10s. 6d. net.

Dr. L. Volkmann. Iconografia Dantesca.

The Pictorial Representations of the "Divine Comedy." With 17 Plates from Miniatures, Prints, and Designs, and numerous Vignettes, Initials, Head and Tail pieces. Printed on superfine paper, limited to 300 numbered copies. Imp. 8vo. Cloth, gilt top. £1 1s. net.

ARHÆOLOGICAL WORKS.

Prof. E. Babelon. Manual of Oriental Antiquities,

Including the Architecture, Sculpture, and Industrial Arts of Chaldæa, Assyria, Persia, Syria, Judæa, Phœnicia and Carthage. By ERNEST BABELON, Librarian of the Department of Medals and Antiques in the Bibliothèque Nationale, Paris. With 241 Illustrations. New Edition, with an additional Chapter on the Recent Finds at Susa. Crown 8vo. Cloth extra, gilt top, 7s. 6d. net.

"The 'Manual of Oriental Antiquities,' which takes deservedly a high position both for the general accuracy of its statements and excellent character of its illustrations."—*Athenæum*.

"M. Babelon's work has already won such a high measure of praise from the students of Oriental archæology that its place is assured among modern authorities on the art and culture of the ancient civilised nations of Western Asia."—*Academy*.

"The quantity of information contained in one small volume is wonderful, embracing the art history of Chaldæa, Assyria, Persia, Syria, Judæa, Phœnicia, and Carthage. By the study of the illustrations alone, a clear idea can be gained of the different characteristics of these nations."—*Speciator*.

ARHÆOLOGICAL WORKS—*continued.*

Prof. Jean Capart. Primitive Art in Egypt.

By JEAN CAPART, Keeper of the Egyptian Antiquities of the Royal Museums, Brussels ; Lecturer at the University of Liège. Translated from the Specially Revised Original Edition, by A. S. GRIFFITH. One Volume, with 213 Illustrations, 30 of which are new, Royal 8vo. Cloth extra, price 16s. net.

- I. PRELIMINARY CONSIDERATIONS.
- II. PERSONAL ADORNMENT.
- III. ORNAMENTAL AND DECORATIVE ART.
- IV. SCULPTURE AND PAINTING.
- V. THE EARLIEST PHARAONIC REMAINS.
- VI. DANCING, MUSIC AND POETRY.
- VII. CONCLUSIONS, INDEX.

M. CAPART deals with the primitive civilization of Egypt. One chapter he devotes to its junction with the earliest Pharaonic civilization and the recently discovered remains of that period. The book is fascinating in its description of art and culture as they existed in the Nile Valley six or seven thousand years ago. M. CAPART has produced a work which introduces us to a new world of interest, while the anthropologist and ethnologist will find material collected and conclusions arrived at which are of the greatest interest and importance.

"M. Capart has chosen a fascinating subject, which he has treated in an interesting and lucid manner. At the same time he gives full references for every statement he makes ; thus, while the book will stand on its own merits, it also affords a valuable guide to the whole literature of the subject."—*Daily News*.

"It is gratifying to find such a treatise as this made easily accessible to all in the excellent English translation."—*Glasgow Herald*.

"Valuable to the students of both Art and Egyptology."—*Tablet*.

ARCHÆOLOGICAL WORKS—*continued.*

Maxime Collignon. Manual of Mythology in Relation to Greek Art.

Translated and enlarged by JANE E. HARRISON, Author of "Myths of the Odyssey," "Introductory Studies in Greek Art," etc. With 140 Illustrations. New and cheaper edition, revised. Crown 8vo. Cloth. 7s. 6d.

"This is a good book. It fills a gap in our literature, doing for Greek mythology much the same service which Mrs. Jamieson rendered to Christian hagiology."—*Academy*.

Prof. Charles Diehl. Excursions to Greece to recently explored Sites of Classical Interest.

Mycenæ, Tiryns, Dodona, Delos, Athens, Olympia, Eleusis, Epidauros, Tanagra; by CHARLES DIEHL, Professor at the University of Nancy. Translated by EMMA R. PERKINS. Illustrated. Crown 8vo. Cloth. 7s. 6d.

"It would be difficult to point to a single volume in English which takes so comprehensive a survey or deals with its materials in a manner at once so scientific and so popular as this work of M. Diehl."—*Times*.

Talfourd Ely. Olympos: Tales of the Gods of Greece and Rome.

With 47 Woodcuts and 6 Full-page Photographic Plates. Crown 8vo. Cloth. 7s. 6d.

"One feature of the book should be especially useful to young readers. Zeus and Jupiter, Hera and Juno, Poseidon and Neptune, and the rest, have parallel but distinct accounts given to them, so that the difference of origin of Greek and Roman deities is made clear."—*St. James's Gazette*.

"Makes a capital gift-book"—*Scotsman*.

The Demotic Magical Papyrus of London and Leiden.

Edited by F. LL. GRIFFITH (Reader in Egyptology in the University of Oxford, Corresponding Member of the Academy of Sciences at Berlin), and SIR HERBERT THOMPSON, Bart. Vol. I. 210 pp. Royal 8vo. Cloth. (Limited Edition.) 10s. 6d. net.

Do. Thirty-three Plates. Folio. Cloth. 10s. 6d. net.

ARCHÆOLOGICAL WORKS—*continued.*

Prof. F. Maspero. Manual of Egyptian Archæology.

A Popular Guide to the Egyptian Antiquities for Students and Travellers.

Chapter I. CIVIL AND MILITARY ARCHITECTURE.

„ II. RELIGIOUS ARCHITECTURE.

„ III. TOMBS.

„ IV. PAINTING AND SCULPTURE.

„ V. THE INDUSTRIAL ARTS.

Translated by AMELIA B. EDWARDS, Ph.D., LL.D. With 336 Illustrations. 5th Edition, augmented and revised. Crown 8vo. Cloth, 6s.

“It is a marvel of erudition and condensation. It sums up the long results of thousands of years of Egyptian civilisation in language precise enough to make the work a handbook for the specialist, and popular enough to insure its becoming a guide to the antiquarian lore of the country for travellers in Egypt.”—*Scotsman.*

Pierre Paris. Manual of Ancient Sculpture.

Translated and augmented by JANE E. HARRISON, Author of “Myths of the Odyssey,” “Introductory Studies in Greek Art,” etc. With 187 Illustrations. Crown 8vo. Cloth extra, gilt top. 10s. 6d.

“M. Paris' admirable manual gives us within the narrow compass a lucid and compendious survey of the sculpture of the ancient world.”—*St James's Gazette.*

Prof. A. Wiedemann. The Ancient Egyptian Doctrine of the Immortality of the Soul.

With 21 Illustrations. Crown 8vo. Cloth. 3s.

“Prof. Wiedemann's treatise is quite a perfect thing of its kind. He treats his fascinating subject with marvellous clearness, and the reader follows his guidance through the mazes of the great system of immortality with breathless interest.”—*Saturday Review.*

“Prof. Wiedemann's little book appeals not only to the Egyptologist, but also to the student of religion and history, as well as to that larger public which is interested in all that relates to the thoughts and beliefs of civilized men, when set forth in lucid language by a skilful and learned interpreter.”—*Academy.*

ARHÆOLOGICAL WORKS—*continued.*

Prof. A. Wiedemann. The Religion of the Ancient Egyptians.

With 73 Illustrations from the Monuments. Demy 8vo. Cloth. 12s. 6d.

"Prof. Wiedemann's work evinces sound scholarship, and merits the attention of all who are interested in the study of the religions of the world."—*Morning Post.*

"We have no hesitation in saying that the volume before us is the most lucid and thorough monograph in English on the religion of the Egyptians as disclosed by the monuments."—*Guardian.*

CHEMISTRY AND ENGINEERING WORKS.

Carl Busley. The Marine Steam Engine. Its Construction, Action and Management.

Translated by H. A. B. COLE, Member of the Institution of Naval Architects. Third Edition, revised and enlarged. Vol. I., complete, with Atlas of 63 Plates containing over 1,500 Drawings and Diagrams. 8vo. Cloth. 1892-1902. £2 net.

Paul Heyne. Practical Dictionary of Electrical Engineering and Chemistry.

In the German, English, and Spanish Languages, treating specially of Modern Machine Industry, the Foundry, and Metallurgy. 3 Vols. 8vo. Cloth. 15s.

Also separately:—

Vol. I. GERMAN-ENGLISH-SPANISH. 5s.

„ II. ENGLISH-SPANISH-GERMAN. 5s.

„ III. SPANISH-GERMAN-ENGLISH. 5s.

Prof. Dr. Lassar-Cohn. Chemistry in Daily Life.

Translated into English by M. M. PATTISON MUIR, M.A., Fellow of Gonville and Caius College, Cambridge. With 22 Illustrations. Third Edition, revised and augmented. Crown 8vo. Cloth. 5s.

"We like this book, and every page proves to be interesting reading."—*Lancet.*
"The variety of matter with which the author deals is amazing."—*Daily Chronicle.*

"A work of this kind, in our opinion, may be credited with an educational value of no ordinary nature."—*Glasgow Herald.*

CHEMISTRY AND ENGINEERING WORKS—*continued.*

Prof. Dr. Lassar-Cohn. Introduction to Modern Scientific Chemistry.

Translated from the Second German Edition by M. M. PATTISON MUIR, M.A., Fellow of Gonville and Caius College, Cambridge. With 58 Illustrations by the Author. New Edition. Crown 8vo. Cloth. 3s. 6d.

"Prof. Lassar-Cohn's Introduction to Modern Scientific Chemistry is a delightful book, clearly and well written. It is intended to be both scientific and popular."—*British Medical Journal.*

"We would particularly recommend the book to those who have been discouraged by the forbidding aspect of the average chemistry textbook."—*Mechanical World.*

"It covers in a series of clear and interesting lectures the initiatory doctrines of scientific chemistry, and is distinguished among books for its success in making the subject attractive to readers not specially covenanted to this study."—*Scotsman.*

Prof. Dr. Robt. Lüpke. The Elements of Electro-Chemistry.

Second Edition, revised and enlarged, by M. M. PATTISON MUIR, M.A., Fellow and Lecturer of Gonville and Caius College, Cambridge. With 64 Illustrations in the Text. Demy 8vo. Cloth. 7s. 6d.

"The book is laid out with great skill and care, and arranged with the evident intention of putting together a connected account of recent progress in electro-chemistry."—*Electrician.*

GERMAN LANGUAGE.

Muret-Sanders' Encyclopædic Dictionary of the English and German Languages.

Unabridged Edition. 4 Vols. 4to. Half-calf. £4 4s.

Muret-Sanders' Encyclopædic Dictionary is the latest, largest, and by far the most comprehensive of all English-German Dictionaries, and specially adapted for the use of scientific and literary men. Used in all Government Offices.

Muret-Sanders' English-German and German-English Dictionary for Schools

and General Readers. Abridgment of the Encyclopædic Dictionary. In 2 Vols. Royal 8vo. Half-calf. 16s.

GERMAN LANGUAGE—*continued.***Muret-Sanders' English-German and German-English Pocket Dictionary.**

for quick Reference, the use of Travellers, and Conversation. Bound in 1 Vol. 16mo. Cloth. 3s. 6d.

William Eysenbach. Practical Grammar of the German Language.

With Reading Lessons and a German-English and English-German Vocabulary. New Edition. 8vo. Cloth. 3s. 6d.

Bismarck's Table Talk.

The Story of his Life in his own words. With Notes and an Introduction. Edited by CHARLES LOWE, M.A., author of "Prince Bismarck, an Historical Biography," etc. With Portrait. New and Cheaper Edition. Crown 8vo. Boards. 3s. 6d.

MUSICAL WORKS (WAGNER.)**Richard Wagner to Mathilde Wesendonck. Letters and Leaves from a Diary.**

With Portraits and Facsimiles. Translated by WILLIAM ASHTON ELLIS. Demy 8vo. Cloth extra. 16s. net.

"These letters are likely to create a sensation throughout the world. For the first time is one of the most remarkable chapters in Wagner's life—the genesis and completion of his *Tristan*—laid bare in its inmost recesses. Without this glimpse the picture of Wagner's life is incomplete."—*Kölnische Zeitung*.

"We are presiding over the creation of great works of art, seeing how they germinate in the artist's mind, observing how they are modified by subsequent thought and experience."—*Daily Telegraph*.

"Nothing more sincere, nothing more intimate was ever written than these letters and journals addressed to the woman who came into Wagner's life precisely when his genius required her, and dropped out of it precisely when his service was accomplished."—*Outlook*.

"Not even the letters to Liszt afford so intimate a picture of the poet-composer's inner life and the growth of his riper creations."—*Musical World*.

"As an example of the private and intimate correspondence of a great man, they will rank beside Goethe's Letters to Frau von Stein."—*Scotsman*.

"Of all Wagner books in existence, this book of letters should be the most popular with the musician, with the student of psychology of genius, and with the general reader."—*Fall Mall Gazette*.

MUSICAL WORKS (WAGNER)—*continued.*

Correspondence of Wagner and Liszt.

Translated into English, with a Preface by Dr. FRANCIS HUEFFER.
2 Vols. 8vo. Cloth, gilt top. £1 1s.

"Nothing more instructive with regard to the real character and relations of Liszt and Wagner has been published. Seldom have the force and fervour of Wagner's German been rendered with such accuracy and character in a strange tongue."—*Manchester Guardian.*

Richard Wagner's Letters to Otto Wesendonck et al.

Translated and Indexed by WM. ASHTON ELLIS. 16mo. Cloth, gilt top. 5s. net.

Letters of Richard Wagner to Emil Heckel.

With a Brief History of the Bayreuth Festivals Translated and Indexed by WM. ASHTON ELLIS. 16mo. Cloth, gilt top. 5s. net.

Letters to Franz Liszt.

Edited and Collected by LA MARA. Translated by CONSTANCE BACHE.

Vol. I.

Years of Travel as Virtuoso. With a Portrait.

Vol. II.

From Rome to the End. With a Frontispiece.

2 Vols. Crown 8vo. Cloth. £1 1s.

"Between six and seven hundred letters, every one of which is worth reading, are reproduced in this collection, and are lavishly supplemented by Chronological and Explanatory Notes, which render the book extremely valuable to musicians and men of letters as a work of reference. Its technical production, moreover, is in every respect exemplary."—*Daily Telegraph.*

MUSICAL WORKS (WAGNER)—*continued.*

Wagner and his Works.

The Story of his Life, with Critical Comments, by HENRY T. FINCK.
With Two Portraits. 2 Vols. Crown 8vo. Cloth. £1 1s.

"Mr. Finck's work is perhaps the most exhaustive and appreciative account of the great composer that has appeared in the English language."—*Times.*

J. E. Mathew. A Handbook of Musical History and Biography.

With 160 Illustrations of Portraits, Musical Instruments, Facsimiles of rare and curious Musical Works. Demy 8vo. Cloth. 10s. 6d.

"The author covers the entire ground of his subject from the time of St. Gregory to the present day, and serves admirably for those who wish to obtain some general idea as to the progress of the art. The facts are succinctly set forth, the statements are correct, and the many illustrations give the work a distinct value."—*Daily Telegraph.*

FENCING.

Capt. Alfred Hutton. The Swordsman.

A Manual of Fence for the Foil, Sabre, and Bayonet. With an Appendix consisting of a Code of Rules for Assaults, Competitions, etc. New Edition. With 42 Illustrations. Crown 8vo. Boards. 1s. 6d.

Capt. Alfred Hutton. Old Sword Play.

With 58 Illustrations, containing a Series of Studies of the Swordsmanship of the 16th, 17th, and 18th Centuries, embracing the Two-hand Sword, Rapier and Dagger, Broadsword and Buckler, "Case of Rapiers," Early Small Sword Play, etc. Superfine Dutch paper. (Limited to 300 Copies.) Royal 8vo. Buckram. £1 1s. net.

IN
OF
OF
IN
IN
IN

AS. B 11 m E

Manual of Oriental antiquities, inc

Tozzer Library

AWJ1991



3 2044 043 182 088